New Fence

Proposed Manege 40m x 20m

Double Gates

Manege Fence (See Detail)
1800 1800

Existing Hedge

New Fence

New Fence

Proposed Concrete Storage Yard 20m x 20m

New Access Road Suggested Construction

Remove vegitaion layer down to firm strata.
Base layer of 200mm well compacted 75mm hardcore blinded with 40mm down to dust crusher run

Plan

This drawing is not a contractual or construction specification. Please refer to indvidual contractors written specifications and details for contractual details.

All work must conform with Planning, Building Control and CDM Regulations. Dimensions to be checked on site prior to commencement of work.

REV	REVISION	DATE	BY

Ivan J. Cooper (Moorside) Ltd
Architectural and Engineering Design
Cauldon Lowe, Stoke on Trent, ST10 3ET.
Phone 01538 702738, Fax 702662.

CLIENT
M/s E. Coop

CONTRACT
Proposed Storage Yard, Manege & Access Road At: Ball Lane, Norton

TITLE
Menage and Concrete Storage Yard Plan

CONTRACT No *K Wainman Associates*
SCALES *1:100*
DATE *23/02/16* DRAWN *drc*
DRAWING NUMBER *3580-02*