Key: See Important Notes on 373/50.3/2

- Existing tree canopies and i/d. For detail & protection see Tree Heritage report
- Existing surfaces which do not change
- New block paving, to match existing, laid stretcher bond with V-joints down. On steps: Yorkstone treads.
- New tarmac surfaces
- Geogrid with grass infill to allow cherrypicker access.
- Porous tarmac as specified by engineer
- Resin bound surface on sub-base as specified by engineer
- New Turf 150mm topsoil
- Bulbs
- QR New mainly Indigenous planting of Shrubs and Trees. 500mm topsoil generally with 1m x 1m x1m at treepits.
- PT New Thematic planting of Shrubs and Trees. 500mm topsoil generally with 1m x 1m x1m at treepits.
- New Thematic Ground Covers & Climbers. 500mm topsoil
- New Thematic planting of Perennials. 500mm topsoil
- Garden Fence 1100 high
- Handrail 1100 high
- Knee rail 500 high for plant protection
- Chain link fence 1100 high
- Chain link fence 1800 high
- Close boarded fence 2400 high
- Armco barrier (see Engineer)
- Rock edge
- Rubble clad retention
- Rock retention (see Engineer)
- Soil retention (see Engineer)
- Sitting stone edge
- Erratic Stones
- Existing levels
- Proposed levels
- Extg Public Footpaths
- ATR Projected site wide paths

Site Levels shown are indicative only and for accurate construction levels please refer to latest revision of Engineer's Siteworks Drawings

See ATH Extension Planting Schedule for Keys and Quantities of Planting

All headwall concrete to be hidden by rubble stone

Sunken Garden

Yard

Extension Lower Ground Floor
SSL 156.25 (see TMP drawings)
Internal details for information only

Rev J 19.4.16 Steps from terrace omitted.
Rev H 8.4.16 Further changes as confirmed in EA note of 6.4.16.
Rev G 4.1.16 Fire path south of lake removed. Small pond removed. Armco barrier for erratics on service road. Sitting stones removed at entrance.
Rev F 2.1.16 Paving amended in parking bays and entrance circle.
Rev E 20.1.16 Armco barrier added along drop to Deer Wall and replaces Erratic stones around entrance roundabout, co-ordination with Engineers drawings. Landscape Keys added.
Rev D 1.12.15 Retention reduced at east turning head, rockwork reduced below spa terrace, garden cherrypicker geogrid reduced, fence extended at spa terrace, handrails added to steps and paths, minor changes to car park, planting detail & protection added, key updated.
Rev C 26.10.15 Road levels amended to reflect engineers drawings, Changes in paving and planting in sunken garden to reflect plan changes, new path added for treehouses, clear of mound.
Rev B 17.9.15 Road levels amended to reflect engineers drawings, additional detail on pond outflow shown with amendments.
Rev A 28.8.15 Retention to sunken garden reduced. Roundabout removed & 10 car spaces added. Parking spaces changed to Grasscrete.

NICHOLS BROWN WEBBER LLP
ARCHITECTS AND LANDSCAPE PLANNERS
POND HOUSE, NORTHEND, HENLEY-ON-THAMES, OXON RG9 6LG
TEL: +44 (0)1491 638 536 EMAIL: enquiries@nbwarchitects .co.uk

PROJECT
Alton Towers Resort/ Hotel Extension

DRAWING TITLE
Garden Plan as Proposed

PLOT DATE 1.12.15 | CHECKED

SCALE: 1/250 @ A1, 1/500 @ A3 | STATUS: S

PROJECT NO: **373/50.3** | DRAWING NO: **5** | REVISION: **J**