373/95/18 B SW8 Planting Schedule

Please read with NBW plan 373/95/8 for planting positions

12.5.16 **Amended 10.2.17**

Bat friendly species

New EHS Tree Planting (Indigenous & Park Trees)

1.0x1.0x0.75m treepit, ReRoot 600, 80L PAS 100 planting compost, Rootgrow Mycorrhiza, R/Rain UrbanRRURB2A irrigation, Aborguy SASMP, Broadleaf P4 polymer, Arborteck strimmer guard. Allow for supply & instal of ReRoot 600 to 25no trees planted in proximity to underground services. 75mm bark mulch.

In the following species in positions shown on plans



Key	Botanical name	Common name	%	Size	Cond	No
CB	Carpinus betulus	Hornbeam		16-18cm	cont	30
CD	Cedrus deodara	Deodar Cedar		1.75-2.0	cont	4
PS	Pinus sylvestris	Scots Pine		1.75-2.0	cont	13
QR	Quercus robur	Common Oak		16-18cm	cont	22
SG	Sequoiadendron giganteum	Wellingtonia		1.75-2.0	cont	17
SA	Sorbus aucuparia	Rowan		16-18cm	cont	8
TB	Taxus baccata	Yew		16-18cm	cont	3
						97

Mainly Indigenous Understorey Edge planting



0.6x0.6x0.6m treepit, 30L PAS 100 planting compost, Rootgrow mycorrhiza, Broadleaf P4 polymer, 1.2m x 32mm x 32mm tanalised stake, 600mm Green Tubex Shelterguard Tree shelters. 75mm bark mulch.

Planted at av. centres of **1.0** **m over** **1,130** sqm **gives** **1,130**

In the following species planted randomly in groups of 3, 5 & 7

Key	Botanical name	Common name	%	Size	Cond	No
	Acer campestre	Field Maple	5%	1.2-1.5	BR	57
	Carpinus betulus	Hornbeam	5%	1.2-1.5	BR	57
	Corylus avellana	Hazel	5%	1.2-1.5	BR	57
	Crataegus monogyna	Hawthorn	10%	1.2-1.5	BR	113
	Euonymus europaeus	Spindle Tree	10%	1.2-1.5	BR	113
	Pinus sylvestris	Scots Pine	10%	0.9-1.2	cont	113
	Prunus avium	Bird Cherry	5%	1.2-1.5	BR	57
	Prunus laurocerasus	Laurel	15%	0.9-1.2	cont	170
	Prunus lusitanica	Portugal Laurel	10%	0.9-1.2	cont	113
	Salix caprea	Goat Willow	10%	1.2-1.5	BR	113
	Sorbus aucuparia	Rowan	10%	1.2-1.5	BR	113
	Taxus baccata	Yew	5%	1.2-1.5	BR	57
			100%			

Mainly Indigenous Ground Cover Planting



0.3x0.3x0.3m planting pit, 10L PAS 100 planting compost, Rootgrow mycorrhiza, Broadleaf P4 polymer, any canes to be capped. 75mm bark mulch.

Planted at av. centres of **0.5** **m planted over** **265** sqm **gives** 1,060

In the following species in positions shown on plan

Planted in random groups of 3, 5 and 7

Botanical name	Common name	%	Size	Cond	No
Alium ursinum	Wild Garlic	20%	Pot or tray		212
Cotoneaster Integerrimus	Wild Cotoneaster	15%	3L	cont	159
Polypodium vulgare	Common Polypody	15%	3L	cont	159
Hedera helix Hibernica	Irish Ivy	15%	3L	cont	159
Hypericum calycinum	Rose of Sharon	10%	3L	cont	106
Ruscus aculeatus	Butcher's broom	10%	3L	cont	106
Vinca major	Greater Periwinkle	15%	3L	cont	159
		100%			

Wildflower Meadow Turf 2500 sqm

This only includes areas indicated on the plans. No allowance is made for other existing grassed areas which may need making good at the end of the contract.