

Rev.	Drawn	Comments	Date
------	-------	----------	------

New feature cross by specialist.

Feature canopy / roof by specialist——
with high performance single membrane
finish and standing seam profiles.

Remove extg. doors and install double glazed powder coated aluminium screen by specialist.

Form new opening for new —
feature double glazed window.

Exlg. ground floor level. _____

New facing brickwork to match extg:

Line of extg. pavement.

Replace single glazed ribbon windows with double glazed white PVC uPVC windows (to be agreed.)
to implement to be agreed.)

Remove exit doors and install aluminium screen by specialist to form entrance.

New double glazed electrically operated bi-fold doors to open out. (Connected to the alarm system) to full size in open position.)

Level threshold for wheelchair access to detail.

- Remove extg. doors and install double glazed powder coated aluminium screen by specialist to form entrance.

—New double glazed electrically operated bi-fold doors to open out. (Connected to fire alarm installation and to fail safe in open position.)

to detail.

eslido del municipal access

[illegible]

Feature canopy / roof by specialist — with high performance single membrane finish and standing seam profiles.

New double glazed electrically operated bi-fold doors to open out. (Connected to fire alarm installation and to fall safe in open position.)

Extg. ground floor level.

Level threshold for wheelchair access to detail.

New facing brickwork to match extg.

Position of exit, window dotted.

Form new day opening in exit, external wall for means of escape. Make good exit, brick.

Position of extg. window dotted

Form new door opening in extg. external wall for means of escape. Make good extg. bkwk.

Cheadle Methodist Church, ST10 1EE

Project

Proposed alterations to create first floor.

Revised scheme proposal.

Elevation to Chapel St. & Side Elevation.

Status CONSTRUCTION

Date Jan 2017

SM
Drawn

Scale 1:50

Checked

Project No. Drawing No.