Clarke Equine Services
3 Llewelyn Road
Colwyn Bay
Cony
LL29 7AP
Tel: 07748 970174
E mail: jamestclarke1@outlook,com

RECD 5 JAN 2018

Ref: Mr Pountney, Conditions discharge application DOC/2017/0078 in relation to Planning Permission SMD/2017/0325 for horse exercise arena".

Dear Mr Johnston

We would like to confirm that we would carry a landscaping scheme on completion of ménage build, turf would be laid to land surrounding menage and a planting scheme would be carried out as set below.

**Planting Scheme**

Hedging plants to be 60-80cm high bare root, planted in staggered rows 450mm apart, seven plants per lin metre., to be protected with 400mm high plastic guards supported with 750mm stake. Stock proof fencing would be erected to protect the landscaping scheme. All dead or diseased or damaged plants would be replaced as and when required.

**Species mix:**

30% Hawthorn ( Crataagus Monogyna) , 20% Hazel ( Corylus Avellana), 20% Blackthorn ( Ptunus Spinosa) , 10% Dogwood ( Cornus Sanguinea) , 10% Mple (Acer Campestre) , 10% Holly ( Ilex Aquifolium) Also additional climbers/shrubs would be planted one plant every 19 mteres to enhance wildlife.

If you require any further information please contact me at anytime.

Regards

Gayle Clarke