JOB No	DRG No	REV
5307	205	03

FOR DETAILS OF PROPOSED CURRENT DIVERSION SEE DRAWING 5307-200

SCHOOL — KEEP — CLEAR

ALLEY LANE

SUGAR STREET

Plot 1 FFL 165.900
Plot 2 FFL 164.650
Plot 3 FFL 164.650
Plot 4 FFL 163.375
Plot 5 FFL 163.050
Plot 6 FFL 163.375
Plot 7 FFL 165.000
Plot 8 FFL 165.450
Plot 9 FFL 165.450
Plot 10 FFL 165.990

FFL 163.200
FFL 163.500
FFL 163.300
FFL 165.325

PACKAGED TREATMENT PLANT

PS

Proposed culvert diversion
CL 164.85
IL 163.88

Approx. line of existing culvert to be abandoned

Existing filter chambers to be made redundant. Flows diverted to new Sewage Treatment Plant via new foul drainage as shown

Slab for above ground kiosks

PACKAGED TREATMENT PLANT BY WPL OR SIMILAR APPROVED

STORAGE MANHOLE
CL 163.60
IL 160.73

WL=160.63

PACKAGED PUMPING STATION TO DISCHARGE AT A RATE OF 15L/S (TBC) AT A HEAD OF 3.20m (TBC)
CL 163.60
IL 160.70 INCOMING (ø150) FROM PLANT
IL 160.10 SUMP
IL 162.70 OUTGOING (RISING-MAIN)
IL 160.70 (ø150) INCOMING FROM TANK

No.1 & No. 2 Marsh Cottages
Properties have an existing consent to discharge effluent from septic tanks into the feeder channel

Existing C&RT Feeder Channel

CD1 CL 166.00 IL 165.40 *
CD2 CL 165.71 IL 161.21 *
CD3 CL 165.14 IL 163.81
CD4 CL 164.80 IL 163.49
CD5 CL 163.67 IL 163.15 *
CD6 CL 163.51 IL 163.01 *

LEGEND

- Proposed Surface Water Sewer & MH (Adopted)
- Proposed Foul Sewer & Manhole (Adopted)
- Proposed Surface Water Sewer & MH (Private)
- Existing Foul Sewer & Manhole (Private)
- Existing Sewer to be abandoned
- Existing Manhole to be abandoned
- S1.01 — New Surface Water Sewer and Reference
- F1.01 — New Foul/Combined Sewer and Reference
- SIC1 — New Surface Water Inspection Chamber and Reference (Private)
- RE1 — New SW Rodding Eye
- FIC1 — New Foul Inspection Chamber and Reference (Private)
- ACO — ACO Drain
- Backdrop
- Rising main
- G1 SD — New Highway Gully / Threshold Slot Drain

NOTES

1. All dimensions in metres unless noted otherwise.
2. All levels in metres unless noted othewise.
3. Proposed private drainage subject to the approval of Building Control.
4. Proposed private sewers designed generally in accordance with the requirements set out in "Sewers for Adoption" 7th Edition.
5. A Section 104 application to adopt the sewers must be made to United Utilities.
6. All proposed levels to be checked and confirmed on site by the contractor prior to commencement of works. Any discrepancies to be reported to the engineer immediately. All downstream levels to be checked and confirmed by the contractor prior to construction of any upstream drainage.
7. All proposed cover levels to be checked against proposed final finished surface levels and adjusted to suit on site (see also Architects drawings).
8. All inspection chambers shown to be 450mmø minimum for access and maintenance purposes.
9. All manholes to be 1200mmø dia unless noted otherwise.
10. Refer to architects drawings for all domestic foul & SW drainage connection positions around and within buildings.
11. Materials should comply with requirements of part E sections E2.21 and E2.22 of SfA7.
12. All pipes to be plastic in accordance with SFA 7th Edition Part E and note 12 above. Pipe entry and exit through walls to be in accordance with Approved Document H of Building Regulations 2010 paragraphs H 2.23, 2.24 and Diagram 7.
13. Class Z concrete bedding required where cover <1.2m in the carriageway and <900mm in private shared access roads and <350mm in private gardens and pathways. Compressible filler required at all joints throughout depth of concrete surround, Class S bedding elsewhere.
14. For highway drains Class Z bedding required for pipes <900mm cover, crown to surface.
15. ACO Drains to be M100D with sump units and trapped roddable outlet.
16. Covers to inspection chambers around buildings to be minimum B125 and D400 in all trafficked / car park areas.
17. All foul pipes to be 100mmø unless otherwise stated.
18. All surface water pipes to be 150mmø unless otherwise stated.
19. All foul pipes to have a minimum gradient of 1:40 (underslab) and 1:80 elsewhere, except as noted otherwise.
20. All SW pipes to have minimum gradient of 1:150 unless noted otherwise.
21. For details of surface water drainage refer to RBA drawing 5307/206.

Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationery Office © Crown Copyright Richard Broun Associates Colwyn Bay Licence No: AR 0100027961

REV	DATE	NATURE OF REVISION	BY	CHECKED
03	03/01/17	FOR APPROVAL - TELEMETRY KIOSKS SHOWN	JME	DE
02	03/01/17	FOR APPROVAL - DRAINAGE COMPOUND REVISED TO SUIT LANDSCAPE ARCHITECTS COMMENTS	JME	DE

DO NOT SCALE THIS DRAWING. THIS DRAWING IS COPYRIGHT. CONTRACTORS MUST CHECK ALL DIMENSIONS ON SITE. ARCHITECT / ENGINEER TO BE NOTIFIED OF ANY DISCREPANCIES.

Engineering Consultancy
RBA Ltd, 26 Mostyn Road, Colwyn Bay, Conwy LL29 8PB
01492 533117 admin@rba.ltd.uk www.rba.ltd.uk

CLIENT: BERNEL LTD

PROJECT: DEVELOPMENT ON LAND AT SUGAR STREET, RUSHTON SPENCER

DRAWING: PROPOSED FOUL DRAINAGE GA

SCALE	SIZE	DRAWN	CHKD	DATE	JOB	DRG	REV
1:200	A1	JME	DE	12.12.17	5307	205	03