STATEMENT OF SIGNIFICANCE & IMPACT: ASSESSMENT TABLE

Proposed Works (*item by item*):	Significance of the historic fabric/area that will be affected:	The impact of the proposed work(s) on the historic fabric/area:
Underpinning of single story stone detached building at Cheddleton Flint Mill. ***11 Heli piles to a depth of 5 metres.***	***Inspection of the building by structural engineers showed that the left hand corner of the building had been subject to long term differential settlement. The end wall is bowing out and cracks are appearing in the front of the building.***	The underpinning will stabilise the building and prevent it from falling down. There will be no visible impact once the works have been completed as the piles are underground and no trace will be seen on the surface.