



Key

- SITE BOUNDARY
- PROPOSED ORNAMENTAL SHRUBS:
Species to be planted at a density of 3 Plants/M²
See Schedule on Drawing PP01.00
- PROPOSED ORNAMENTAL HEDGE:
Evergreen species
See Schedule on Drawing PP01.00
- PROPOSED NATIVE HEDGE:
To be planted in a double staggered row at 5 plants/Lin M
See Schedule on Drawing PP01.00
- EXISTING VEGETATION TO BE RETAINED:
- TURFED GRASS AREAS:
Amenity Grade Turf to be laid on min. 150mm depth of topsoil
- GRASSLANDS WITH WILD FLOWER PLANTING:
See Schedule on Drawing PP01.00
- Native Fruit Mix:
See Schedule on Drawing PP01.00
- MARGINAL PLANTING:
See Schedule on Drawing PP01.00
- REMOVED TREES
- PROPOSED TREES
Proposed species list below.
See Schedule on Drawing PP01.00
- PROPOSED TIMBER FENCE
TO EDGE OF ECOLOGICAL AREA

Tree Species

Ace	Acer campestre 'Streetwise'
Bp	Betula pendula
Cb	Carpinus betulus
Cf	Carpinus betulus 'Frans Fontaine'
Ms	Malus sylvestris
Pa	Prunus avium
Qr	Quercus robur
Sx	Salix alba
Tc	Tilia cordata

A	19-01-18	PLANTING UPDATE	HS
	04-01-18	PLANTING LAYOUT	HS
Rev	Date	Description	Initials

LANDSCAPE ARCHITECTS

PGLA Ltd
Landscape Architects
229 Ducie House
Ducie Street
Manchester
M1 2JW

t: 0161 238 9138
e: info@pgla.co.uk
w: www.pgla.co.uk

Client
KEYWORKER HOMES

Project
BIDDULPH FORGE WORKS

Description
**LANDSCAPE PLAN
PLANTING PLAN**

Status
PLANNING

Scale
1:200 @ A1

Drawn
HS

Date
JAN 2018

Job number
BID1210_

Drawing number
PP01.1

Revision
A

Original size 100mm @ A1