

**BS5837 Survey Work Analysis**

Tree: 1	Priority: 1 Year	Actions Required:		Hours	Done
Turkey Oak <i>Quercus cerris</i>		Fell	Fell and remove stump(s)	04:30	No
Tree Comment:				Total for Tree	04:30
Survey Comment: Suppressed tree with heavily asymmetric crown. Historic failure of large branch at 8m. Also previously heavily pruned.					
Tree: 2	Priority: 1 Year	Actions Required:		Hours	Done
Sycamore <i>Acer pseudoplatanus</i>		See Comment	Unspecified	02:00	No
Tree Comment:				Total for Tree	02:00
Survey Comment: Multistemmed with tight unions. Remove deadwood. Tidy stubs.					
Tree: 3	Priority: 1 Year	Actions Required:		Hours	Done
Common Ash <i>Fraxinus excelsior</i>		See Comment	Unspecified	03:00	No
Tree Comment:				Total for Tree	03:00
Survey Comment: Retaining wall immediately to the E. Forms joint crown with adjacent trees. Major and minor deadwood throughout crown. Remove all deadwood.					
Tree: 4	Priority: N/A	Actions Required:		Hours	Done
Whitebeam <i>Sorbus aria</i>		No action	Unspecified		No
Tree Comment:				Total for Tree	
Survey Comment: Forms joint crown with adjacent tree.					

BS5837 Survey Work Analysis

Tree: 5	Priority: N/A	Actions Required:	Hours	Done
Common Oak <i>Quercus robur</i>		No action Unspecified		No
Tree Comment:			Total for Tree	
Survey Comment: Boundary tree. Partially rooted in wall, with steep drop to N & W. High crown.				
Tree: 6	Priority: 1 Year	Actions Required:	Hours	Done
Common Hazel <i>Corylus avellana</i>		Coppice To 0.5m stumps	03:00	No
Tree Comment:			Total for Tree	03:00
Survey Comment: Boundary tree.				
Tree: 7	Priority: N/A	Actions Required:	Hours	Done
Common Hawthorn <i>Crataegus monogyna</i>		No action Unspecified		No
Tree Comment:			Total for Tree	
Survey Comment: Boundary tree. High crown.				
Tree: 8	Priority: 1 Year	Actions Required:	Hours	Done
Common Hawthorn <i>Crataegus monogyna</i>		See Comment Unspecified	00:30	No
Tree Comment:			Total for Tree	00:30
Survey Comment: Ivy covers stem and crown. Adjacent tree hung up in crown. Full inspection not possible. Re-assess condition once adjacent tree removed. Sever ivy.				
Tree: 9	Priority: 6 Months	Actions Required:	Hours	Done
Common Ash <i>Fraxinus excelsior</i>		Fell Fell to ground level	03:00	No
Tree Comment:			Total for Tree	03:00
Survey Comment: Windthrown dead stem, hung up in adjacent hawthorn. Fell. Prune adjacent hawthorn if necessary.				

BS5837 Survey Work Analysis

Tree: 10	Priority: N/A	Actions Required:	Hours	Done
A Hedgerow - <i>Unknown</i>		No action Unspecified		No
Tree Comment:			Total for Tree	
Survey Comment: Boundary hedgerow consisting of hawthorn, holly, hazel, elder.				
Tree: 11	Priority: N/A	Actions Required:	Hours	Done
Crack Willow <i>Salix fragilis</i>		No action Unspecified		No
Tree Comment:			Total for Tree	
Survey Comment: Boundary tree. Multistemmed with tight unions. Forms joint crown with adjacent willow. Minor deadwood throughout.				
Tree: 12	Priority: N/A	Actions Required:	Hours	Done
Crack Willow <i>Salix fragilis</i>		No action Unspecified		No
Tree Comment:			Total for Tree	
Survey Comment: Boundary tree. Multistemmed with tight unions. Forms joint crown with adjacent willow. Minor deadwood throughout.				
Tree: 13	Priority: 6 Months	Actions Required:	Hours	Done
Crack Willow <i>Salix fragilis</i>		See Comment Unspecified	05:00	No
Tree Comment:			Total for Tree	05:00
Survey Comment: Extensive material stored on RPA. Extensive mechanical damage to base of main stem. Multistemmed with tight unions and included bark. Historic failure of large limbs. Remove materials from RPA. (not included in quoted hours) Pollard at approximately 2m. Option to fell and replant.				
Tree: 14	Priority: N/A	Actions Required:	Hours	Done
A Group - -		No action Unspecified		No
Tree Comment:			Total for Tree	
Survey Comment: Group of young trees on quarry edge. Consisting of birch, oak, hawthorn. No apparent significant defects.				

BS5837 Survey Work Analysis

Tree: 15	Priority: 1 Year	Actions Required:	Hours	Done
Crack Willow				
<i>Salix fragilis</i>		See Comment Unspecified	03:00	No
Tree Comment:			Total for Tree	03:00
Survey Comment: Extensive material stored on RPA. Extensive mechanical damage to base of main stem. Multistemmed with tight unions and included bark. Historic failure of large limbs. Remove materials from RPA. (not included in quoted hours) Pollard at approximately 2m. Option to fell and replant.				
Tree: 16	Priority: 1 Year	Actions Required:	Hours	Done
Crack Willow				
<i>Salix fragilis</i>		See Comment Unspecified	02:00	No
Tree Comment:			Total for Tree	02:00
Survey Comment: Extensive material stored on RPA. Extensive mechanical damage to base of main stem. Multistemmed with tight unions and included bark. Historic failure of large limbs. Remove materials from RPA. (not included in quoted hours) Pollard at approximately 2m. Option to fell and replant.				
Tree: 17	Priority: 6 Months	Actions Required:	Hours	Done
Crack Willow				
<i>Salix fragilis</i>		See Comment Unspecified	02:00	No
Tree Comment:			Total for Tree	02:00
Survey Comment: Extensive material stored on RPA. Extensive mechanical damage to base of main stem. Multistemmed with tight unions and included bark. Historic failure of large limbs. Remove materials from RPA. (not included in quoted hours) Pollard at approximately 2m. Option to fell and replant.				
Tree: 18	Priority: 6 Months	Actions Required:	Hours	Done
Crack Willow				
<i>Salix fragilis</i>		See Comment Unspecified	02:00	No
Tree Comment:			Total for Tree	02:00
Survey Comment: Extensive material stored on RPA. Extensive mechanical damage to base of main stem. Multistemmed with tight unions and included bark. Historic failure of large limbs. Remove materials from RPA. (not included in quoted hours) Pollard at approximately 2m. Option to fell and replant.				

BS5837 Survey Work Analysis

Tree: 19	Priority: 1 Year	Actions Required:	Hours	Done
Crack Willow <i>Salix fragilis</i>		See Comment Unspecified	02:00	No
Tree Comment:			Total for Tree	02:00
Survey Comment: Extensive material stored on RPA. Extensive mechanical damage to base of main stem. Multistemmed with tight unions and included bark. Historic failure of large limbs. Remove materials from RPA. (not included in quoted hours) Pollard at approximately 2m. Option to fell and replant.				
Tree: 20	Priority: 1 Year	Actions Required:	Hours	Done
Crack Willow <i>Salix fragilis</i>		See Comment Unspecified	03:00	No
Tree Comment:			Total for Tree	03:00
Survey Comment: Extensive material stored on RPA. Extensive mechanical damage to base of main stem. Multistemmed with tight unions and included bark. Historic failure of large limbs. Remove materials from RPA. (not included in quoted hours) Pollard at approximately 2m. Option to fell and replant.				
Tree: 21	Priority: N/A	Actions Required:	Hours	Done
Sycamore <i>Acer pseudoplatanus</i>		No action Unspecified		No
Tree Comment:			Total for Tree	
Survey Comment: Material stored on RPA.				
Tree: 22	Priority: N/A	Actions Required:	Hours	Done
Crack Willow <i>Salix fragilis</i>		No action Unspecified		No
Tree Comment:			Total for Tree	
Survey Comment: Tree on quarry edge. Extensive mechanical damage to main stem.				

BS5837 Survey Work Analysis

Tree: 23	Priority: 6 Months	Actions Required:	Hours	Done
Crack Willow <i>Salix fragilis</i>		See Comment	Unspecified	02:00
Tree Comment:			Total for Tree	02:00
Survey Comment: Extensive material stored on RPA. Extensive mechanical damage to base of main stem. Multistemmed with tight unions and included bark. Historic failure of large limbs. Remove materials from RPA. (not included in quoted hours) Pollard at approximately 2m. Option to fell and replant.				
Tree: 24	Priority: N/A	Actions Required:	Hours	Done
Sycamore <i>Acer pseudoplatanus</i>		No action	Unspecified	No
Tree Comment:			Total for Tree	
Survey Comment: Boundary tree, anchored on steep bank on edge of quarry.				
Tree: 25	Priority: Over 2 Years	Actions Required:	Hours	Done
A Hedgerow - <i>Unknown</i>		See Comment	Unspecified	No
Tree Comment:			Total for Tree	
Survey Comment: Boundary hedgerow consisting of willow, hazel, holly. Long term consider coppicing hazel, and pruning / thinning the holly as required.				
Tree: 26	Priority: N/A	Actions Required:	Hours	Done
Sycamore <i>Acer pseudoplatanus</i>		No action	Unspecified	No
Tree Comment:			Total for Tree	
Survey Comment: Boundary tree. Partially suppressed by adjacent oak. Asymmetric crown. Materials stored on RPA. Historic pruning wounds. Minor cavities.				

BS5837 Survey Work Analysis

Tree: 27	Priority: 1 Year	Actions Required:	Hours	Done
Common Oak <i>Quercus robur</i>		See Comment Unspecified	02:00	No
Tree Comment:			Total for Tree	02:00
Survey Comment: Boundary tree. Fine form. Minor deadwood throughout. Mechanical damage to low hanging branches to the E. Crown lift to clear 4m to the E, including target pruning of damaged branches.				
Tree: 28	Priority: N/A	Actions Required:	Hours	Done
Common Oak <i>Quercus robur</i>		No action Unspecified		No
Tree Comment:			Total for Tree	
Survey Comment: Boundary tree. Poorly visible through dense holly understorey. Little low crown. Minor deadwood throughout.				
Tree: 29	Priority: 6 Months	Actions Required:	Hours	Done
Crack Willow <i>Salix fragilis</i>		See Comment Unspecified	04:00	No
Tree Comment:			Total for Tree	04:00
Survey Comment: Material stored on RPA. Multistemmed with tight unions and included bark. Heavily asymmetric crown. Historic failure of large limbs. Recent hard pruning of large low limbs to the E. Pollard at approximately 2m. Option to fell and replant.				
Tree: 30	Priority: 6 Months	Actions Required:	Hours	Done
Crack Willow <i>Salix fragilis</i>		See Comment Unspecified	02:00	No
Tree Comment:			Total for Tree	02:00
Survey Comment: Material stored on RPA. Heavily asymmetric crown. Exposed to increased and unaccustomed wind loading once adjacent tree pollarded. Pollard at approximately 2m. Option to fell and replant.				
Tree: 31	Priority: N/A	Actions Required:	Hours	Done
A Hedgerow - <i>Unknown</i>		No action Unspecified		No
Tree Comment:			Total for Tree	
Survey Comment: Boundary hedge. Consisting exclusively of young leyland cypress. Well maintained and forms screen with adjacent property.				

Report selection criteria.

Projects.

Hollington Stone Quarry

Date Range.

Any Date

Work types.

----> Coppice :: To 0.5m stumps
----> Fell :: Fell and remove stump(s)
----> Fell :: Fell to ground level
----> No action :: Unspecified
----> See Comment :: Unspecified

Latest Survey.

All surveys for the selected trees.
---> Last survey for each selected tree.

Work Completed.

---> Work Completed
---> Work Not Completed

Number of trees in selected Project(s) 31

Number of trees in Report selection 31