

Proposed Side Elevation



Proposed Rear Elevation



Proposed Part Front Elevation

Materials Specification.

Roof Covering
Natural Slate to Match Existing but Set at a Pitch of 45 Degrees

External Walls
Masonry to be Coursed Stone to Match Existing
Cills to be 140mm Deep Art Stone Cills
Timber Framework to be Oak Frame.

Windows
Oak Stained Hardwood Windows and Doors.

Rainwater Goods
Black Pvc Half Round Section Gutters.
Black Pvc Round Section Downpipes.

Fascias, Soffits, Barge Boards, Dentils Etc.
Oak Stained Hardwood

Note:
Extent of proposed extension indicated by hatched masonry to walls.

Any glazing within windows below 800mm, from floor level to be in toughened laminate glazing.
Any glazing within doors below 1500mm, from floor level to be in toughened laminate glazing.

RJB

A Member of The Chartered Institute of Architects Technologists
Unit 10C, Quays Reach, Trafford Way, Off South Langworthy Road,
Salford Quays, Salford. M50 2XY
Tel / Fax 0161 737 8253 Mobile 07711 068526
e-mail address - mail@rjbarchitectural-designs.com

Client
Mr M. Ball

Project
Extension to
Spite Hall
Lake Road
Rudyard

Subject
Proposed Part Elevations

Date	Scale	Drawn	Rev
01/10	1:50		

Drawing Number 10395/ 04

RJB Architectural Designs take no responsibility for any dimensions obtained by scaling from this drawing. If no dimension is shown the recipient must ascertain the dimension specifically from RJB Architectural Designs. Supplying this drawing in digital form is solely for convenience and no reliance may be placed on digital data. All data must be checked against hard copy. Dimensions must be checked on site. Any discrepancies must be reported to RJB Architectural Designs immediately. This drawing is copyright of RJB Architectural Designs.