SCALE 1:50

0m 1m 2m 3m 4m 5m

TAPERED KERB.

NEW DROPPED KERB CROSSING.

TAPERED KERB

NEW 5.00M WIDE TARMAC PAVED VEHICLE CROSSING IN ACCORDANCE WITH STAFFS COUNTY COUNCIL SPECIFICATION.

EXISTING GRASS VERGE

EXISTING FOOTPATH

EXISTING GRASS VERGE

BOUNDARY

NEW BRICKWORK GATE PILLARS.

EXISTING HEDGEROW

PLAN ON NEW GATEWAY

TARMAC PAVED ENTRANCE AREA.

5.00M SET BACK TO GATES.

215MM THK BRICKWORK WALL BUILT TO 1500MM HIGH WITH ART. STONE COPINGS. TO EACH SIDE OF DRIVEWAY ENTRANCE

NEW TIMBER GATES INWARD OPENING.

NEW BRICKWORK GATE PILLARS.

5.00M.

DRIVEWAY.

NEW 1800MM HIGH X 5000MM WIDE GATEWAY WITH TIMBER GATES TO OPENING.

NEW RED FACING BRICKWORK GATE PILLARS WITH ART. STONE COPINGS

EXISTING MIXED SPECIES HEDGEROW CUT BACK EACH SIDE OF NEW ACCESS.

ELEVATION TO UTTOXETER ROAD

PROPOSED NEW VEHICLE ACCESS AT 32 UTTOXETER ROAD, DRAYCOTT, STAFFS, ST11 9NR FOR MRS. P. A. MARSDEN

'A' REVISED IN ACCORDANCE WITH PLANNING OFFICER REQUIREMENTS 17/10/2014.

PLAN SCALE 1:50 AT A3.
AUGUST 2014

HARRISON WOOD
Architecture + Construction Consultancy
Structural Design Services
Martin A. Levie
BA(Hons)Arch. ICIOB. FIPD. FFB.

Unit 3, Studio 2, Silverdale Enterprise Park
Kents Lane, Silverdale,
Newcastle-under-Lyme, Staffs, ST5 6SR.

Tele : 01782 - 312630 / 711144
Mob : 07970-308358
E : harrisonwood.consult@gmail.com
Property Consultant and Registered Building Expert Witness