3590 CLOUD HOUSE FARM

WINDOW SCHEDULE_REVISION B

REF	LOCATION	NOTES
WG.01	Farm Office	**Replacement** stone mullion window: 5No fixed double glazed units. 1No side hung metal frame casement unit (6 units total) See detail drawing 3590_30_01
WG.02	Sitting Room	Existing stone mullion window: 10No fixed double glazed units. 1No fixed double glazed unit with glazing bar. 1No side hung metal frame casement unit (12 units total) See detail drawing 3590_30_01
WG.03	Family Room	Existing stone mullion window (and adjacent door): 2 No fixed double glazed units. (2 units total) See detail drawing 3590_30_01
WG.04	Family Room	Existing stone mullion window: 4No fixed double glazed units. 5No fixed double glazed unit with glazing bar. 1No side hung metal frame casement unit (10 units total) See detail drawing 3590_30_01
WG.05	Family Room	Existing stone mullion window: 6No fixed double glazed units. 1No side hung metal frame casement unit (8 units total) See detail drawing 3590_30_01

REF	LOCATION	NOTES
WG.06	Family Room	Existing opening in external stone wall: 1No fixed double glazed unit with glazing bar. See detail drawing 3590_30_01
WG.07	Utility	Existing stone mullion window: 2No fixed double glazed units. 1No side hung metal frame casement unit (3 units total) See detail drawing 3590_30_01
WG.08	Kitchen	Aluminium framed sliding doors with fixed light above See detail drawing 3590_32_01
WG.09	Kitchen	Aluminium framed casement window. Aluminium stub cill. Catnic lintel with stone coursing (no stone head) See detail drawing 3590_31_01
WG.10	Dining	Aluminium framed sliding doors. Steel lintel to structural engineers design – zinc flashing. See detail drawing 3590_32_01
WG.11	Dining	Structural glazed link
WG.12	Staff Boot Room	Aluminium framed casement window. Aluminium stub cill. Catnic lintel with stone coursing (no stone head) See detail drawing 3590_31_01
WG.13	Staff Boot Room	Aluminium framed casement window. Aluminium stub cill. Catnic lintel with stone coursing (no stone head) See detail drawing 3590_31_01
WG.14	Dining (Internal)	Existing stone mullion window: 2No fixed double glazed units. (2 units total) **Glass to be opaque – equivalent to Pilkington Optifloat Opal Privacy Level 5** See detail drawing 3590_30_01

REF	LOCATION	NOTES
WG.15	Kitchen (Internal)	Existing stone mullion window: 1No fixed double glazed unit. (1 units total) See detail drawing 3590_30_01
W1.01	Bedroom 4	Existing stone mullion window: 3No fixed double glazed units. 2No fixed double glazed unit with glazing bar. 1No side hung metal frame casement unit with glazing bar (6 units total) See detail drawing 3590_30_01
W1.02	Landing	Existing stone mullion window: 9No fixed double glazed units. **1No fixed double glazed unit, of which one pane to be original retained glass of historic value.** 2No side hung metal frame casement unit (12 units total) See detail drawing 3590_30_01
W1.03	Bedroom 1	Existing stone mullion window: 9No fixed double glazed units. 1No side hung metal frame casement unit (10 units total) See detail drawing 3590_30_01
W1.04	Bedroom 1	Existing stone mullion window: 4No fixed double glazed units. 3No fixed double glazed unit with glazing bar. 1No side hung metal frame casement unit (8 units total) See detail drawing 3590_30_01

REF	LOCATION	NOTES
W1.05	Bedroom 2	Existing stone mullion window: 3No fixed double glazed units. 1No fixed double glazed unit with glazing bar. **1No side hung metal frame double casement unit to serve as emergency egress. To incorporate large stiles to give appearance of mullion.** (5 units total) See detail drawing 3590_30_01
W1.06	Bedroom 2	Existing stone mullion window: 3No fixed double glazed units. 1No side hung metal frame casement unit (4 units total) See detail drawing 3590_30_01
W1.07	Bathroom	Existing stone mullion window: 1No fixed double glazed units. 1No side hung metal frame casement unit (2 units total) See detail drawing 3590_30_01
W1.08	Bedroom 3	**Replacement** stone mullion window: 1No fixed double glazed units. 1No side hung metal frame casement unit (2 units total) See detail drawing 3590_30_01
W1.09	Bedroom 4	Existing stone mullion window: 2No fixed double glazed units. 1No side hung metal frame casement unit (3 units total) See detail drawing 3590_30_01
W2.01	Loft/Plant Room	Existing stone mullion window: 4No fixed double glazed unit with glazing bar. (4 units total) See detail drawing 3590_30_01

REF	LOCATION	NOTES
W2.02	TV Room	Existing stone mullion window: 1No fixed double glazed unit with glazing bar. 1No side hung metal frame casement unit (2 units total) See detail drawing 3590_30_01
W2.03	Study	Existing stone mullion window: 1No fixed double glazed units. 1No side hung metal frame casement unit (2 units total) See detail drawing 3590_30_01
WR.01	Over Kitchen	In-line rooflight – see detail drawing 3590_20_02
WR.02	Over Kitchen	In-line rooflight – see detail drawing 3590_20_02
WR.03	Over Kitchen	In-line rooflight – see detail drawing 3590_20_02
WR.04	Over Dining Room	Structural glass ribbon – see detail drawing 3590_20_02
WR.05	Over Dining Room	Structural glazed link – see glass ribbon detail drawing 3590_20_02