Condition 7

Shepherd Hut
Tongue and Groove timber sealed with Cuprinol colour stain "Seagrass" (Pastel Green) and Grey Trims

Amenities Building
Timber Clad(5" Log Lap) Sealed with Cuprinol colour stain – Autumn Gold/Harvest Brown

Entrance and Car Park

A cleared width of hardcore stone compressed with a road roller

Condition 8

Hard Surfacing materials – 10m x 1m path of Indian Stone from Amenities block through to steps area
Golden Gravel for base of Shepherd Huts

Soft Surfacing materials – all other areas grassed
Means of Enclosure – existing fencing/hedges

Condition 13

Treament Plant. – See Spec Attached

Marsh Industries
Marsh Ensign Sewage treatment plant, 6 person tank
Product Code MARSH6PE
See attached plan highlighted in Pink
Building Inspectors recommendation
Approved inspectors UK Ltd, Congleton
Rob 07494 818840

Condition 15

Disposal of Surface Water

100mm perforated land drain pipe, in trenches of recommended depth
Covered with a layer of pea gravel, covered with existing soil as agreed by Building Inspector (see Plans highlighted in Green)
Finishing into a Soak Away