Project No:- P17-300 Project Title : Alton Tower Lodges												Rev.	01	
												Date:	25-Apr-18	
LUMINAIRE									LAMP			MANUFACTURER/REFERENCE		Notes
Ref	Description	Emergeny Y/N Type	Location	Dimensions	Control Gear	Finishes	Luminaire Efficacy	Images	Type	Colour Temperature	Rating	Manufacturer	Product	
A	Bollard Ligting	N	Circulatiion paths	Height 970 mm Diameter 200mm	N/A	Black	47lum/W		LED		751lum 16 W	Thorn	Tea / TEA BODY 4L105 730 BK CLI	IP64 Rated

LUMINAIRE SCHEDULE NOTES:

The foregoing is for guidance and general information only. The specific clauses detailing the lighting installation are given in the relevant clauses of the Electrical Services Specification and the accompanying foregoing is for guidance and general info

1 The Contractor may not propose alternative luminaires to those specified in the Schedule.

2 All information given in this Schedule must be checked and verified with the manufacturers. Any discrepancies must be reported to the Engineer before ordering.

3 The contractor shall be responsible for ordering all additional items which are required for a complete installation within the specified ceilings, walls and floors.

4 Luminaires shall comply with the relevant / Current sections of BS 4533 & EN 60598

5 Generally, the luminaires shall be provided with independent means of support or rest on the ceiling grid. The Contractor shall check suitability of the luminaire for installation on/in the indicated ceiling type.

6 All “lay in” type luminaires shall be complete with retaining clips or other means to ensure that diffusers do not lift on door closing, etc.

7 All colours of luminaires must be verified by the Contractor withn the Architect prior to procurement.

8 The Contractor shall ensure that all luminaires are suitable to be mounted on/in the ceiling types that are shown on the Architects drawings prior to procurement.

9 Any specials shall be submitted for approval (pre-production sample) and the Contractor shall allow for this approval time in his programme.

10 Luminaires shall not be lamped or tubed until immediately prior to hand-over. If, by agreement, luminaires are used during construction, the luminaires used during this period shall be re-lamped at hand-over.

11 All luminaires shall be cleaned and free of dust, dirt, finger prints and other deleterious materials prior to hand-over of the installation. Where dirt, dust, finger prints, corrosion or other conditions have caused imperfections in the luminaire, they shall be replaced at no extra cost to the Client.

12 All LED CRI should be greater than 87.

ADDITIONAL:

These equipment schedules are issued in line with the level of design development at the date of issue.

The contractor shall select final equipment based on the subsequent work stages up to and inclusive of the requirements of RIBA stage F2/4C installation design. The contractor shall satisfy themselves of the site dimensions and relevant installation details for specific items of equipment and interdependencies of plant items. All equipment selected shall be issued as technical submittals for approval by the Engineer. Equipment ordered against Elementa equipment schedules shall be entirely at the contractors risk.