



NEW SCREEN PLANTING WITH POST AND WIRE FENCING TO FRONT SECTION OF SIDE BOUNDARY

PART REMOVE EXISTING DRY STONE WALL, FORM NEW ACCESS AND MAKE GOOD - TRIM GARDEN PLANTS ALSO AS REQUIRED

EXISTING STAY WIRE TO POST TO BE RELOCATED IN ASSOCIATION WITH UTILITY PROVIDER

PROPOSED NEW ACCESS

TEGULA PAVED DRIVE

NEW SPECIMEN TREE PLANTING

REMOVE LLEYLANDI HEDGING TO THIS BOUNDARY AND INSTALL NEW 1800MM HIGH POST AND PANEL FENCING

BUFF COLOURED PAVING AROUND PROPOSED DWELLING





REAR BOUNDARY TO BE NEW BRICK WALL APPROVED UNDER PLANNING CONSENT 6MDV/2017/0708 BUT WITH RAISED HEIGHT AS PER SECTIONAL DRAWING

ERECT NEW 2.4 METRE HIGH BRICK BOUNDARY WALL TO AGREED DESIGN - SEE ADJACENT PHOTOS

CONNECTION STORM AND FOUL DRAINAGE TO EXISTING COMBINED SYSTEM

CLAY LAKE

Stoney Lane

Drive

Garden

Parking

Parking

5LDBY

Westfield Cottage

Car Port

Garage

Rear Vehicular Access

G.F.L. 153.550

Garden 98m2

7906

5027

Kennel

Shed

Gate

Conifer Hedge

INDICATIVE SITE PLAN AS PROPOSED 1:100
INCLUDING ROOF PLAN

0 1 2 3 4 5
Scale Bar @ 1:100 on A1 Sheet

N

RICS
The mark of
property professionalism worldwide

Clients are advised to clarify dimensions with the author prior to setting out and not to scale from the drawing. This drawing is copyright and should not be reproduced without the written consent of RLM ASSOCIATES.

**RLM ASSOCIATES**

| | |
|---|---|
| JOB | WESTFIELDS COTTAGE, ENDON. |
| CLIENT | Mr. & Mrs. WESTON. |
| DRAWING | SITE PLAN AS PROPOSED - AMENDED. |
| DATE | January 2019. |
| SCALE | 1:100. |
| DRWG No. | RLM770A/3. |
| REVISION | B. |