The Contractor is to check and verify in conjunction with the Architects details all setting out points, building and site dimensions, levels and sewer invert levels at connection points and ensure that they are fully conversant with the contents and requirements of the site investigation report before work starts. The Contractor is to comply in all respects with current building legislation, British Standard Specifications, Building Regulations etc.,whether or not specifically stated on this drawing.
This drawing is not intended to show details of ground conditions or ground contaminants. Each area of ground relied upon to support any structure depicted (including drainage) must be investigated by the Contractor any areas of formation for said structures which do not comply with the Building Regulations as deemed by the site investigation engineer must be immediately notified to the Engineer and Architect. Any suspected ingression of ground contaminants into the foundation trench must be further investigated and suitably advised upon. Any earthworks shown indicate typical slopes for guidance only and should be investigated further by a suitable geotechnical expert. Where existing trees are shown to be retained they should be subject to a full Arboricultural inspection for safety. All trees are to be planted so as to ensure they are a minimum of 5 metres from buildings and 3 metres from drainage and services, where applicable. A foundation is to be provided to accommodate the proposed tree planting, where applicable.
© This drawing and the building works depicted are the copyright of Banners Gate Ltd and may not be reproduced or amended except by written permission. No liability will be accepted for amendments made by other persons.

GENERAL NOTES

- This drawing is to be read in conjunction with relevant architectural and engineering drawings.
- Levels indicated in blocks are Finished floor levels and are 150mm above adjacent finished ground levels unless otherwise shown.
- Levels of the existing road at the point of tie-in with proposed site road must be checked prior to commencement of works.
- Any discrepancies between the details shown and actual on site conditions to be reported immediately to the engineer prior to commencement of works.

EXTERNAL WORKS & FEATURES NOTES

- All rear garden gradients are approximate and may vary due to site conditions.
- All retaining structures to be designed by a structural engineer.
- Type of retaining structure to be determined by the client.
- Extents of illustrated retaining structures, exposed brickwork below DPC, tanking, and double DPC's are shown as indicative only and may vary due to site conditions.
- Retained heights shown are indicative and may vary along the length of feature.

SHEET LAYOUT SCALE = 1:5000



External Levels & Features Legend:

Levels

- 101.20 — Proposed Finished Floor Level
- 100.80 — Proposed Garage Level
- 80.00 — Proposed Shed Level
- 80.00 — Proposed Rear of Footway Level
- 80.00 — Proposed External Level
- Ex.80.00 — Existing External Level
- 1/20 — Proposed Fall Direction & Gradient
- Proposed Flat Gradient (up to 1 in 100)
- M — Part M Level Access Indicator
- Level Threshold Demarcation
  - *900mm x 1200mm - Part M Category 1
  - *1200mm x 1200mm - Part M Category 2
  - *1500mm x 1500mm - Part M Category 3
  - *Minimum Threshold Area

External Works

- Ddpc — Proposed Double Damp Proof Coursing
- 450dbrk — Proposed Exposed Brickwork *(millimeters below damp proof course)*
- 450tank — Proposed Tanking *(millimeters above damp proof course)*
- 450RW — Proposed Masonry Retaining Wall
- 300GB — Proposed Gravel Board
- 150SOE — Proposed Slab on Edge
- Proposed Bank / Slope
  - *min. gradient = 1 in 10*
  - *max. gradient = 1 in 3*
- 4s — Proposed Steps

Drainage

- Aco — Proposed Aco Drain
- d-c — Proposed Dished Channel
- GS8.40 — Proposed Gully & Level

General

- Site Boundary
- Proposed S38 Road Gully *(subject to the relevant Highway Authorities Approval)*

Temporary screen is to be fitted in manhole over outgoing sewer during construction works to avoid debris entering into the existing network.

Proposed 1 in 2 banks to tie in with existing ground must be re-inforced and confirmed suitability by a geo-technical engineer.

Access to SUDs for maintenance and public access

NOTE: Hedgerow on the south boundary (from plots 22 to 23 and 39 to 40) to be cut back 1 meter from the centre line and maintained by the agreed management company

Future extension access point

SUDS

Courtyard

Beech Close

ASSUMED ROUTE

Rev.	Description	Date	By
G	External works amended to suit pond redesign	21.03.19	TB
F	External works amended to suit clients comments	10.12.18	TB
E	Additional levels added to corner of plots. Legend amended. Additional levels added ajacent play area	15.03.18	LJ
D	Updated to suit amended layout	20.02.18	OB
C	External features amended to suit Keepmoat comments.	01.02.18	LH
B	External levels & FFL's amended to suit revised BM3 layout.	26.01.18	LH
A	External levels & FFL's amended to suit revised BM3 layout.	07.12.17	LJ
-	First Issue	23.10.17	TB

Drawing Status

PRELIMINARY

Please note while these drawings may be used for tender purposes, drawings are subject to Client approval as part of ongoing consultations and design checks. Amendments may therefore be requested.

Client: Keepmoat

Project: Ashbourne Road, Cheadle, Stoke-on-Trent

Title: External Levels & Features Layout

Sheet 2 of 3

BANNERS GATE
CIVIL, STRUCTURAL & ARCHITECTURAL DESIGN SERVICES
10-11 Birmingham Street, Halesowen, West Midlands B63 3HN
Tel: 0121 687 1500 Fax: 0121 687 1501
E-mail: mail@bannersgate.com

Scale: 1:250 @ A1	Drawn: TB
Date: October 2017	Checked: DA
File: 16164 / dwgs / civils / current	Drawing: 16164 / 102 G