NEW SCREEN PLANTING WITH POST AND WIRE FENCING TO FRONT SECTION OF SIDE BOUNDARY

PART REMOVE EXISTING DRY STONE WALL, FORM NEW ACCESS AND MAKE GOOD - TRIM GARDEN PLANTS ALSO AS REQUIRED

CLAY LAKE

Stoney Lane

PROPOSED NEW ACCESS

Drive

Garden

Parking

'SUDS'

G.F.L. 153.550

Garden 98m2

Parking

Car Port

Westfield Cottage

Garage

Rear Vehicular Access

Kennel

Shed

Conifer Hedge

ERECT NEW 1.95 METRE HIGH BRICK BOUNDARY WALL TO AGREED DESIGN - SEE ADJACENT PHOTOS

CONNECTION STORM AND FOUL DRAINAGE TO EXISTING COMBINED SYSTEM

7906

5027

NEW SPECIMEN TREE PLANTING

TEGULA PAVED DRIVE

REMOVE LLEYLANDI HEDGING TO THIS BOUNDARY AND INSTALL NEW 1800MM HIGH POST AND PANEL FENCING

BUFF COLOURED PAVING AROUND PROPOSED DWELLING

REAR BOUNDARY TO BE NEW BRICK WALL APPROVED UNDER PLANNING CONSENT 6MD/2017/0708

INDICATIVE SITE PLAN AS PROPOSED 1:100
INCLUDING ROOF PLAN

0 1 2 3 4 5
Scale Bar @ 1:100 on A1 Sheet

N

RICS
The mark of
property professionalism worldwide

Clients are advised to clarify dimensions with the author prior to setting out and not to scale from the drawing. This drawing is copyright and should not be reproduced without the written consent of RLM ASSOCIATES.

RLM ASSOCIATES

JOB	WESTFIELDS COTTAGE, ENDON.
CLIENT	Mr. & Mrs. WESTON.
DRAWING	SITE PLAN AS PROPOSED - AMENDED.
DATE	January 2019.
SCALE	1:100.
DRWG No.	RLM770A/3.
REVISION	D.