To:	**Staffordshire Moorlands Planning**
From:	**Adam Tatton**
Re:	**Driveway widening / Kerb drop**

Date 14th January 2020

Site & Correspondence Address:

71 Cellarhead Rd, Werrington, ST9 0HW

Applicant:

Mr Adam Tatton

Application Notes

Extend existing low level stone wall to new brick gate posts. Drawing no 001801003 proposed includes transition kerb.

Remove existing road kerb to site access and supply and lay 125 x 150mm concrete half battered road kerbs extending foundation with transition ends of pavement crossing all backed with a minimum of 150mm of concrete, and lower footpath to suit in with minimum 150mm thickness of limestone hardcore road base complying with Cla8use 803, 806 or 816, 40mm thick base course of 20mm dense bitumen macadam in accordance with BS 4987: 1993, Clause 6.5, 200pen binder and 20mm thick wearing course of 6mm medium graded bitumen macadam in accordance with BS 4987: 1993, Clause 7.6, 200pen binder all to the approval of Staffordshire County Council Highways Department.

No gradient to exceed 1 in 12

Form extended parking area of macadam on minimum 150mm thickness of limestone hardcore.

Site to be left clean and tidy on completion and any damage to adjoining areas to be made good. All works to be carried out in strict accordance with all relevant BS Codes of Practice, good building practice and all relevant Health & Safety Legislation. All dimensions and levels to be checked on site.

Photo Of Existing Entrance

