This drawing is the copyright of Rhodes & Partners and must not be copied or passed to a third party without consent of the company.

Denotes Permeable paving attenuation system (Tobermore or similar approved) to attenuate individual plot roof surface water with discharge rate of 1 l/s

N

Drainage Area Schedule

Reference		Area [m²]	Pipe run
Area 1		70	S1.000
Area 2		74	S1.001
Area 3		421	S1.002
Area 4		155	S1.003
Area 5		145	S1.004
Area 6		378	S1.005
Area 7		49	S1.006
Area 8		194	S1.007
Area 9		163	S1.008
Area 10		643	S2.000
Area 11		70	S2.001
Area 12		940	S2.002
Area 13		42	S2.003
Area 14		74	S2.004
Area 15		137	S2.005

Rev	Description	By	Chkd	Date
P4	Scale bar added and "do not scale" annotations removed as requested	AR	GL	09/03/2020
P3	Levels Revised	AR	GL	02/03/2020
P2	Areas Revised	AR	GL	17/02/2020
P1	Preliminary Issue	AR	GL	07/01/2020

Drawing Status: PRELIMINARY

Rhodes & partners
Consulting Civil and Structural Engineers
The Lodge, Compstall Mills Estate, Compstall, Stockport SK6 5HN
t: 0161 427 8388 e: office@rhodesandpartners.co.uk

Client: Walton Homes

Project: The Birches, Cheadle

Drawing Title: Drainage Areas Layout

Drawn By:	Checked By:	Date:	Scale:
AR	GL	07/01/2020	1:500 on A2

Drawing No: D23080-DR-DA-101 Revision: P4

Drainage Areas Layout
[Scale 1:500]

0 5 10 15 20 25m
Scale 1:500