Ref SMD/2017/0099

## Schedule of work

(11) Maintain existing driveway but on completion put some new chippings to make repair.

(12) Form new drains to septic tank as per building Regulations plan attached.

(13) Form new path to back and front door as per plan

(14) Fix two bat boxes on gable End at high level.

Internal

(1) Strip out existing floors and Form new concrete floors to existing levels. & Building Reg requirements.

(2) New floor joists where necessary.

(3) Inject cream Biokill Crown damproof course.

(4) Fix stud partitions to all external walls with necessary insulation to meet Building Regulations

(5) Re point existing internal brick walls & pillars and Arches to leave exposed

(6) ~~Plaster~~ First fix electrical and plumbing work

7 Plaster all stud walls. & ceilings

(8) Fix new skirting & Doors.

(9) Fix new Timeless Heritage windows & Doors. in Chartwell Green.

10 Re instate existing Driveway using matching chippings.