roof ten
roof eleven
roof thirteen
roof fourteen
roof fifteen
roof sixteen
roof twelve
roof nine
roof four
roof three
roof five
roof two
roof six
roof seven
roof eight
roof seventeen
roof one
chimney 1
chimney 2
chimney 3
chimney 4
chimney 5
dormer access 1
dormer access 2
The White Hart

leaking uPVC gutter, blocked with leaves
gas boiler flue
broken cast iron RWP shoe
short cast Iron RWP- wall clamp fixed
broken cast iron RWP shoe, leaves in back inlet gutter
no RWP shoe (gutter inlet) uPVC hopper
leaking uPVC gutter
truncated original brick stack capped and vented
minor repairs to holes required to lead dormer/ new s/w door and bolt required.
open joints to copings
modern brick chimney stack capped and vented

original brickwork capped and vented
point up open joints to copings
natural blue-black slate covering
dormer access lead, needs new s/w door
lead covered king ridge roll
lead valley covered in aluminium/bitumen paint

Rev	Date	Drawn	Description
C	05/02/2019	SJ	Tender Issue, notes amended
B	02/02/2017	SE	Notes added
A	09/01/2017	JLL	Survey notes included

ctd architects
Clerk Bank House
Clerk Bank
LEEK
Staffordshire
ST13 5HE
t : 01538 373477
f : 01538 386503
e : info@ctdarchitects.co.uk
w : www.ctdarchitects.co.uk

ctd architects © 2016
- This drawing is copyright.
- All dimensions to be checked on site before proceeding.
- Contractor must notify the architect of any discrepancies before proceeding.
- Contractor to check/adjust dimensions of new work to suit existing conditions. Do not assume existing structure or details are plumb, square or level.
- All drawings to be read in conjunction with all other consultants drawings and specs.

Client: Foxlowe Arts Centre

Project: Foxlowe Arts Centre
Market Place, LEEK, Staffordshire, ST13 6AD

Title: Roof Plan 'as Existing'

Scale 1:100 | Size A2 | Drawn JLL | Chk'd CH | Date 25/11/16

Status: LISTED BUILDING CONSENT

Job No. 1558 | Drawing No. AL 14 | Rev. C