

Plant mixed stock at 2.0m c/s					
%age	Species	Size (mm)	Type	No	Notes
10	Ilex aquifolium	300–450	1L	40	min 3 breaks lower 1/3rd
30	Picea abies	300–450	1L	117	single leader, evenly branched
30	Pinus sylvestris	300–450	1L	117	single leader, evenly branched
20	Quercus petraea	300–450	br	80	
10	Sorbus aucuparia	450–600	br	40	
			Total	394	
Plant specimen trees randomly through mix					
%age	Species	Girth (mm)	Type	No	
n/a	Picea abies	120–150	RB	15	single leader, evenly branched
n/a	Pinus sylvestris	175–200	RB	15	single leader, evenly branched
n/a	Quercus petraea	100–120	br	15	
n/a	Sorbus aucuparia	100–120	br	15	
			Total	60	

Planting Notes:

1. Plant handling at the nursery, and during transit up to delivery , shall be in accordance with 'Plant Handling' the booklet published by the Committee for Plant Supply and Establishment (CPSE). The contractor shall comply with clauses 3 & 4 of the above booklet (obtained from the Horticulture Trades Association) which refers to the receipt, unloading and temporary storage of plants. Individual species in plant mixes to be planted in groups of 3 to 7no.

2. Plants shall be first class examples of their species or variety, free from all pests and diseases with good fibrous root systems and materially undamaged.
(Refer to relevant sections of BS3936 Parts 1–4 'Specification of Nursery Stock')

3. All planting is to be in general compliance with BS4428: 1989 'Code of Practice for General Landscape Operations (excluding hard surfaces)'.

4. Tree pits to be 350mm cubed. Pits to be back filled with 2/3rd imported topsoil and 1/3rd tree planting compost (non peat based). Broadleaf P4 or equivalent and an approved fertiliser to be incorporated into the backfill. The amount of additives used per pit shall be in accordance with the manufacturer's instructions.

5. One number 80 litre bag of tree planting compost (non peat based) is to be incorporated into the specimen tree pits. Compost must be thoroughly mixed with with excavated (or imported) topsoil. Broadleaf P4 or equivalent and an approved fertiliser to be incorporated into the backfill. The amount of additives used per pit shall be in accordance with the manufacturers instructions.

6. All trees are to be staked and secured as followed:
i) All specimen trees are to be double staked to 750mm above ground and secured using a single rubber tie and spacer. Spiral rabbit guards must be fitted to all specimen trees.

ii) All bare root stock shall be protected by an approved form of rabbit proof shelter. Securley staked in accordance with the manufacturer's recommendations.

7. The contractor must ascertain for himself the exact location of any underground services and maintenance points.

KEY

- Approximate extent of existing woodland
- Proposed areas of additional planting
- Un-bound sub-base to plots
- Roadway
- Proposed cabins (inc relocation of cabin 39)
- Existing buildings and cabins

Quarry Walk Park, Cheadle, Staffs ST10 1RQ

Quarry Walk Park LTD

Proposed Development
Landscape Works

General Arrangement Plan

PR/17/DW01/GA/01

The plant room

Vanessa Swift Bsc Dip LA CMLI
Landscape Architect
M: 07918 081407
F: 08717 145212
E:vanessa@theplantroom.co.uk
www.theplantroom.co.uk

May 2017

1:500 @ A2