A 520

Darleyshire Farm

PROPOSED NEW DWELLING

FWMH01
IL -600.000

FWMH02
IL -600.057

RE

100ø 1:100 fall

100ø 1:80 fall

SWMH01
IL -450.000

100ø 1:80 fall

100ø 1:100 fall

SWMH03
IL -450.98

FWMH05
IL -600.167

100ø 1:80 fall

100ø

MARSH SEWAGE TREATMENT TANK

IL: -600.264

RE

100ø 1:80 fall

100ø 1:100 fall

FWMH01
IL -600.000

SWMH02
IL -450.00

FWMH02
IL -600.057

100ø

Pipe taken to existing stream

Filled drainage mound in accordance with Building Regulations Part H2 Sections 1.37 to 1.44

9000

5000

1in2 slope

EXISTING WATER COURSE

N

Rev ID	Date	Comment

wood goldstraw yorath
ARCHITECTS QUANTITY SURVEYORS CDM CO-ORDINATORS

Churchill House, Regent Road, Stoke on Trent, ST1 3RH
Tel: 01782 208000 Fax: 01782 208712 E-mail: info@woodgoldstraw.co.uk
www.woodgoldstraw.co.uk

Client
MR AND MRS G CHADWICK

Project
PROPOSED DWELLING TO REPLACE BARN

Scale	Issue Date
1:100	28/08/2020

Sheet Size	Drawn
A0	

Title
DRAINAGE PLAN

Drawing Number	Revison ID
2991-04-13	

CAD file path:
X:\2-PROJECTS\2991 Chadwick, Mr & Mrs\2991-04 Proposed New Bungalow\Design\Drawings & Dwgs\Revit\CAD\PROPOSED BUNGALOW.pln

Copyright. Wood Goldstraw Yorath LLP

Contractors are to check all dimensions on site and refer any discrepancies to the Architect immediately. This drawing has been prepared for planning purposes only and to the best of our knowledge the original digital document is accurate at the stated scale. However, we cannot accept liability for the accuracy of third party data (OS mappings, topographical survey information, etc) used in the production of this document which we have relied upon in good faith. Key dimensions are noted for reference and any further specific dimensional information can be provided upon request.