Native Hedge Mix

Species	Specification	% of mix
Prunus domestica (Pd)	60 - 80 cms bare root	10 %
Crataegus monogyna (Cm)	60 - 80 cms bare root	70 %
Corylus avellana (Ca)	60 - 80 cms bare root	15 %
Ilex aquifolium (Ia)	2 litre pot pot grown	5 %

Existing hedge to be retained and any gaps where present to be planted with mix as schedule at 300mm centres.

Existing hedge to be retained and any gaps where present to be planted with mix as schedule at 300mm centres.

Manure Storage area formed with impermeable concrete surface capable of containing, or facilitating the collection of, all manure generated leachate manure generated from the stables with sufficient capacity to store 6 months worth of manure.

Orchard

Garden

Proposed Stables

Driveway

The Engine House

Field

North

Site Plan 1:100 @ A1

0.0m 2.0m 4.0m 6.0m 8.0m

Scale bar @ 1:100

Rev.	Drawn	Comments.	Date

MAC
ARCHITECTURAL DESIGN LTD
Moorland House, 123 Moorland Road, Burslem, ST6 1JD.
T:01782 503302 E:admin@mac-arch.co.uk

Client:
Mr J Foxall

Project:
Proposed Stables at The Old Engine House, Biddulph Road, Mow Cop, Stoke on Trent, Staffs. ST7 3PU

Title:
Site Plan

Status:
Planning.

Paper Size A1: July 2020 Drawing Ref: 1557-AL09A