MANHOLE COVER LEVELS APPROX (m)	144.069
FOUL WATER SEWER INVERT LEVELS (m)	142.719
SURFACE WATER SEWER INVERT LEVELS (m)	
MANHOLE DIAMETER (mm)	Type E 1200
Road 2 Datum: 138.000M AOD	F1 ch=1.5
CHAINAGE ON CENTRELINE (m)	0.000 2.500 10.000 20.000 30.000 35.843
LEVELS ON CENTRELINE OF CARRIAGEWAY (m)	144.099 144.037 144.270 144.582 144.893 145.075
LEVELS ON LEFT HAND CHANNEL (m)	144.208 144.519 144.831 145.013
LEVELS ON RIGHT HAND CHANNEL (m)	144.208 144.519 144.831 145.013
VERTICAL DESIGN ON CARRIAGEWAY CENTRELINE	GRADIENT 3.114% (1 in 32.109) LENGTH = 33.343m
HORIZONTAL DESIGN ON CARRIAGEWAY CENTRELINE	STRAIGHT LENGTH = 33.343m
EXISTING LEVELS (m)	144.347 144.127 144.119 144.120 144.154 144.157 144.212 144.217 144.311 144.338 144.397 144.545 144.675
PROPOSED CHAINAGE (m)	-4.500 -3.512 -2.500 -0.000 2.500 4.500 35.843 36.855 37.843
PROPOSED LEVELS (m)	144.212 144.162 144.037 144.099 144.037 144.212 145.075 145.200 145.250

Rev	Description	Chk'd/App'd	Date

Issue
PRELIMINARY

Client/Architect
BROAD OAK PROPERTIES LTD

Contract
TRAVELLERS REST
LEEKBROOK

Title
LONGITUDINAL SECTION
ROAD 2
SHEET 2 OF 2

KEYTECH DEVELOPMENT DESIGN LTD
RIVERSIDE OFFICES, MOUNTBATTEN WAY, CONGLETON, CW12 1DY
PHONE: 07710199945, EMAIL: gary@keytechdesign.co.uk

Date JAN 2021 Scale 1/200
Original size A1
Drawn HB
Checked Approved

Drawing No. Revision.
K873-104