PROPOSED FFL 249.90

RETAINING WALL

STEP IN BASE OF RETAINING WALL

OUTLINE OF RETAINING WALL BASE

STEP IN BASE OF RETAINING WALL

THIS ANGLE OF WALL TO BE 90°

STEP IN BASE OF RETAINING WALL

THIS WALL TO BE PARALLEL WITH END WALL OF PROPOSED BUILDING

THIS WALL TO BE PARALLEL TO END WALL OF EXISTING BUILDING

KEY

INDICATES LOCATION OF RETAINING WALL

DEMOLITION OF EXISTING BUILDING TO BE CONFIRMED

SEE RJP DRAWING 10942-11 FOR SECTIONS AND 10942-12 FOR ELEVATIONS / RETAINING WALL DETAILS

Area Under Demolition

Area Under Construction

Area Covered in Rubble/Concrete.

Building Demolished

Cut PR

Cut PR

MH CL 250.10 IL 248.58

MH CL 249.72 IL 249.26

MH CL 248.53 IL 247.92

MH CL 248.67 IL 247.40

MH CL 248.11 IL 247.55

Silted No Exit Visible

Silted

top conc=247.81

leaves on ground poss. items obscured

line hidden

line hidden

UTT Enclosed Ø150

63mm MDPE

RWP

UTT Enclosed

SITE LAYOUT SHOWING PROPOSED RETAINING WALL LOCATIONS

1:100

NOTES:

+ 247.10 – INDICATES PROPOSED GROUND LEVEL

Rev	Details	Drawn By	Ckd/App By	Date
P2	ISSUED FOR PLANNING	LR	SJR	24.02.22
C	RETAINING WALL SETTING-OUT AMENDED	LR	SJR	15.02.22
B	UPDATED TO SHOW ADJUSTED BUILDING LOCATION AND RE-ISSUED FOR CONSTRUCTION	LR	SJR	11.02.22
A	ISSUED FOR CONSTRUCTION	LR	SJR	04.02.22
P1	ISSUED FOR COMMENT	LR	SJR	02.02.22

Client: amey

Project: HMP WERRINGTON

Title: SITE LAYOUT SHOWING PROPOSED RETAINING WALL LOCATIONS

Issued For: PLANNING

Reid Jones partnership

Consulting Civil & Structural Engineers

9 Orrell Road, Orrell, Wigan, WN5 8EY, Tel 01942 216006

3 Cross Street, Preston, PR1 3LT, Tel 01772 498007

E-mail enq@reidjonespartnership.co.uk

Web address www.reidjonespartnership.co.uk

Scale: AS INDICATED @ (A1)

Project No:	Drawing No:	Issue:
10942	10	P2

This drawing is confidential and is the property of Reid Jones Partnership. It must not be disclosed to any third party, copied or lent without prior written consent. The contractor is to check all dimensions on site prior to commencement of works.

QMS ISO 9001 : 2015 REGISTERED QUALITY MANAGEMENT