



Outline Battery Safety Management Plan

RE Projects Development Limited – Newfields Farm

SHF.1807.005.PL.R.001.01 - OBSMP



Contact Details:

Enzygo Ltd. (Sheffield Office)
Samuel House, 5 Fox Valley Way,
Stocksbridge,
Sheffield,
S36 2AA

tel: +44 (0) 114 321 5151
email: nick.soucek@enzygo.com
www: enzygo.com

Outline Battery Safety Management Plan

Project:	Newfields Farm Battery Energy Storage System
Document:	SHF.1807.005.PL.R.001.01 – Outline Battery Safety Management Plan
For:	RE Projects Development Limited
Status:	Final
Date:	27/07/2022
Author:	Nick Soucek - Senior Planning Consultant
Reviewer:	Doug Moulton - Director of Planning

Disclaimer:

This report has been produced by Enzygo Limited within the terms of the contract with the client and taking account of the resources devoted to it by agreement with the client.

We disclaim any responsibility to the client and others in respect of any matters outside the scope of the above.

This report is confidential to the client, and we accept no responsibility of whatsoever nature to third parties to whom this report, or any part thereof, is made known. Any such party relies on the report at their own risk.

Enzygo Limited Registered in England No. 6525159

Registered Office: Gresham House, 5-7 St. Pauls Street, Leeds, England, LS1 2JG

Contents

1.0	Introduction.....	2
1.1	Introduction.....	2
1.2	Purpose of Document	2
1.3	Background.....	2
1.4	Document Structure	2
2.0	Description of Works	3
2.1	Description of Works	3
2.2	Overview of battery fire safety approach.....	4
3.0	Guidance	6
3.1	Guidance	6
3.2	Li-Ion Battery Transportation Guidance.....	6
3.3	Consultation response from Cheddleton Parish Council	7
3.4	Battery Energy Storage System Design Approach.	8
3.5	Allianz Risk Consulting Battery Energy Storage System Design Recommendations	8
4.0	Battery Energy Storage System Detailed Design Stage- Pre-construction Information	12
4.1	Battery and Rack Safety Standards	12
4.2	Fire Detection and Suppression	13
4.3	Safety Information.....	14
5.0	Conclusion.....	15
5.1	Summary	15
5.2	Outputs	15
	Glossary	16

1.0 Introduction

1.1 Introduction

- 1.1.1 This Outline Battery Safety Management Plan (OBSMP) has been prepared by Enzygo Ltd. to accompany a full planning application¹ which has been submitted to Staffordshire Moorlands District Council for a proposed 99.9MW battery storage facility and associated works at Newfields Farm, Rownall Road, Wetley Rocks, Staffordshire, ST9 0BS, Grid Reference: SJ 94398 49115 (The development).
- 1.1.2 Enzygo Ltd have worked closely with RE Projects Development Limited in collating the technical and safety information used for the detailed design of the Battery Energy Storage System (BESS).

1.2 Purpose of Document

- 1.2.1 The OBSMP details the regulatory guidance reviewed by Enzygo Ltd., to ensure that all safety concerns around the BESS element of the development are addressed in so far as is reasonably practicable.
- 1.2.2 Battery storage technology is continuously evolving as are the regulations and guidance on the safe operation of a BESS. Whilst the current design is based on the latest regulations, Enzygo will continue to review the regulations and the manufacturers guidelines to ensure that the design continues to meet the best practice for the design and operation of a BESS.

1.3 Background

- 1.3.1 RE Projects Development Limited is seeking to develop a 99.9 MW BESS and associated infrastructure at Newfields Farm. A planning application has been submitted to Staffordshire Moorlands District Council (application reference: SMD/2022/0180), and is due for determination in July 2022.

1.4 Document Structure

- 1.4.1 This Outline Battery Safety Management Plan includes the following sections:
- Introduction, including purpose of the document, background, document structure, contributors and consultation requirements
 - Description of proposed works
 - Guidance
 - Battery Energy Storage System Detailed Design Stage
 - Conclusions and Summary of Outputs

¹ SMD/2022/0180 "Development of a Battery Energy Storage System (BESS) with ancillary infrastructure, security fence, access, landscaping and biodiversity enhancements, to provide balancing services to the local electricity grid", validated 21/04/2022.

2.0 Description of Works

2.1 Description of Works

2.1.1 The proposed development is a 99.9MW Battery Energy Storage System (BESS) which will comprise of the following:

- 132/33kv Grid connected switchyard
- DNO Substation
- Customer Control/Switchgear Building
- 80 no. 40ft Battery storage containers
- 20 no. MV Transformers
- 120 no. PCS (Power Conversion Systems)
- Underground cabling
- Fencing
- CCTV monitoring system
- Hardstanding
- Parking facilities

2.1.2 An extract of the Overall Site Layout (drawing no.: 88-10-05-PL-LA-OA), submitted in support of the planning application, is shown below:




Figure 1 – Extract of Overall Site Layout

2.1.3 The batteries are housed in the 80 no. 40ft ISO containers shown in Figure 1 above.



Figure 2 – Extract of Plan and Elevations of 40 ft Battery Container Unit

2.1.4 Elevations of the 40ft containers are shown in Figure 2.

2.2 Overview of battery fire safety approach

2.2.1 The Newfields Farm BESS will use CATL EnerOne modular outdoor liquid cooled units which are certified to UL9540A. These units follow the principles for Battery Safety as follows:

- 1) Fire prevention – using battery technology proven to be at low risk of fire
- 2) Equipment monitoring – in the event that temperatures increase to unsafe levels, systems will be automatically turned off
- 3) Fire suppression – in the event that fire, smoke, or other gases are detected, then systems are in place to suppress any ignition to prevent a runaway event

Fire Prevention

2.2.2 It is proposed that the Battery Energy Storage System will use lithium ferrophosphate battery cells (LFP) as its chosen form of Lithium-Ion battery technology. LFP batteries are proven to have a lower temperature rise when compared to other types of lithium-ion batteries during thermal runaway events. Thermal runaway is a condition that occurs when the chemical reaction inside a battery cell exceeds its ability to disperse heat.

2.2.3 LFP batteries charge at a rate of 1C which means that they can deliver a fast recharge and discharge response whilst generating little heat. They require less ventilation or cooling and can withstand higher temperatures without decomposing. The cells utilise liquid-cooling cell

to pack (CTP) technology, which helps to further stabilise temperatures within cells to minimise internal temperature differential which both helps from a safety perspective as well as increasing the service life of the units.

- 2.2.4 As well as LFP batteries having stable characteristics, the prismatic cell has multi-layered protection and are housed in sealed Aluminium casing, offering a further level of protection and most importantly good thermal conductivity and cooling performance.

Equipment Monitoring

- 2.2.5 Active temperature monitoring is set up at the following scales in order to minimise the likelihood of propagation across cells, modules, and cabinets:

- The temperature of every cell is monitored, and the temperature should be within the range of 15°C and 33°C. Each cell will be continually monitored to ensure that they stay within this range;
- There is separate temperature monitoring of the battery modules (comprised of the cells); and
- At the top level there is active monitoring of the ambient temperature of each BESS cabinet.

- 2.2.6 The systems have sensors at the cell, module, unit and system level and the necessary software to warn or if necessary, automatically shut down in the event of a problem.

Fire Suppression

- 2.2.7 In addition to the temperature monitoring of the cabinets, they are also actively monitored for smoke and other gases. The positive detection of two of the temperature, gas, or smoke monitors will automatically trigger the aerosol fire suppression systems that are sealed within each BESS cabinet.

3.0 Guidance

3.1 Guidance

3.1.1 The following international guidance has been considered during the preparation of this OBSMP:

- Allianz Risk Consulting (ARC): *Battery Energy Storage Systems (BESS) Using Li-ion Batteries*, Tech Talk Volume 26 (2019)²
- National Fire Protection Association (NFPA): NFPA855, Standard for the Installation of Stationary Energy Storage Systems (2020)³
- UL 9540A Test Method, Testing the fire safety hazards associated with propagating thermal runaway within battery systems⁴
- Consolidated Edison and New York State Energy Research and Development Authority- *Considerations for ESS Fire Safety* (February 2017)⁵.

3.1.2 At the time of writing, the NFPA and UL United States of America standards are not explicitly relevant to the United Kingdom but notwithstanding this provide valuable guidance and are referred to in the ARC technical note.

3.1.3 More detailed UK guidance is emerging, and it is expected that the regulatory environment will be more developed by the detailed design stage. Examples of existing UK guidance include:

- The Energy Operations Forum: *Good Practice Guide* (December 2014)⁶
- Institute of Engineering and Technology - *Code of Practice for Electrical Energy Storage Systems* (August 2017)⁷
- The Energy Institute: Battery Storage Guidance Note 1- Battery Storage Planning (August 2019)⁸.

3.2 Li-Ion Battery Transportation Guidance

3.2.1 International guidance for testing and certification for the transportation of Li-Ion batteries exists in the form of UN38.3⁹, published by the United Nations as recommendations.

3.2.2 European Agreement Concerning the International Carriage of Dangerous Goods by Road (ADR) 2019¹⁰ includes mandatory rules for signatory states based on UN38.3 recommendations. In the ADR UN 38.3 is mentioned as obligatory. The United Kingdom is a signatory to these rules, so must apply them.

² <https://www.agcs.allianz.com/content/dam/onemarketing/agcs/agcs/pdfs-risk-advisory/tech-talks/ARC-Tech-Talk-Vol-26-BESS.pdf>

³ <https://www.nfpa.org/codes-and-standards/all-codes-and-standards/list-of-codes-and-standards/detail?code=855>

⁴ <https://www.ul.com/services/ul-9540a-test-method>

⁵ www.nyserda.ny.gov

⁶ <https://www.eatechnology.com/engineering-projects/electrical-energy-storage/>

⁷ <https://shop.theiet.org/code-of-practice-for-electrical-energy-storage-systems>

⁸ <https://bit.ly/3LiJ2YP>

⁹ https://www.unece.org/fileadmin/DAM/trans/danger/ST_SG_AC.10_11_Rev6_E_WEB_-_With_corrections_from_Corr.1.pdf

¹⁰ https://www.unece.org/fileadmin/DAM/trans/danger/ST_SG_AC.10_11_Rev6_E_WEB_-_With_corrections_from_Corr.1.pdf

- 3.2.3 UK guidance on the transport of dangerous goods is available online on the Government's "Moving dangerous goods, Guidance" website¹¹.

3.3 Consultation response from Cheddleton Parish Council

- 3.3.1 Cheddleton Parish Council (CPC) are a statutory consultation body in the consideration of planning application SMD/2022/0180. CPC objected to the application (09/06/2022) on the following grounds:

Cheddleton Parish Council Object most strongly on grounds of safety concerns which has been reported to the house of lord's science and technology committee and green belt which requires exceptional circumstances.

- 3.3.2 CPC states two reasons for objection, battery safety and Green Belt. The latter is beyond the scope of this report. Regarding concerns around battery safety, the report in question is the *House of Lords Science and Technology Select Committee: 1st Report of Session 2021-22 – Battery Strategy goes flat: Net-zero target at risk*¹². The Science and Technology Select Committee heard from lobbying groups across the public and private sectors, and the report shows the wide ranging concerns that were raised. The purpose of the report was to present recommendations to government that would help to facilitate the country's transition away from reliance on fossil fuels for energy and transport and towards the use of batteries and fuel cells for the purposes of meeting the UK's 2050 net-zero target, whilst also achieving economic gains in the developing areas of battery and fuel cell technologies.

- 3.3.3 With regards to battery safety specifically the recommendations set out in the report states:

90. The Government should take steps to build public confidence in the safety of batteries and hydrogen technologies. The concerns of residents and drivers about the fire safety of batteries must be taken seriously. Action must be taken to mitigate the risks of existing battery installations, including more stringent safety standards. Regulations and incentives should be used to drive development of safer battery technologies in transport and stationary applications. Effective fire-fighting protocols need to be developed, with provision of training and equipment for fire fighters, other first responders and vehicle maintenance workers.

- 3.3.4 It is imperative that all new battery installations meet the highest safety standards. This is an ongoing process as technologies and the relevant legislation, standards, and guidance evolves and change. The current relevant guidance on battery safety is set out in the previous section and applied to this OBSMP.

- 3.3.5 The development at Newfields Farm, subject to this planning application, is proposing to use battery technology that meets the current battery safety guidelines. As set out in this OBSMP the applicants are able to use this report which includes a safety log that can be used to help mitigate any potential events.

¹¹ <https://www.gov.uk/guidance/moving-dangerous-goods>

¹² <https://committees.parliament.uk/publications/6975/documents/77086/default/>

3.4 Battery Energy Storage System Design Approach.

3.4.1 The Development will minimise fire risk by:

- Procuring components that comply with all relevant legislation and best practice guidance
- Employment of construction techniques that comply with all relevant legislation and best practice guidance
- Including automatic fire detection systems in the facility design
- Including automatic fire suppression systems in the facility design
- Including redundancy in the system design to provide multiple layers of protection
- Designing the facility to contain and restrict the spread of fire through the use of fire-resistant materials, and adequate separation between elements of the BESS
- Offering to work with the fire and rescue (FRS) service to develop a tactical response that will minimise risk in the event of fire

3.5 Allianz Risk Consulting Battery Energy Storage System Design Recommendations

3.5.1 The recommendations set out in the ARC publication are set out in the table below, alongside a demonstration of compliance with the guidance and response from the applicant as appropriate.

Table 1: ARC Recommendations

ARC Recommendation	Project Response
Fire department • Invite the fire department to your property to discuss BESS hazards. An adequate emergency response is the key to avoiding an uncontrolled fire. Keep in mind that some fire fighters will not fully understand the hazards and may assume that lithium-ion batteries are the same as lithium batteries • Key questions to discuss with the fire department include: - What is the main difference between extinguishing and cooling? - How to handle a damaged battery?	The fire and rescue service (FRS) is a statutory consultee and has been asked to comment on the planning application; as of 26/07/22 no response has been received. RE Projects Development Ltd will engage with the FRS, following consent, to discuss a site-specific response plan in the form of a Tactical Information Record for the Newfields Farm BESS.

- How to manage the flammable and toxic gases? • Plan training exercises with the fire department when the system is commissioned. • Standard Operating Procedures (SOP) & standard Operating Guidelines (SOG) are of major importance and should be updated and tested on a regular basis.	
Construction and Location • Install BESS outdoors a minimum of 20 m (65 ft.) from important buildings or equipment. Maintain a minimum of 3 m (10 ft.) separation from lot lines, public ways and other exposures. • Within the module, maintain a minimum of 1 m (3 ft.) separation distance between enclosures for all units up to 50 kWh when not listed, or up to 250 kWh when listed. • Install a thermal barrier where the minimum space separation cannot be provided. • If the BESS must be located indoors, install in a 2 hour fire rated cut-off room, which is accessible directly outdoors for manual firefighting. • Restrict the access to competent employees or sub-contractors. • Ensure enclosures are non-combustible.	The design of the BESS will reflect prevailing legislative requirements and UK industry recommendations. The minimum recommended separation of 3m, will be utilised between individual battery containers. Separation between components within BESS containers/modules will comply with identified applicable UK regulations and legislation identified at the time of detailed design. Thermal barriers will be utilised where the minimum space separation cannot be provided, also in accordance with applicable regulations. The BESS containers will be located outdoors Access to the BESS containers will only be available to competent operational staff who have received appropriate training and certification where required by legislation, or under the supervision of competent operational staff. All enclosures will be non-combustible to EI120 standard.
Material, equipment and design • BESS will be tested in accordance with UL 9540A, <i>Test Method for Evaluating Thermal Runaway Fire Propagation in Battery Energy Storage Systems</i>. This standard evaluates thermal runaway, gas composition, flaming, fire spread, reignition and the effectiveness of fire protection systems. Data generated can be used to determine the fire and	The BESS utilised will hold the relevant test certificates and meet the electrical safety regulation applicable under UK regulations and legislation. The detailed design identifies the location of capacitors transformers and switch gear which are located in line with fire safety best practice.

explosion protection requirements for a BESS. Place capacitor, transformer, and switch gear in separate rooms according to best engineering practices.	
Ventilation and temperature control - Maintaining temperature control is vital to these batteries' longevity and proper operation as they degrade exponentially at elevated temperatures. - Ensure ventilation is provided in accordance with the manufacturer's recommendations. - Install and maintain the ventilation during all stages of a fire. Ventilation is important since batteries will continue to generate flammable gas as long as they are hot. Also, carbon monoxide will be generated until the batteries are completely cooled through their core.	All enclosures will include adequate Heating Ventilation and Air Conditioning (HVAC) installations incorporating redundancy. The behaviour of HVAC and air circulation in the event of a pre-alarm and main alarm will be defined by the manufacturer (and, if applicable, the certifier) with due regard to the extinguishing agent used.
Gas detection and smoke detection - Install a very early warning fire detection system, such as aspirating smoke detection. - Install carbon monoxide (CO) detection within the container or BESS room.	A minimum of two types of fire detection system will be deployed, (e.g., optical, heat, chemical etc.). The fire detection system will be installed with fire resistant wires and components. Carbon monoxide detectors will be installed as required.
Fire protection - Install Liquid cooled gas suppression system. - This includes: - Smoke detection - Water dry pipe - Fused sprinkler heads - Thermal detection - Flammable gas detection - Vent - Aerosol	The fire protection concept will be based on the prevention of propagation with high construction standards, suppression systems and distances to adjacent installations. The BESS will include a gas-based extinguishing fire suppression system, as a first barrier of security against fire propagation within a container. Separation between adjacent installations is a security redundancy measure to limit fire

- Arc Flash: $\leq 12 \text{ cal/cm}^2$	propagation in case of a suppression system failure or a non-typical failure event.
Maintenance • Follow original equipment manufacturer recommendations for the inspection, testing and maintenance of BESS. In addition, ensure that the following are completed: - Measure the internal resistance of the cells. Replace cells when a dramatic drop is detected. Keep in mind that the internal resistance is mainly independent of the state of charge, but increases as the battery ages. Therefore, it is a good gauge of predictable life. - Perform infrared scanning at least once per year. - Check for fluid leakage. - Implement electric terminal torquing procedures to maintain connection integrity.	Internal resistance is measured as part of the State of Health (SOH) control system, with maintenance and replacement carried out regularly to respond to the results. Constant insulation monitoring of each battery bank detects potential leakage. Prepare an operating procedure for the swap-out of faulty cells/modules. This will include plans for suitable storage locations for the modules prior to removal from site. Torque tests are part of the operation and maintenance process. Infrared scanning will take place annually.

4.0 Battery Energy Storage System Detailed Design Stage- Pre-construction Information

4.1 Battery and Rack Safety Standards

4.1.1 The batteries that will be installed in the BESS will be Lithium Iron Phosphate (ferrophosphate) type Li-ion battery cells. The cells and modules will be compliant with the following standards:

- UN38.3¹³ - International guidance for the transportation of Li-Ion batteries
- UL1973¹⁴ - Batteries for Use in Stationary and Motive Auxiliary Power Applications
- UL9540A¹⁵ - Test Method for Evaluating Thermal Runaway Fire Propagation in Battery Energy Storage Systems.
- IEC62619¹⁶ - Secondary cells and batteries containing alkaline or other non-acid electrolytes - Safety requirements for secondary lithium cells and batteries, for use in industrial applications

4.1.2 The racks are integrated into CATL EnerOne modular outdoor liquid cooled units compliant with the following standards:

- UL9540A (see above)
- UL1973 (see above)
- IEC62619 (see above)
- IEC62477-1¹⁷ - Safety requirements for power electronic converter systems and equipment - Part 1: General
- IEC61000-6-2¹⁸/4¹⁹ - Electromagnetic compatibility (EMC) - Part 6-2: Generic standards - Immunity standard for industrial environments; Part 6-4: Generic standards - Emission standard for industrial environments

4.1.3 The primary fire safety standard above is **UL9540A**, a test method and methodology developed to address safety concerns around lithium-ion batteries and battery energy storage systems to be permanently installed in mixed occupancy or high rise buildings, identified by the building codes and the fire service in the United States.

4.1.4 All cells, racks, and modules to be installed at the proposed battery storage site will have passed the UL9540A evaluations for thermal runaway fire propagation. At the level of the cell the methodology develops cell thermal runaway initiation technique and characteristics including gas composition. At the module level the approach determines propagation behaviour within the module and thermal energy release outside of the module. Both open and closed room scenarios are considered for unit to unit fire spread with heat release rate and gas analysis to determine the potential for explosion.

¹³ [1520832_E_ST_SG_AC.10_11_Rev6.pdf\(unece.org\)](https://www.unece.org/standards/standardscatalog/ul-9540a-test-method)

¹⁴ <https://standardscatalog.ul.com/ProductDetail.aspx?productId=UL1973>

¹⁵ <https://www.ul.com/services/ul-9540a-test-method>

¹⁶ <https://webstore.iec.ch/publication/28895>

¹⁷ <https://webstore.iec.ch/publication/7080>

¹⁸ <https://webstore.iec.ch/publication/25630>

¹⁹ <https://webstore.iec.ch/publication/26622>

- 4.1.5 Results from the UL 9540A Test Method addresses the following key issues identified by building codes and the fire service:
- BESS installation instructions
 - Installation ventilation requirements
 - Effectiveness of fire protection (integral or external)
 - Fire service strategy and tactics
- 4.1.6 The current ICC International Fire Code²⁰ allows an *individual* BESS unit (in this case the containers) not exceeding 50 kWh and having a maximum quantity of systems totalling 600 kWh of energy per indoor fire area (battery room). The 2018 IFC and the draft NFPA 855 standard for installation of energy storage systems currently limits the individual BESS unit size for UL9540 listed units to 250 kWh.
- 4.1.7 These individual BESS units are to be installed with a minimum separation distance of 3 feet (1 metre) between units and between units and any wall. The latest IFC and NFPA 855 drafts allow the code official (AHJ) to approve larger individual BESS units, and separation distances less than 3 feet based on large scale fire testing conducted in accordance with the UL 9540A Test Method.
- 4.1.8 The proposed battery storage units (the containers) are well within the unit maximum of 50kWh, and in total comprise 100kWh which is significantly less than 600 kWh.

4.2 Fire Detection and Suppression

- 4.2.1 The battery units have an integrated aerosol fire extinguishing system that consists of:
- Smoke detector
 - Temperature detector
 - Aerosol fire extinguishing device
- 4.2.2 When either the smoke or temperature detectors are triggered it is classified as a first level fire alarm. When this happens the alarm cabinet quits the state of operating and sends a signal to the Environmental Management System (EMS).
- 4.2.3 When both the detectors are triggered it is classified as a second level fire alarm. When this happens the aerosol of the alarm cabinet is released, with all of the electrical cabinets in the system out of operation and signal reported to the EMS.
- 4.2.4 The extinguishing agent is composed of ultra-fine potassium salt particles and inert gas. Potassium salt is considered to be one of the most effective fire-extinguishing agents; its fire-extinguishing mechanism is similar to the highly effective Halon²¹ which extinguish fires by impeding the complex chemical chain reaction of combustion or explosion. The combustion chain reaction requires the participation of OH, H and O radicals, and ultrafine potassium salt particles can quickly consume these free radicals and prevent the combustion chain reaction from proceeding.
- 4.2.5 In the event of the detectors both being triggered a specified concentration of fire extinguishing agent is sprayed to fill the entire protection area, and which will result in total

²⁰ (2018 IFC) Paragraph 1207.5.1 Size and Separation

²¹ The use of Halon extinguishers and other CFCs was linked to Ozone depletion and their use is banned in the UK and internationally.

flooding of the area that will extinguish any open flame. This method is effective in combating electrical fires, electrolyte fires and other combustibles fires (A/B/C fires).

4.3 Safety Information

- 4.3.1 The table below sets out a guide for the information that will be maintained as a 'safety log' by the operator so best practice is followed to minimise fire risk. The applicant is committed to producing and maintaining this document as part of a best practice approach.
- 4.3.2 The information in the safety log will help to inform the Tactical Information Record developed with the FRS.

Table 2: Detailed Design Information for Safety Log

Specification	Reason for Inclusion
Statement of Compliance with Applicable Legislation	To demonstrate compliance with legislation.
Detailed Design Drawing of Battery Energy Storage System	To ensure available and safe access for fire appliances To enable FRS to evaluate the available access for fire appliances to all parts of the BESS. To show separation between components of the BESS.
Statement of design responses to fire risk	To accompany the detailed design drawing and explain how the risk of fire spreading has been addressed through the Development Design.
Battery Specification	To ensure that FRS are aware of the specific type of batteries installed. This would include the battery chemistry as well as size and format of each cell.
Fire Detection System Specification	To demonstrate how the requirement for fire suppression has been addressed.
Fire Suppression System Specification	To demonstrate how the requirement for fire suppression has been addressed.
Standard Operating Procedures and Guidelines (Relevant to Safety)	To demonstrate an ongoing commitment to regular checks and maintenance during operation e.g., plans for swap-out of suspected modules. Include a list of competencies and/or certification requirements for competent Site Operating Staff.
BESS Installation Contractor Emergency Protocol (during construction)	To demonstrate that protocols are in place to manage a fire during construction.
Site Operator Emergency Protocol (during operation, including decommissioning)	To demonstrate that protocols are in place to manage a fire during the operation and decommissioning.
Battery Transportation Plan	To ensure that the transportation of battery cells, including delivery of new, used failed and replacement battery cells to and from the site is carried out in accordance with prevailing legislation.

5.0 Conclusion

5.1 Summary

- 5.1.1 The OBSMP outlines the proposed development for a proposed 99.9MW battery storage facility and associated works, and how it will be managed from a fire safety risk mitigation perspective.
- 5.1.2 The document collates the technical and safety information used for the detailed design of the BESS to ensure that all safety concerns around the facility are addressed in so far as is reasonably practicable.
- 5.1.3 The OBSMP may be updated once the proposed phasing of development is known and in line with any new regulations and/or guidelines that are introduced.

5.2 Outputs

- 5.2.1 The applicants are committed to working towards the following Fire Safety outputs:

Tactical Information Record

- 5.2.2 RE Projects Development Limited invite the FRS to develop a Tactical Information Record for the Newfields Farm BESS; which will facilitate FRS responders to the site with technical and tactical information about the site and best approaches in the event of a fire event.

Safety Log

- 5.2.3 RE Projects Development Limited will produce a 'safety log' which will be maintained and updated by the operator as part of a best practice approach. A guide to the information to be included in the safety log is set out above.
- 5.2.4 The safety log will be made available to the FRS, and could be used as the basis for the Tactical Information Record set out above.

Glossary

- ADR - Agreement Concerning the International Carriage of Dangerous Goods by Road
- ARC - Allianz Risk Consulting
- BESS – battery energy storage system
- CO - Carbon Monoxide
- ESS – Energy Storage System
- FRS –Fire & Rescue Service
- HVAC - Heating Ventilation and Air Conditioning
- Li-ion - Lithium-ion
- LFP - Lithium Iron Phosphate battery cells
- LPA - Local Planning Authority
- National Fire Protection Association (NFPA)
- OBSMP - Outline Battery Safety Management Plan
- SOG - Standard Operating Guidelines
- SOH - State of Health
- SOP - Standard Operating Procedures



Enzygo specialise in a wide range of technical services:

Property and Sites

Waste and Mineral Planning

Flooding, Drainage and Hydrology

Landscape Architecture

Arboriculture

Permitting and Regulation

Waste Technologies and Renewables

Waste Contract Procurement

Noise and Vibration

Ecology Services

Contaminated Land and Geotechnical

Traffic and Transportation

Planning Services

BRISTOL OFFICE

The Byre
Woodend Lane
Cromhall
Gloucestershire GL12 8AA
Tel: 01454 269 237

SHEFFIELD OFFICE

Samuel House
5 Fox Valley Way
Stocksbridge
Sheffield S36 2AA
Tel: 0114 321 5151

MANCHESTER OFFICE

Ducie House
Ducie Street
Manchester
M1 2JW
Tel: 0161 413 6444

Please visit our website for more information.

enzygo.com