STAFFORDSHIRE moorlands DISTRICT COUNCIL

ACHIEVING · EXCELLENCE

Dealt with by: Environmental Health

Direct Dial: (01538) 395400

Email: EHealth.Consultation@highpeak.gov.uk

Our Ref: **smd/2022/0516**

Your Ref: as above

Date: 22nd November 2022

MEMORANDUM: PLANNING CONSULTATION

LOCATION	**30 Buxton Road** **Leek**
PROPOSED DEVELOPMENT	**Change of use of existing commercial property to form charity accommodation with associated operational development**

Potential Areas of Environmental Concern -

1.Construction Impacts (condition)
2. Asbestos (Advisory)
3. Sound insulation (Advisory)
4. Lighting (Condition)

General Comments

- Asbestos: A Demolition or refurbishment asbestos survey and risk assessment should be carried out prior to the demolition/renovation of the existing buildings. The enforcing authority for this type of work is the Health and Safety Executive (HSE) and it is recommended that you contact them directly to discuss their requirements: http://www.hse.gov.uk/

- Sound Insulation: It would be advisable the glazing in the property has a noise reduction specification to ensure that sound levels in the proposed meeting rooms and offices are at a reasonable level. See guidance set out in BS8233:2014 Guidance on sound insulation and noise reduction for buildings.

Recommendation – No objection subject to condition.

1. Construction & Demolition Works: Time of operations

Unless prior permission has been obtained in writing from the Local Planning Authority, all noisy activities shall be restricted to the following times of operations.

- 08:00 - 18:00 hours (Monday to Friday);
- 08:00 - 13:00 hours (Saturday)
- No working is permitted on Sundays or Bank Holidays.

In this instance a noisy activity is defined as any activity (for instance, but not restricted to, building construction/demolition operations, refurbishing and landscaping) which generates noise that is audible at the site boundary.

Reason: To avoid the risk of disturbance to neighbouring dwellings from noise during unsocial hours.

2. Construction & Demolition: Pollution Control

I. During construction/demolition phases amplified music and/or radios shall not be audible beyond the site boundary;
II. Any waste material associated with the demolition or construction shall not be burnt on site but shall be kept securely for removal to prevent escape into the environment. All waste transfer records should be retained for inspection by officers of the Local Planning Authority;
III. No activity hereby permitted shall cause dust to be emitted beyond the site boundary so as to adversely adjacent residential properties and/or other sensitive uses and/or the local environment. In the event dust is caused to escape the site boundary the activity shall be stopped until sufficient dust suppression has been undertaken to prevent further escape. There shall always be the appropriate means and sufficient water resources on site for dust suppression. These should be made available for inspection when required by officers of the Local Planning Authority

Reason: *To protect the amenities of the area during construction*

3. Lighting

The artificial lighting incorporated into this site in connection to this application shall not increase the pre-existing illuminance at the adjoining light sensitive locations when the light (s) is (are) in operation. Details of all artificial lighting to be installed under this permission should be submitted to and approved by the Local Planning Authority prior to development commencing.

Reason: *To protect the local amenities of the local residents by reason of excess of illuminance*

Advisory:

Please be aware that the responsibility for safe development and secure occupancy of the site rests with the developer.

- A Demolition or refurbishment asbestos survey and risk assessment should be carried out prior to the demolition of the existing buildings. The enforcing authority for this type of work is the Health and Safety Executive (HSE) and it is recommended that you contact them directly to discuss their requirements: http://www.hse.gov.uk/

- Any approved foul drainage system should meet the British Standard 6297:2007+A1:2008: Code of practice for the design and installation of drainage fields for use in wastewater treatment http://www.bsigroup.com

- Any approved noise scheme and measurements should pay due regard to British Standard BS8233: Sound insulation and noise reduction for buildings (Code of Practice), BS4142:2014 Methods for rating and assessing industrial or commercial sound and/or the Building Regulations 2010 Document E or other appropriate guidance.

- Advice on controlling flies and light can be found in: Statutory Nuisance from Insects and Artificial Light (defra 2005) available as a free download http://archive.defra.gov.uk/environment/quality/local/legislation/cnea/documents/statnuisance.pdf

- During any demolition and construction activities (including landscaping) the contractor shall take all reasonable steps to prevent dust formation and prevent any dust formed from leaving the site boundary.

    - The control of dust and emissions from construction and demolition Best Practice Guidance, produced by the greater London councils http://www.london.gov.uk/sites/default/files/BPGcontrolofdustandemissions.pdf

    - Building Research Establishment Guidance Document 'Control of Dust from Construction and Demolition Activities' (BR456)

- If required, Contamination risk assessments shall be carried out in accordance with UK policy the Land contamination risk management framework (LCRM), published by the Environment Ageny https://www.gov.uk/government/publications/land-contamination-risk-management-lcrm

    - Submission of reports should also be made to the Environment Agency for comment with regard to their remit to protect ground and surface waters from pollution and their obligations relating to contaminated land.

    - The Local Planning Authority will determine the acceptability of reports on the basis of the information made available to it. Please be aware that should a risk of harm from contamination remain post development, where the applicant had prior knowledge of the contamination, the applicant is likely to be liable under Part II (a) of the Environmental

    Protection Act 1990 and as such become and "appropriate person". In this event the applicant will be lawfully responsible to remove the risk posed by the contamination.

    - Equally if during any site works a pathway for any contaminant on site is created and humans, waters, property or ecological systems are exposed to this, the applicant or those acting on behalf of the applicant will be liable under part II (a) of the Environmental Protection Act 1990 if the risks are not adequately addressed during the site redevelopment.

    - During investigation and remediation works the applicant and those acting on behalf of the applicant must ensure that site workers, public property and the environment are protected against noise, dust, odour and fumes

    - The applicant is advised that should there be a requirement as part of the Remediation Strategy to treat, reuse or remove contaminated material on the site, the Environment Agency must be consulted, as these activities may need to be licensed or permitted. Contaminated materials identified for removal off site must be disposed of in an appropriately licensed landfill site.

    - Staffordshire Moorlands District Council is keen to liaise with all stakeholders involved in this application. As such, we recommend that a proposed scope of works is forwarded to

the Environmental Protection Department and agreed in principle prior to site investigation works being undertaken. The Environmental Protection Department is also prepared to review draft copies of reports prior to final submission to the Planning Department in order to ensure that works undertaken are sufficient to discharge the contaminated land conditions.

Regards,
Environmental Health