

RPS Group Plc

Noble House, Capital Drive
Linford Wood
Mitlton Keynes, MK14 6QP

Date 29/10/2022
File AAC5895 SITE 3D AREA 1 ...

Hill Helicopters
Blythe Bridge
Staffs

Designed by SAS
Checked by

Page 1



Innovyze

Network 2020.1

Network Design Table for Surface Network 1

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section	Type	Auto Design
2.000	9.137	0.032	286.1	0.000	5.00	0.0	0.600	o	375	Pipe/Conduit		
1.001	54.711	0.176	310.8	0.288	0.00	0.0	0.600	o	525	Pipe/Conduit		
1.002	38.668	0.125	310.1	0.140	0.00	0.0	0.600	o	525	Pipe/Conduit		
3.000	27.616	0.780	35.4	0.029	5.00	0.0	0.600	o	300	Pipe/Conduit		
1.003	70.020	0.225	311.2	0.249	0.00	0.0	0.600	o	525	Pipe/Conduit		
1.004	21.720	0.054	402.0	0.171	0.00	0.0	0.600	o	525	Pipe/Conduit		
4.000	69.277	0.292	237.0	0.000	5.00	0.0	0.600	o	300	Pipe/Conduit		
4.001	12.862	0.054	237.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit		
1.005	20.699	0.048	431.2	0.000	0.00	0.0	0.600	o	525	Pipe/Conduit		
1.006	39.760	0.076	523.2	0.000	0.00	0.0	0.600	o	525	Pipe/Conduit		
5.000	36.412	0.154	237.0	0.000	5.00	0.0	0.600	o	300	Pipe/Conduit		
5.001	31.480	0.133	237.0	0.136	0.00	0.0	0.600	o	300	Pipe/Conduit		
5.002	14.447	0.061	237.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit		
6.000	19.111	0.115	166.1	0.000	5.00	0.0	0.600	o	225	Pipe/Conduit		

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
2.000	58.50	5.14	154.160	0.000	0.0	0.0	0.0	1.07	117.8	0.0
1.001	50.64	7.04	153.978	0.805	0.0	0.0	0.0	1.27	273.9	110.4
1.002	48.93	7.55	153.802	0.945	0.0	0.0	0.0	1.27	274.2	125.2
3.000	58.35	5.17	154.682	0.029	0.0	0.0	0.0	2.65	187.4	4.5
1.003	46.13	8.48	153.677	1.222	0.0	0.0	0.0	1.26	273.7	152.7
1.004	45.24	8.80	153.452	1.393	0.0	0.0	0.0	1.11	240.5	170.7
4.000	54.07	6.14	153.970	0.000	0.0	0.0	0.0	1.02	71.9	0.0
4.001	53.23	6.35	153.677	0.000	0.0	0.0	0.0	1.02	71.9	0.0
1.005	44.39	9.12	153.398	1.393	0.0	0.0	0.0	1.07	232.1	170.7
1.006	42.71	9.80	153.350	1.393	0.0	0.0	0.0	0.97	210.5	170.7
5.000	56.37	5.60	155.490	0.000	0.0	0.0	0.0	1.02	71.9	0.0
5.001	54.16	6.11	155.336	0.136	0.0	0.0	0.0	1.02	71.9	19.9
5.002	53.22	6.35	155.203	0.136	0.0	0.0	0.0	1.02	71.9	19.9
6.000	57.67	5.31	155.338	0.000	0.0	0.0	0.0	1.01	40.2	0.0

©1982-2020 Innovyze

RPS Group Plc

Noble House, Capital Drive
Linford Wood
Mitlton Keynes, MK14 6QP

Date 29/10/2022
File AAC5895 SITE 3D AREA 1 ...

Hill Helicopters
Blythe Bridge
Staffs

Designed by SAS
Checked by

Page 2



Innovyze

Network 2020.1

Network Design Table for Surface Network 1

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
5.003	10.300	0.043	237.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
5.004	5.646	0.024	237.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
7.000	11.728	0.044	267.0	0.000	5.00	0.0	0.600	o	300	Pipe/Conduit	
7.001	20.824	0.078	267.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
7.002	6.964	0.026	267.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
8.000	17.905	0.111	161.0	0.000	5.00	0.0	0.600	o	225	Pipe/Conduit	
8.001	3.653	0.023	161.0	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
7.003	4.087	0.015	267.0	0.086	0.00	0.0	0.600	o	300	Pipe/Conduit	
7.004	43.503	0.020	2175.2	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
9.000	9.577	0.031	313.0	0.366	5.00	0.0	0.600	o	375	Pipe/Conduit	
9.001	8.332	0.027	313.0	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
9.002	5.162	0.016	313.0	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
5.005	13.430	0.045	298.4	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
5.006	36.092	1.050	34.4	0.079	0.00	0.0	0.600	o	375	Pipe/Conduit	
5.007	19.236	0.053	361.4	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
5.003	52.56	6.52	155.142	0.136	0.0	0.0	0.0	1.02	71.9	19.9
5.004	52.21	6.61	155.099	0.136	0.0	0.0	0.0	1.02	71.9	19.9
7.000	58.20	5.20	155.258	0.000	0.0	0.0	0.0	0.96	67.7	0.0
7.001	56.51	5.57	155.214	0.000	0.0	0.0	0.0	0.96	67.7	0.0
7.002	55.97	5.69	155.136	0.000	0.0	0.0	0.0	0.96	67.7	0.0
8.000	57.79	5.29	155.288	0.000	0.0	0.0	0.0	1.03	40.9	0.0
8.001	57.51	5.35	155.176	0.000	0.0	0.0	0.0	1.03	40.9	0.0
7.003	55.66	5.76	155.110	0.086	0.0	0.0	0.0	0.96	67.7	12.9
7.004	48.55	7.67	155.020	0.086	0.0	0.0	0.0	0.38	41.9	12.9
9.000	58.43	5.16	155.074	0.366	0.0	0.0	0.0	1.02	112.5	58.0
9.001	57.78	5.29	155.043	0.366	0.0	0.0	0.0	1.02	112.5	58.0
9.002	57.38	5.38	155.016	0.366	0.0	0.0	0.0	1.02	112.5	58.0
5.005	47.88	7.88	155.000	0.588	0.0	0.0	0.0	1.04	115.3	76.2
5.006	47.29	8.08	154.955	0.667	0.0	0.0	0.0	3.10	342.4	85.4
5.007	46.41	8.38	153.829	0.667	0.0	0.0	0.0	1.06	169.2	85.4

©1982-2020 Innovyze

RPS Group Plc

Noble House, Capital Drive
Linford Wood
Mitlton Keynes, MK14 6QP

Date 29/10/2022
File AAC5895 SITE 3D AREA 1 ...

Innovyze

Hill Helicopters
Blythe Bridge
Staffs

Designed by SAS
Checked by

Network 2020.1

Page 3



Network Design Table for Surface Network 1

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
10.000	11.786	0.262	45.0	0.040	5.00	0.0	0.600	o	225	Pipe/Conduit	
10.001	13.732	0.399	34.4	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
5.008	13.394	0.037	361.4	0.053	0.00	0.0	0.600	o	450	Pipe/Conduit	
5.009	100.220	0.277	361.4	0.256	0.00	0.0	0.600	o	450	Pipe/Conduit	
5.010	32.566	0.076	426.5	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	
11.000	25.768	0.135	190.9	0.567	5.00	0.0	0.600	o	450	Pipe/Conduit	
11.001	39.769	0.207	192.1	0.223	0.00	0.0	0.600	o	600	Pipe/Conduit	
12.000	16.844	0.100	167.6	0.034	5.00	0.0	0.600	o	225	Pipe/Conduit	
13.000	6.558	0.039	167.0	0.036	5.00	0.0	0.600	o	225	Pipe/Conduit	
12.001	6.785	0.041	165.5	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
11.002	47.050	0.148	317.9	0.000	0.00	0.0	0.600	o	600	Pipe/Conduit	
14.000	30.701	0.184	167.0	0.271	5.00	0.0	0.600	o	300	Pipe/Conduit	
14.001	14.629	0.088	167.0	0.119	0.00	0.0	0.600	o	375	Pipe/Conduit	
11.003	24.868	0.080	310.8	0.079	0.00	0.0	0.600	o	600	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
10.000	58.71	5.10	154.662	0.040	0.0	0.0	0.0	1.96	77.7	6.4
10.001	58.21	5.20	154.400	0.040	0.0	0.0	0.0	2.24	89.0	6.4
5.008	45.81	8.59	153.776	0.760	0.0	0.0	0.0	1.06	169.2	94.3
5.009	41.89	10.16	153.739	1.016	0.0	0.0	0.0	1.06	169.2	115.3
5.010	40.68	10.72	153.461	1.016	0.0	0.0	0.0	0.98	155.5	115.3
11.000	57.78	5.29	154.105	0.567	0.0	0.0	0.0	1.47	233.5	88.7
11.001	56.04	5.67	153.820	0.790	0.0	0.0	0.0	1.75	495.8	119.9
12.000	57.84	5.28	154.129	0.034	0.0	0.0	0.0	1.01	40.0	5.3
13.000	58.67	5.11	154.068	0.036	0.0	0.0	0.0	1.01	40.1	5.7
12.001	57.32	5.39	154.029	0.070	0.0	0.0	0.0	1.01	40.3	10.9
11.002	53.62	6.25	153.613	0.860	0.0	0.0	0.0	1.36	384.6	124.8
14.000	57.17	5.42	154.036	0.271	0.0	0.0	0.0	1.21	85.8	42.0
14.001	56.38	5.60	153.778	0.390	0.0	0.0	0.0	1.40	154.5	59.6
11.003	52.45	6.55	153.465	1.329	0.0	0.0	0.0	1.38	389.0	188.8

©1982-2020 Innovyze

[illegible]

RPS Group Plc		Page 5																				
Noble House, Capital Drive Linford Wood Mitlton Keynes, MK14 6QP	Hill Helicopters Blythe Bridge Staffs																					
Date 29/10/2022	Designed by SAS																					
File AAC5895 SITE 3D AREA 1 ...	Checked by																					
Innovyze	Network 2020.1																					
Simulation Criteria for Surface Network 1 <table><tr><td>Rainfall Model</td><td>FEH</td></tr><tr><td>Return Period (years)</td><td>2</td></tr><tr><td>FEH Rainfall Version</td><td>2013</td></tr><tr><td>Site Location</td><td>GB 398031 338663 SJ 98031 38663</td></tr><tr><td>Data Type</td><td>Point</td></tr><tr><td>Summer Storms</td><td>Yes</td></tr><tr><td>Winter Storms</td><td>No</td></tr><tr><td>Cv (Summer)</td><td>0.750</td></tr><tr><td>Cv (Winter)</td><td>0.840</td></tr><tr><td>Storm Duration (mins)</td><td>30</td></tr></table>			Rainfall Model	FEH	Return Period (years)	2	FEH Rainfall Version	2013	Site Location	GB 398031 338663 SJ 98031 38663	Data Type	Point	Summer Storms	Yes	Winter Storms	No	Cv (Summer)	0.750	Cv (Winter)	0.840	Storm Duration (mins)	30
Rainfall Model	FEH																					
Return Period (years)	2																					
FEH Rainfall Version	2013																					
Site Location	GB 398031 338663 SJ 98031 38663																					
Data Type	Point																					
Summer Storms	Yes																					
Winter Storms	No																					
Cv (Summer)	0.750																					
Cv (Winter)	0.840																					
Storm Duration (mins)	30																					
©1982-2020 Innovyze																						

RPS Group Plc		Page 6																																																																								
Noble House, Capital Drive Linford Wood Mitlton Keynes, MK14 6QP	Hill Helicopters Blythe Bridge Staffs																																																																									
Date 29/10/2022	Designed by SAS																																																																									
File AAC5895 SITE 3D AREA 1 ...	Checked by																																																																									
Innovyze	Network 2020.1																																																																									
Online Controls for Surface Network 1																																																																										
Hydro-Brake® Optimum Manhole: S26, DS/PN: 5.006, Volume (m³): 11.6																																																																										
Unit Reference MD-SHE-0062-1500-0700-1500 Design Head (m)0.700 Design Flow (l/s)1.5 Flush-Flo™Calculated ObjectiveMinimise upstream storage ApplicationSurface Sump AvailableYes Diameter (mm)62 Invert Level (m)154.955 Minimum Outlet Pipe Diameter (mm)75 Suggested Manhole Diameter (mm)1200																																																																										
Control Points Head (m)Flow (l/s) Design Point (Calculated)0.7001.5 Flush-Flo™0.2111.5 Kick-Flo®0.4461.2 Mean Flow over Head Range-1.3																																																																										
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated																																																																										
<table><tr><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td></tr><tr><td>0.100</td><td>1.4</td><td>1.200</td><td>1.9</td><td>3.000</td><td>2.9</td><td>7.000</td><td>4.3</td></tr><tr><td>0.200</td><td>1.5</td><td>1.400</td><td>2.1</td><td>3.500</td><td>3.1</td><td>7.500</td><td>4.5</td></tr><tr><td>0.300</td><td>1.5</td><td>1.600</td><td>2.2</td><td>4.000</td><td>3.3</td><td>8.000</td><td>4.6</td></tr><tr><td>0.400</td><td>1.4</td><td>1.800</td><td>2.3</td><td>4.500</td><td>3.5</td><td>8.500</td><td>4.8</td></tr><tr><td>0.500</td><td>1.3</td><td>2.000</td><td>2.4</td><td>5.000</td><td>3.7</td><td>9.000</td><td>4.9</td></tr><tr><td>0.600</td><td>1.4</td><td>2.200</td><td>2.5</td><td>5.500</td><td>3.9</td><td>9.500</td><td>5.0</td></tr><tr><td>0.800</td><td>1.6</td><td>2.400</td><td>2.6</td><td>6.000</td><td>4.0</td><td></td><td></td></tr><tr><td>1.000</td><td>1.8</td><td>2.600</td><td>2.7</td><td>6.500</td><td>4.2</td><td></td><td></td></tr></table>			Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	0.100	1.4	1.200	1.9	3.000	2.9	7.000	4.3	0.200	1.5	1.400	2.1	3.500	3.1	7.500	4.5	0.300	1.5	1.600	2.2	4.000	3.3	8.000	4.6	0.400	1.4	1.800	2.3	4.500	3.5	8.500	4.8	0.500	1.3	2.000	2.4	5.000	3.7	9.000	4.9	0.600	1.4	2.200	2.5	5.500	3.9	9.500	5.0	0.800	1.6	2.400	2.6	6.000	4.0			1.000	1.8	2.600	2.7	6.500	4.2		
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)																																																																			
0.100	1.4	1.200	1.9	3.000	2.9	7.000	4.3																																																																			
0.200	1.5	1.400	2.1	3.500	3.1	7.500	4.5																																																																			
0.300	1.5	1.600	2.2	4.000	3.3	8.000	4.6																																																																			
0.400	1.4	1.800	2.3	4.500	3.5	8.500	4.8																																																																			
0.500	1.3	2.000	2.4	5.000	3.7	9.000	4.9																																																																			
0.600	1.4	2.200	2.5	5.500	3.9	9.500	5.0																																																																			
0.800	1.6	2.400	2.6	6.000	4.0																																																																					
1.000	1.8	2.600	2.7	6.500	4.2																																																																					
Hydro-Brake® Optimum Manhole: S23, DS/PN: 1.008, Volume (m³): 14.1																																																																										
Unit Reference MD-SHE-0119-7400-1500-7400 Design Head (m)1.500 Design Flow (l/s)7.4 Flush-Flo™Calculated ObjectiveMinimise upstream storage ApplicationSurface Sump AvailableYes Diameter (mm)119 Invert Level (m)153.240 Minimum Outlet Pipe Diameter (mm)150 Suggested Manhole Diameter (mm)1200																																																																										
©1982-2020 Innovyze																																																																										

RPS Group Plc		Page 7																																																																								
Noble House, Capital Drive Linford Wood Mitlton Keynes, MK14 6QP	Hill Helicopters Blythe Bridge Staffs																																																																									
Date 29/10/2022	Designed by SAS																																																																									
File AAC5895 SITE 3D AREA 1 ...	Checked by																																																																									
Innovyze	Network 2020.1																																																																									
<u>Hydro-Brake® Optimum Manhole: S23, DS/PN: 1.008, Volume (m³): 14.1</u>																																																																										
<table><tr><td>Control Points</td><td>Head (m)</td><td>Flow (l/s)</td></tr><tr><td>Design Point (Calculated)</td><td>1.500</td><td>7.4</td></tr><tr><td>Flush-Flo™</td><td>0.441</td><td>7.4</td></tr><tr><td>Kick-Flo®</td><td>0.920</td><td>5.9</td></tr><tr><td>Mean Flow over Head Range</td><td>-</td><td>6.5</td></tr></table>			Control Points	Head (m)	Flow (l/s)	Design Point (Calculated)	1.500	7.4	Flush-Flo™	0.441	7.4	Kick-Flo®	0.920	5.9	Mean Flow over Head Range	-	6.5																																																									
Control Points	Head (m)	Flow (l/s)																																																																								
Design Point (Calculated)	1.500	7.4																																																																								
Flush-Flo™	0.441	7.4																																																																								
Kick-Flo®	0.920	5.9																																																																								
Mean Flow over Head Range	-	6.5																																																																								
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated																																																																										
<table><tr><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td></tr><tr><td>0.100</td><td>4.2</td><td>1.200</td><td>6.7</td><td>3.000</td><td>10.3</td><td>7.000</td><td>15.3</td></tr><tr><td>0.200</td><td>6.7</td><td>1.400</td><td>7.2</td><td>3.500</td><td>11.0</td><td>7.500</td><td>15.9</td></tr><tr><td>0.300</td><td>7.2</td><td>1.600</td><td>7.6</td><td>4.000</td><td>11.8</td><td>8.000</td><td>16.4</td></tr><tr><td>0.400</td><td>7.4</td><td>1.800</td><td>8.1</td><td>4.500</td><td>12.4</td><td>8.500</td><td>16.8</td></tr><tr><td>0.500</td><td>7.4</td><td>2.000</td><td>8.5</td><td>5.000</td><td>13.1</td><td>9.000</td><td>17.3</td></tr><tr><td>0.600</td><td>7.3</td><td>2.200</td><td>8.9</td><td>5.500</td><td>13.7</td><td>9.500</td><td>17.8</td></tr><tr><td>0.800</td><td>6.7</td><td>2.400</td><td>9.2</td><td>6.000</td><td>14.3</td><td></td><td></td></tr><tr><td>1.000</td><td>6.1</td><td>2.600</td><td>9.6</td><td>6.500</td><td>14.8</td><td></td><td></td></tr></table>			Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	0.100	4.2	1.200	6.7	3.000	10.3	7.000	15.3	0.200	6.7	1.400	7.2	3.500	11.0	7.500	15.9	0.300	7.2	1.600	7.6	4.000	11.8	8.000	16.4	0.400	7.4	1.800	8.1	4.500	12.4	8.500	16.8	0.500	7.4	2.000	8.5	5.000	13.1	9.000	17.3	0.600	7.3	2.200	8.9	5.500	13.7	9.500	17.8	0.800	6.7	2.400	9.2	6.000	14.3			1.000	6.1	2.600	9.6	6.500	14.8		
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)																																																																			
0.100	4.2	1.200	6.7	3.000	10.3	7.000	15.3																																																																			
0.200	6.7	1.400	7.2	3.500	11.0	7.500	15.9																																																																			
0.300	7.2	1.600	7.6	4.000	11.8	8.000	16.4																																																																			
0.400	7.4	1.800	8.1	4.500	12.4	8.500	16.8																																																																			
0.500	7.4	2.000	8.5	5.000	13.1	9.000	17.3																																																																			
0.600	7.3	2.200	8.9	5.500	13.7	9.500	17.8																																																																			
0.800	6.7	2.400	9.2	6.000	14.3																																																																					
1.000	6.1	2.600	9.6	6.500	14.8																																																																					
©1982-2020 Innovyze																																																																										

RPS Group Plc		Page 8
Noble House, Capital Drive Linford Wood Miltlton Keynes, MK14 6QP	Hill Helicopters Blythe Bridge Staffs	
Date 29/10/2022 File AAC5895 SITE 3D AREA 1 ...	Designed by SAS Checked by	
Innovyze	Network 2020.1	

Storage Structures for Surface Network 1

Cellular Storage Manhole: S79, DS/PN: 2.000

Invert Level (m) 154.160 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	51.0	0.0	0.801	0.0	0.0
0.800	51.0	0.0			

Tank or Pond Manhole: HW4, DS/PN: 5.005

Invert Level (m) 155.000

Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	0.0	0.301	1125.3	0.601	1170.3	0.901	1215.6
0.101	1095.4	0.401	1140.3	0.701	1185.4	1.000	1230.7
0.201	1110.3	0.501	1155.3	0.801	1200.5	1.001	1230.8

Cellular Storage Manhole: S27, DS/PN: 15.000

Invert Level (m) 153.350 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	2185.0	0.0	0.801	0.0	0.0
0.800	2185.0	0.0			

Tank or Pond Manhole: HW8, DS/PN: 1.007

Invert Level (m) 153.275

Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	431.2	0.401	553.2	0.801	684.3	1.201	824.4
0.101	460.8	0.501	585.1	0.901	718.5	1.301	860.8
0.201	491.1	0.601	617.6	1.001	753.2	1.312	865.0
0.301	521.9	0.701	650.7	1.101	788.5		

RPS Group Plc		Page 9
Noble House, Capital Drive Linford Wood Milton Keynes, MK14 6QP	Hill Helicopters Blythe Bridge Staffs	
Date 29/10/2022	Designed by SAS	
File AAC5895 SITE 3D AREA 1 ...	Checked by	
Innovyze		Network 2020.1

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 1

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	0.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	4
Number of Online Controls	2	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location	GB 398031 338663 SJ 98031 38663
Data Type	Point
Cv (Summer)	0.750
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	OFF
DVD Status	OFF
Inertia Status	OFF

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
Return Period(s) (years)	2, 30, 100
Climate Change (%)	0, 0, 30

WARNING: Half Drain Time has not been calculated as the structure is too full.

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
1.000	S9	15 Winter	2	+0%	100/15 Summer	100/15 Winter		
2.000	S79	15 Winter	2	+0%	100/15 Summer	100/15 Winter		
1.001	S8	15 Winter	2	+0%	30/15 Winter			
1.002	S16	15 Winter	2	+0%	30/15 Summer	100/30 Winter		
3.000	S67	15 Winter	2	+0%	100/15 Summer			
1.003	S68	15 Winter	2	+0%	30/15 Summer			
1.004	S3	15 Winter	2	+0%	30/15 Summer			
4.000	S24	15 Summer	2	+0%	100/15 Summer			
4.001	S25	180 Winter	2	+0%	30/15 Summer			
1.005	S42	180 Winter	2	+0%	30/15 Summer			
1.006	HW6	180 Winter	2	+0%	30/15 Summer			

©1982-2020 Innovyze

RPS Group Plc

Noble House, Capital Drive
Linford Wood
Mitlton Keynes, MK14 6QP

Date 29/10/2022
File AAC5895 SITE 3D AREA 1 ...

Hill Helicopters
Blythe Bridge
Staffs

Designed by SAS
Checked by

Page 10



Innovyze

Network 2020.1

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)

for Surface Network 1

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
1.000	S9	154.506	-0.328	0.000	0.28			71.6	OK	3
2.000	S79	154.164	-0.371	0.000	0.00		12	0.2	OK	2
1.001	S8	154.216	-0.286	0.000	0.41			101.8	OK	
1.002	S16	154.064	-0.262	0.000	0.48			114.3	OK	1
3.000	S67	154.714	-0.268	0.000	0.03			4.3	OK	
1.003	S68	153.959	-0.243	0.000	0.55			138.4	OK	
1.004	S3	153.820	-0.157	0.000	0.76			145.4	OK	
4.000	S24	153.970	-0.300	0.000	0.00			0.0	OK	
4.001	S25	153.797	-0.181	0.000	0.00			0.2	OK	
1.005	S42	153.797	-0.126	0.000	0.30			54.0	OK	
1.006	HW6	153.789	-0.086	0.000	0.29			52.6	OK	

©1982-2020

Innovyze

RPS Group Plc

Noble House, Capital Drive
Linford Wood
Miltton Keynes, MK14 6QP

Date 29/10/2022
File AAC5895 SITE 3D AREA 1 ...

Hill Helicopters
Blythe Bridge
Staffs

Designed by SAS
Checked by

Page 11



Innovyze

Network 2020.1

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)

for Surface Network 1

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
5.000	S17	15 Summer	2	+0%	100/15 Winter			
5.001	S18	15 Winter	2	+0%	100/15 Summer			
5.002	S19	15 Winter	2	+0%	100/15 Summer			
6.000	S76	15 Summer	2	+0%				
5.003	S77	15 Winter	2	+0%	100/15 Summer			
5.004	HW3	15 Winter	2	+0%	100/15 Summer			
7.000	S70	15 Summer	2	+0%				
7.001	S71	15 Summer	2	+0%				
7.002	S72	15 Winter	2	+0%	100/240 Winter			
8.000	S74	15 Summer	2	+0%				
8.001	S78	15 Winter	2	+0%	100/180 Winter			
7.003	S73	15 Winter	2	+0%	100/180 Winter			
7.004	S75	600 Winter	2	+0%	100/120 Winter			
9.000	S21	15 Winter	2	+0%	30/15 Summer	100/15 Summer		
9.001	S63	15 Winter	2	+0%	30/15 Summer			
9.002	HW2	15 Winter	2	+0%	30/15 Summer			
5.005	HW4	600 Winter	2	+0%	100/120 Winter			
5.006	S26	600 Winter	2	+0%	30/15 Summer			
5.007	S12	15 Winter	2	+0%	30/15 Winter			
10.000	S59	15 Winter	2	+0%	100/15 Summer			
10.001	S60	15 Winter	2	+0%	100/15 Summer			
5.008	S61	15 Winter	2	+0%	30/15 Summer			
5.009	S13	15 Winter	2	+0%	30/15 Summer			
5.010	S14	180 Winter	2	+0%	30/15 Summer			
11.000	S35	15 Winter	2	+0%	100/15 Summer	100/15 Summer		
11.001	S36	15 Winter	2	+0%	30/15 Winter			
12.000	S39	15 Winter	2	+0%	30/15 Winter			
13.000	S65	15 Winter	2	+0%	30/15 Summer			
12.001	S64	15 Winter	2	+0%	30/15 Summer			
11.002	S40	15 Winter	2	+0%	30/15 Summer			
14.000	S66	15 Winter	2	+0%	30/15 Summer	100/15 Summer		
14.001	S41	15 Winter	2	+0%	30/15 Summer			
11.003	S37	15 Winter	2	+0%	30/15 Summer			
5.011	S38	180 Winter	2	+0%	30/15 Summer			
5.012	HW5	180 Winter	2	+0%	30/15 Summer			
15.000	S27	720 Winter	2	+0%	100/120 Winter			
15.001	HW7	180 Winter	2	+0%	30/30 Summer			
1.007	HW8	180 Winter	2	+0%	30/15 Winter			
1.008	S23	180 Winter	2	+0%	2/15 Summer			
1.009	S6	720 Summer	2	+0%				

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
5.000	S17	155.490	-0.300	0.000	0.00			0.0	OK
5.001	S18	155.441	-0.195	0.000	0.26			17.2	OK

©1982-2020 Innovyze

RPS Group Plc		Page 12						
Noble House, Capital Drive Linford Wood Mitlton Keynes, MK14 6QP		Hill Helicopters Blythe Bridge Staffs						
Date 29/10/2022 File AAC5895 SITE 3D AREA 1 ...		Designed by SAS Checked by						
Innovyze		Network 2020.1						
2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1								
PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
5.002	S19	155.312	-0.191	0.000	0.28		17.0	OK
6.000	S76	155.338	-0.225	0.000	0.00		0.0	OK
5.003	S77	155.254	-0.188	0.000	0.30		17.0	OK
5.004	HW3	155.220	-0.179	0.000	0.34		16.8	OK
7.000	S70	155.258	-0.300	0.000	0.00		0.0	OK
7.001	S71	155.214	-0.300	0.000	0.00		0.0	OK
7.002	S72	155.197	-0.239	0.000	0.01		0.5	OK
8.000	S74	155.288	-0.225	0.000	0.00		0.0	OK
8.001	S78	155.189	-0.212	0.000	0.00		0.1	OK
7.003	S73	155.204	-0.206	0.000	0.21		10.2	OK
7.004	S75	155.180	-0.215	0.000	0.03		1.6	OK
9.000	S21	155.310	-0.139	0.000	0.68		54.9	OK
9.001	S63	155.280	-0.138	0.000	0.70		54.1	OK
9.002	HW2	155.253	-0.138	0.000	0.72		54.7	OK
5.005	HW4	155.180	-0.195	0.000	0.02		1.5	OK
5.006	S26	155.179	-0.151	0.000	0.00		1.5	OK
5.007	S12	153.917	-0.362	0.000	0.01		1.8	OK
10.000	S59	154.708	-0.179	0.000	0.09		6.1	OK
10.001	S60	154.442	-0.183	0.000	0.08		6.0	OK
5.008	S61	153.916	-0.309	0.000	0.12		13.9	OK
5.009	S13	153.902	-0.286	0.000	0.26		42.2	OK
5.010	S14	153.793	-0.119	0.000	0.10		13.8	OK
11.000	S35	154.313	-0.242	0.000	0.43		84.6	OK
11.001	S36	154.032	-0.388	0.000	0.27		112.7	OK
12.000	S39	154.186	-0.168	0.000	0.14		5.1	OK
13.000	S65	154.138	-0.155	0.000	0.18		5.4	OK
12.001	S64	154.122	-0.132	0.000	0.35		10.4	OK
11.002	S40	153.889	-0.324	0.000	0.35		116.6	OK
14.000	S66	154.192	-0.145	0.000	0.51		39.9	OK
14.001	S41	153.962	-0.190	0.000	0.48		55.5	OK
11.003	S37	153.816	-0.249	0.000	0.55		168.7	OK
5.011	S38	153.789	-0.196	0.000	0.24		63.1	OK
5.012	HW5	153.785	-0.165	0.000	0.19		62.5	OK
15.000	S27	153.584	-0.366	0.000	0.02		4.4	OK
15.001	HW7	153.685	-0.215	0.000	0.03		4.3	OK
1.007	HW8	153.780	-0.094	0.000	0.03		9.3	OK
1.008	S23	153.783	0.318	0.000	0.20		7.4	SURCHARGED
1.009	S6	153.139	-0.150	0.000	0.25		7.4	OK
	US/MH PN Name	Level Exceeded						
	5.000	S17						
	5.001	S18						
	5.002	S19						
	6.000	S76						
©1982-2020 Innovyze								

RPS Group Plc		Page 13																																																																																																															
Noble House, Capital Drive Linford Wood Mitlton Keynes, MK14 6QP	Hill Helicopters Blythe Bridge Staffs																																																																																																																
Date 29/10/2022 File AAC5895 SITE 3D AREA 1 ...	Designed by SAS Checked by																																																																																																																
Innovyze	Network 2020.1																																																																																																																
<u>2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)</u> <u>for Surface Network 1</u>																																																																																																																	
	<table><thead><tr><th>PN</th><th>US/MH Name</th><th>Level Exceeded</th></tr></thead><tbody><tr><td>5.003</td><td>S77</td><td></td></tr><tr><td>5.004</td><td>HW3</td><td></td></tr><tr><td>7.000</td><td>S70</td><td></td></tr><tr><td>7.001</td><td>S71</td><td></td></tr><tr><td>7.002</td><td>S72</td><td></td></tr><tr><td>8.000</td><td>S74</td><td></td></tr><tr><td>8.001</td><td>S78</td><td></td></tr><tr><td>7.003</td><td>S73</td><td></td></tr><tr><td>7.004</td><td>S75</td><td></td></tr><tr><td>9.000</td><td>S21</td><td>2</td></tr><tr><td>9.001</td><td>S63</td><td></td></tr><tr><td>9.002</td><td>HW2</td><td></td></tr><tr><td>5.005</td><td>HW4</td><td></td></tr><tr><td>5.006</td><td>S26</td><td></td></tr><tr><td>5.007</td><td>S12</td><td></td></tr><tr><td>10.000</td><td>S59</td><td></td></tr><tr><td>10.001</td><td>S60</td><td></td></tr><tr><td>5.008</td><td>S61</td><td></td></tr><tr><td>5.009</td><td>S13</td><td></td></tr><tr><td>5.010</td><td>S14</td><td></td></tr><tr><td>11.000</td><td>S35</td><td>2</td></tr><tr><td>11.001</td><td>S36</td><td></td></tr><tr><td>12.000</td><td>S39</td><td></td></tr><tr><td>13.000</td><td>S65</td><td></td></tr><tr><td>12.001</td><td>S64</td><td></td></tr><tr><td>11.002</td><td>S40</td><td></td></tr><tr><td>14.000</td><td>S66</td><td>2</td></tr><tr><td>14.001</td><td>S41</td><td></td></tr><tr><td>11.003</td><td>S37</td><td></td></tr><tr><td>5.011</td><td>S38</td><td></td></tr><tr><td>5.012</td><td>HW5</td><td></td></tr><tr><td>15.000</td><td>S27</td><td></td></tr><tr><td>15.001</td><td>HW7</td><td></td></tr><tr><td>1.007</td><td>HW8</td><td></td></tr><tr><td>1.008</td><td>S23</td><td></td></tr><tr><td>1.009</td><td>S6</td><td></td></tr></tbody></table>	PN	US/MH Name	Level Exceeded	5.003	S77		5.004	HW3		7.000	S70		7.001	S71		7.002	S72		8.000	S74		8.001	S78		7.003	S73		7.004	S75		9.000	S21	2	9.001	S63		9.002	HW2		5.005	HW4		5.006	S26		5.007	S12		10.000	S59		10.001	S60		5.008	S61		5.009	S13		5.010	S14		11.000	S35	2	11.001	S36		12.000	S39		13.000	S65		12.001	S64		11.002	S40		14.000	S66	2	14.001	S41		11.003	S37		5.011	S38		5.012	HW5		15.000	S27		15.001	HW7		1.007	HW8		1.008	S23		1.009	S6		
PN	US/MH Name	Level Exceeded																																																																																																															
5.003	S77																																																																																																																
5.004	HW3																																																																																																																
7.000	S70																																																																																																																
7.001	S71																																																																																																																
7.002	S72																																																																																																																
8.000	S74																																																																																																																
8.001	S78																																																																																																																
7.003	S73																																																																																																																
7.004	S75																																																																																																																
9.000	S21	2																																																																																																															
9.001	S63																																																																																																																
9.002	HW2																																																																																																																
5.005	HW4																																																																																																																
5.006	S26																																																																																																																
5.007	S12																																																																																																																
10.000	S59																																																																																																																
10.001	S60																																																																																																																
5.008	S61																																																																																																																
5.009	S13																																																																																																																
5.010	S14																																																																																																																
11.000	S35	2																																																																																																															
11.001	S36																																																																																																																
12.000	S39																																																																																																																
13.000	S65																																																																																																																
12.001	S64																																																																																																																
11.002	S40																																																																																																																
14.000	S66	2																																																																																																															
14.001	S41																																																																																																																
11.003	S37																																																																																																																
5.011	S38																																																																																																																
5.012	HW5																																																																																																																
15.000	S27																																																																																																																
15.001	HW7																																																																																																																
1.007	HW8																																																																																																																
1.008	S23																																																																																																																
1.009	S6																																																																																																																
©1982-2020 Innovyze																																																																																																																	

RPS Group Plc

Noble House, Capital Drive
Linford Wood
Miltton Keynes, MK14 6QP

Date 29/10/2022
File AAC5895 SITE 3D AREA 1 ...

Hill Helicopters
Blythe Bridge
Staffs

Designed by SAS
Checked by

Innovyze

Network 2020.1

Page 14



30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 1

Simulation Criteria

Areal Reduction Factor 1.000

Additional Flow - % of Total Flow 0.000

Hot Start (mins) 0

MADD Factor * 10m³/ha Storage 0.000

Hot Start Level (mm) 0

Inlet Coeffiecient 0.800

Manhole Headloss Coeff (Global) 0.500

Flow per Person per Day (l/per/day) 0.000

Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0

Number of Storage Structures 4

Number of Online Controls 2

Number of Time/Area Diagrams 0

Number of Offline Controls 0

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall ModelFEH

FEH Rainfall Version2013

Site LocationGB 398031 338663 SJ 98031 38663

Data TypePoint

Cv (Summer)0.750

Cv (Winter)0.840

Margin for Flood Risk Warning (mm)300.0

Analysis Timestep 2.5 Second Increment (Extended)

DTS StatusOFF

DVD StatusOFF

Inertia StatusOFF

Profile(s)Summer and Winter

Duration(s) (mins)15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080

Return Period(s) (years)2, 30, 100

Climate Change (%)0, 0, 30

WARNING: Half Drain Time has not been calculated as the structure is too full.

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surgecharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
1.000	S9 15	Winter	30	+0%	100/15 Summer	100/15 Winter		
2.000	S79 15	Winter	30	+0%	100/15 Summer	100/15 Winter		
1.001	S8 15	Winter	30	+0%	30/15 Winter			
1.002	S16 15	Winter	30	+0%	30/15 Summer	100/30 Winter		
3.000	S67 15	Winter	30	+0%	100/15 Summer			
1.003	S68 15	Winter	30	+0%	30/15 Summer			
1.004	S3 15	Winter	30	+0%	30/15 Summer			
4.000	S24 60	Winter	30	+0%	100/15 Summer			
4.001	S25 60	Winter	30	+0%	30/15 Summer			
1.005	S42 60	Winter	30	+0%	30/15 Summer			
1.006	HW6 60	Winter	30	+0%	30/15 Summer			

©1982-2020

Innovyze

RPS Group Plc		Page 15
Noble House, Capital Drive Linford Wood Milton Keynes, MK14 6QP	Hill Helicopters Blythe Bridge Staffs	
Date 29/10/2022 File AAC5895 SITE 3D AREA 1 ...	Designed by SAS Checked by	
Innovyze		Network 2020.1

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 1

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
1.000	S9	154.636	-0.198	0.000	0.63		164.1	OK
2.000	S79	154.345	-0.189	0.000	0.32	6	27.6	OK
1.001	S8	154.540	0.038	0.000	0.76		187.1	SURCHARGED
1.002	S16	154.459	0.132	0.000	0.81		191.8	SURCHARGED
3.000	S67	154.729	-0.253	0.000	0.06		9.9	OK
1.003	S68	154.378	0.176	0.000	0.99		250.1	SURCHARGED
1.004	S3	154.161	0.184	0.000	1.45		277.2	SURCHARGED
4.000	S24	154.124	-0.145	0.000	0.00		0.2	OK
4.001	S25	154.124	0.147	0.000	0.04		2.6	SURCHARGED
1.005	S42	154.125	0.202	0.000	1.10		196.6	SURCHARGED
1.006	HW6	154.094	0.219	0.000	1.04		190.7	SURCHARGED

PN	US/MH Name	Level Exceeded
1.000	S9	3
2.000	S79	2
1.001	S8	
1.002	S16	1
3.000	S67	
1.003	S68	
1.004	S3	
4.000	S24	
4.001	S25	
1.005	S42	
1.006	HW6	

[illegible]

RPS Group Plc

Noble House, Capital Drive
Linford Wood
Miltton Keynes, MK14 6QP

Date 29/10/2022
File AAC5895 SITE 3D AREA 1 ...

Hill Helicopters
Blythe Bridge
Staffs

Designed by SAS
Checked by

Page 17



Innovyze

Network 2020.1

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 1

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
5.002	S19	155.407	-0.096	0.000	0.80			47.8	OK
6.000	S76	155.347	-0.216	0.000	0.00			0.1	OK
5.003	S77	155.361	-0.081	0.000	0.81			46.0	OK
5.004	HW3	155.329	-0.069	0.000	0.94			46.4	OK
7.000	S70	155.301	-0.257	0.000	0.00			0.0	OK
7.001	S71	155.301	-0.213	0.000	0.00			0.0	OK
7.002	S72	155.301	-0.135	0.000	0.00			0.0	OK
8.000	S74	155.301	-0.212	0.000	0.00			0.0	OK
8.001	S78	155.301	-0.101	0.000	0.00			0.0	OK
7.003	S73	155.301	-0.109	0.000	0.05			2.4	OK
7.004	S75	155.301	-0.094	0.000	0.04			2.4	OK
9.000	S21	155.673	0.224	0.000	1.53			123.3	SURCHARGED
9.001	S63	155.567	0.149	0.000	1.60			124.2	SURCHARGED
9.002	HW2	155.461	0.070	0.000	1.64			124.9	SURCHARGED
5.005	HW4	155.301	-0.074	0.000	0.02			1.5	OK
5.006	S26	155.342	0.012	0.000	0.00			1.5	SURCHARGED
5.007	S12	154.304	0.025	0.000	0.04			6.1	SURCHARGED
10.000	S59	154.732	-0.155	0.000	0.21			13.9	OK
10.001	S60	154.464	-0.161	0.000	0.18			13.7	OK
5.008	S61	154.305	0.079	0.000	0.23			26.1	SURCHARGED
5.009	S13	154.299	0.110	0.000	0.60			96.7	SURCHARGED
5.010	S14	154.239	0.328	0.000	0.57			77.1	SURCHARGED
11.000	S35	154.512	-0.043	0.000	0.98			192.5	OK
11.001	S36	154.428	0.008	0.000	0.61			257.5	SURCHARGED
12.000	S39	154.415	0.060	0.000	0.32			11.5	SURCHARGED
13.000	S65	154.406	0.113	0.000	0.41			12.2	SURCHARGED
12.001	S64	154.397	0.143	0.000	0.75			22.6	SURCHARGED
11.002	S40	154.378	0.165	0.000	0.67			224.3	SURCHARGED
14.000	S66	154.583	0.246	0.000	1.15			90.0	SURCHARGED
14.001	S41	154.375	0.223	0.000	1.06			122.3	SURCHARGED
11.003	S37	154.310	0.245	0.000	1.13			346.7	SURCHARGED
5.011	S38	154.203	0.218	0.000	1.56			418.8	SURCHARGED
5.012	HW5	154.080	0.130	0.000	0.47			155.4	SURCHARGED
15.000	S27	153.813	-0.137	0.000	0.01			4.3	OK
15.001	HW7	153.976	0.076	0.000	0.03			4.3	SURCHARGED
1.007	HW8	154.060	0.186	0.000	0.04			11.1	SURCHARGED
1.008	S23	154.079	0.614	0.000	0.20			7.4	SURCHARGED
1.009	S6	153.139	-0.150	0.000	0.25			7.4	OK

US/MH
PN Name

Level
Exceeded

5.000 S17

5.001 S18

5.002 S19

6.000 S76

©1982-2020 Innovyze

RPS Group Plc		Page 18																																																																																																															
Noble House, Capital Drive Linford Wood Mitlton Keynes, MK14 6QP	Hill Helicopters Blythe Bridge Staffs																																																																																																																
Date 29/10/2022 File AAC5895 SITE 3D AREA 1 ...	Designed by SAS Checked by																																																																																																																
Innovyze	Network 2020.1																																																																																																																
<u>30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)</u> <u>for Surface Network 1</u>																																																																																																																	
	<table><thead><tr><th>PN</th><th>US/MH Name</th><th>Level Exceeded</th></tr></thead><tbody><tr><td>5.003</td><td>S77</td><td></td></tr><tr><td>5.004</td><td>HW3</td><td></td></tr><tr><td>7.000</td><td>S70</td><td></td></tr><tr><td>7.001</td><td>S71</td><td></td></tr><tr><td>7.002</td><td>S72</td><td></td></tr><tr><td>8.000</td><td>S74</td><td></td></tr><tr><td>8.001</td><td>S78</td><td></td></tr><tr><td>7.003</td><td>S73</td><td></td></tr><tr><td>7.004</td><td>S75</td><td></td></tr><tr><td>9.000</td><td>S21</td><td>2</td></tr><tr><td>9.001</td><td>S63</td><td></td></tr><tr><td>9.002</td><td>HW2</td><td></td></tr><tr><td>5.005</td><td>HW4</td><td></td></tr><tr><td>5.006</td><td>S26</td><td></td></tr><tr><td>5.007</td><td>S12</td><td></td></tr><tr><td>10.000</td><td>S59</td><td></td></tr><tr><td>10.001</td><td>S60</td><td></td></tr><tr><td>5.008</td><td>S61</td><td></td></tr><tr><td>5.009</td><td>S13</td><td></td></tr><tr><td>5.010</td><td>S14</td><td></td></tr><tr><td>11.000</td><td>S35</td><td>2</td></tr><tr><td>11.001</td><td>S36</td><td></td></tr><tr><td>12.000</td><td>S39</td><td></td></tr><tr><td>13.000</td><td>S65</td><td></td></tr><tr><td>12.001</td><td>S64</td><td></td></tr><tr><td>11.002</td><td>S40</td><td></td></tr><tr><td>14.000</td><td>S66</td><td>2</td></tr><tr><td>14.001</td><td>S41</td><td></td></tr><tr><td>11.003</td><td>S37</td><td></td></tr><tr><td>5.011</td><td>S38</td><td></td></tr><tr><td>5.012</td><td>HW5</td><td></td></tr><tr><td>15.000</td><td>S27</td><td></td></tr><tr><td>15.001</td><td>HW7</td><td></td></tr><tr><td>1.007</td><td>HW8</td><td></td></tr><tr><td>1.008</td><td>S23</td><td></td></tr><tr><td>1.009</td><td>S6</td><td></td></tr></tbody></table>	PN	US/MH Name	Level Exceeded	5.003	S77		5.004	HW3		7.000	S70		7.001	S71		7.002	S72		8.000	S74		8.001	S78		7.003	S73		7.004	S75		9.000	S21	2	9.001	S63		9.002	HW2		5.005	HW4		5.006	S26		5.007	S12		10.000	S59		10.001	S60		5.008	S61		5.009	S13		5.010	S14		11.000	S35	2	11.001	S36		12.000	S39		13.000	S65		12.001	S64		11.002	S40		14.000	S66	2	14.001	S41		11.003	S37		5.011	S38		5.012	HW5		15.000	S27		15.001	HW7		1.007	HW8		1.008	S23		1.009	S6		
PN	US/MH Name	Level Exceeded																																																																																																															
5.003	S77																																																																																																																
5.004	HW3																																																																																																																
7.000	S70																																																																																																																
7.001	S71																																																																																																																
7.002	S72																																																																																																																
8.000	S74																																																																																																																
8.001	S78																																																																																																																
7.003	S73																																																																																																																
7.004	S75																																																																																																																
9.000	S21	2																																																																																																															
9.001	S63																																																																																																																
9.002	HW2																																																																																																																
5.005	HW4																																																																																																																
5.006	S26																																																																																																																
5.007	S12																																																																																																																
10.000	S59																																																																																																																
10.001	S60																																																																																																																
5.008	S61																																																																																																																
5.009	S13																																																																																																																
5.010	S14																																																																																																																
11.000	S35	2																																																																																																															
11.001	S36																																																																																																																
12.000	S39																																																																																																																
13.000	S65																																																																																																																
12.001	S64																																																																																																																
11.002	S40																																																																																																																
14.000	S66	2																																																																																																															
14.001	S41																																																																																																																
11.003	S37																																																																																																																
5.011	S38																																																																																																																
5.012	HW5																																																																																																																
15.000	S27																																																																																																																
15.001	HW7																																																																																																																
1.007	HW8																																																																																																																
1.008	S23																																																																																																																
1.009	S6																																																																																																																
©1982-2020 Innovyze																																																																																																																	

RPS Group Plc				Page 19																																																																																																															
Noble House, Capital Drive Linford Wood Mitlton Keynes, MK14 6QP				Hill Helicopters Blythe Bridge Staffs																																																																																																															
Date 29/10/2022 File AAC5895 SITE 3D AREA 1 ...				Designed by SAS Checked by																																																																																																															
Innovyze				Network 2020.1																																																																																																															
100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1																																																																																																																			
Simulation Criteria Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 0.000 Hot Start Level (mm) 0 Inlet Coeffiecient 0.800 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000 Foul Sewage per hectare (l/s) 0.000 Number of Input Hydrographs 0 Number of Storage Structures 4 Number of Online Controls 2 Number of Time/Area Diagrams 0 Number of Offline Controls 0 Number of Real Time Controls 0																																																																																																																			
Synthetic Rainfall Details Rainfall Model FEH FEH Rainfall Version 2013 Site Location GB 398031 338663 SJ 98031 38663 Data Type Point Cv (Summer) 0.750 Cv (Winter) 0.840 Margin for Flood Risk Warning (mm) 300.0 Analysis Timestep 2.5 Second Increment (Extended) DTS Status OFF DVD Status OFF Inertia Status OFF Profile(s) Summer and Winter Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080 Return Period(s) (years) 2, 30, 100 Climate Change (%) 0, 0, 30																																																																																																																			
WARNING: Half Drain Time has not been calculated as the structure is too full.																																																																																																																			
<table><tr><th>PN</th><th>US/MH Name</th><th>Storm</th><th>Return Period</th><th>Climate Change</th><th>First (X) Surchage</th><th>First (Y) Flood</th><th>First (Z) Overflow</th><th>Overflow Act.</th></tr><tr><td>1.000</td><td>S9</td><td>15 Winter</td><td>100</td><td>+30%</td><td>100/15 Summer</td><td>100/15 Winter</td><td></td><td></td></tr><tr><td>2.000</td><td>S79</td><td>30 Winter</td><td>100</td><td>+30%</td><td>100/15 Summer</td><td>100/15 Winter</td><td></td><td></td></tr><tr><td>1.001</td><td>S8</td><td>30 Winter</td><td>100</td><td>+30%</td><td>30/15 Winter</td><td></td><td></td><td></td></tr><tr><td>1.002</td><td>S16</td><td>30 Winter</td><td>100</td><td>+30%</td><td>30/15 Summer</td><td>100/30 Winter</td><td></td><td></td></tr><tr><td>3.000</td><td>S67</td><td>30 Winter</td><td>100</td><td>+30%</td><td>100/15 Summer</td><td></td><td></td><td></td></tr><tr><td>1.003</td><td>S68</td><td>30 Winter</td><td>100</td><td>+30%</td><td>30/15 Summer</td><td></td><td></td><td></td></tr><tr><td>1.004</td><td>S3</td><td>30 Winter</td><td>100</td><td>+30%</td><td>30/15 Summer</td><td></td><td></td><td></td></tr><tr><td>4.000</td><td>S24</td><td>30 Winter</td><td>100</td><td>+30%</td><td>100/15 Summer</td><td></td><td></td><td></td></tr><tr><td>4.001</td><td>S25</td><td>30 Winter</td><td>100</td><td>+30%</td><td>30/15 Summer</td><td></td><td></td><td></td></tr><tr><td>1.005</td><td>S42</td><td>30 Winter</td><td>100</td><td>+30%</td><td>30/15 Summer</td><td></td><td></td><td></td></tr><tr><td>1.006</td><td>HW6</td><td>30 Winter</td><td>100</td><td>+30%</td><td>30/15 Summer</td><td></td><td></td><td></td></tr></table>								PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	1.000	S9	15 Winter	100	+30%	100/15 Summer	100/15 Winter			2.000	S79	30 Winter	100	+30%	100/15 Summer	100/15 Winter			1.001	S8	30 Winter	100	+30%	30/15 Winter				1.002	S16	30 Winter	100	+30%	30/15 Summer	100/30 Winter			3.000	S67	30 Winter	100	+30%	100/15 Summer				1.003	S68	30 Winter	100	+30%	30/15 Summer				1.004	S3	30 Winter	100	+30%	30/15 Summer				4.000	S24	30 Winter	100	+30%	100/15 Summer				4.001	S25	30 Winter	100	+30%	30/15 Summer				1.005	S42	30 Winter	100	+30%	30/15 Summer				1.006	HW6	30 Winter	100	+30%	30/15 Summer			
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.																																																																																																											
1.000	S9	15 Winter	100	+30%	100/15 Summer	100/15 Winter																																																																																																													
2.000	S79	30 Winter	100	+30%	100/15 Summer	100/15 Winter																																																																																																													
1.001	S8	30 Winter	100	+30%	30/15 Winter																																																																																																														
1.002	S16	30 Winter	100	+30%	30/15 Summer	100/30 Winter																																																																																																													
3.000	S67	30 Winter	100	+30%	100/15 Summer																																																																																																														
1.003	S68	30 Winter	100	+30%	30/15 Summer																																																																																																														
1.004	S3	30 Winter	100	+30%	30/15 Summer																																																																																																														
4.000	S24	30 Winter	100	+30%	100/15 Summer																																																																																																														
4.001	S25	30 Winter	100	+30%	30/15 Summer																																																																																																														
1.005	S42	30 Winter	100	+30%	30/15 Summer																																																																																																														
1.006	HW6	30 Winter	100	+30%	30/15 Summer																																																																																																														
©1982-2020 Innovyze																																																																																																																			

RPS Group Plc		Page 20
Noble House, Capital Drive Linford Wood Miltlton Keynes, MK14 6QP	Hill Helicopters Blythe Bridge Staffs	
Date 29/10/2022 File AAC5895 SITE 3D AREA 1 ...	Designed by SAS Checked by	
Innovyze	Network 2020.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
1.000	S9	155.898	1.064	8.105	1.07		279.5	FLOOD
2.000	S79	155.742	1.207	7.506	0.76	12	64.8	FLOOD
1.001	S8	155.820	1.317	0.000	1.12		276.8	FLOOD RISK
1.002	S16	155.680	1.353	0.025	1.27		301.7	FLOOD
3.000	S67	155.540	0.558	0.000	0.08		13.0	SURCHARGED
1.003	S68	155.529	1.327	0.000	1.48		373.4	SURCHARGED
1.004	S3	155.063	1.086	0.000	2.19		418.0	FLOOD RISK
4.000	S24	154.785	0.515	0.000	0.02		1.6	FLOOD RISK
4.001	S25	154.787	0.810	0.000	0.06		3.7	SURCHARGED
1.005	S42	154.792	0.869	0.000	2.30		411.0	SURCHARGED
1.006	HW6	154.551	0.676	0.000	2.20		403.6	SURCHARGED

PN	US/MH Name	Level Exceeded
1.000	S9	3
2.000	S79	2
1.001	S8	
1.002	S16	1
3.000	S67	
1.003	S68	
1.004	S3	
4.000	S24	
4.001	S25	
1.005	S42	
1.006	HW6	

RPS Group Plc

Noble House, Capital Drive
Linford Wood
Miltton Keynes, MK14 6QP

Date 29/10/2022
File AAC5895 SITE 3D AREA 1 ...

Hill Helicopters
Blythe Bridge
Staffs

Designed by SAS
Checked by

Page 21



Innovyze

Network 2020.1

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
5.000	S17	15 Winter	100	+30%	100/15 Winter			
5.001	S18	15 Winter	100	+30%	100/15 Summer			
5.002	S19	15 Winter	100	+30%	100/15 Summer			
6.000	S76	15 Winter	100	+30%				
5.003	S77	15 Winter	100	+30%	100/15 Summer			
5.004	HW3	960 Winter	100	+30%	100/15 Summer			
7.000	S70	960 Winter	100	+30%				
7.001	S71	960 Winter	100	+30%				
7.002	S72	960 Winter	100	+30%	100/240 Winter			
8.000	S74	960 Winter	100	+30%				
8.001	S78	960 Winter	100	+30%	100/180 Winter			
7.003	S73	960 Winter	100	+30%	100/180 Winter			
7.004	S75	960 Winter	100	+30%	100/120 Winter			
9.000	S21	15 Winter	100	+30%	30/15 Summer	100/15 Summer		
9.001	S63	15 Summer	100	+30%	30/15 Summer			
9.002	HW2	15 Summer	100	+30%	30/15 Summer			
5.005	HW4	960 Winter	100	+30%	100/120 Winter			
5.006	S26	960 Winter	100	+30%	30/15 Summer			
5.007	S12	15 Winter	100	+30%	30/15 Winter			
10.000	S59	15 Winter	100	+30%	100/15 Summer			
10.001	S60	15 Winter	100	+30%	100/15 Summer			
5.008	S61	15 Winter	100	+30%	30/15 Summer			
5.009	S13	15 Winter	100	+30%	30/15 Summer			
5.010	S14	15 Winter	100	+30%	30/15 Summer			
11.000	S35	15 Winter	100	+30%	100/15 Summer	100/15 Summer		
11.001	S36	15 Winter	100	+30%	30/15 Winter			
12.000	S39	15 Winter	100	+30%	30/15 Winter			
13.000	S65	15 Winter	100	+30%	30/15 Summer			
12.001	S64	15 Winter	100	+30%	30/15 Summer			
11.002	S40	15 Winter	100	+30%	30/15 Summer			
14.000	S66	15 Winter	100	+30%	30/15 Summer	100/15 Summer		
14.001	S41	15 Winter	100	+30%	30/15 Summer			
11.003	S37	15 Winter	100	+30%	30/15 Summer			
5.011	S38	15 Winter	100	+30%	30/15 Summer			
5.012	HW5	30 Winter	100	+30%	30/15 Summer			
15.000	S27	960 Winter	100	+30%	100/120 Winter			
15.001	HW7	960 Winter	100	+30%	30/30 Summer			
1.007	HW8	60 Winter	100	+30%	30/15 Winter			
1.008	S23	60 Winter	100	+30%	2/15 Summer			
1.009	S6	8640 Winter	100	+30%				

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
5.000	S17	155.792	0.002	0.000	0.03		1.8	SURCHARGED
5.001	S18	155.793	0.157	0.000	1.20		78.6	SURCHARGED

©1982-2020 Innovyze

RPS Group Plc		Page 22
Noble House, Capital Drive Linford Wood Miltlton Keynes, MK14 6QP	Hill Helicopters Blythe Bridge Staffs	
Date 29/10/2022 File AAC5895 SITE 3D AREA 1 ...	Designed by SAS Checked by	
Innovyze	Network 2020.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m ³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
5.002	S19	155.621	0.118	0.000	1.23		73.5	SURCHARGED
6.000	S76	155.521	-0.042	0.000	0.03		1.1	OK
5.003	S77	155.526	0.084	0.000	1.28		72.3	SURCHARGED
5.004	HW3	155.496	0.097	0.000	0.10		5.0	SURCHARGED
7.000	S70	155.495	-0.063	0.000	0.00		0.0	OK
7.001	S71	155.495	-0.019	0.000	0.00		0.0	OK
7.002	S72	155.495	0.059	0.000	0.00		0.0	SURCHARGED
8.000	S74	155.495	-0.017	0.000	0.00		0.0	OK
8.001	S78	155.495	0.094	0.000	0.00		0.0	SURCHARGED
7.003	S73	155.496	0.085	0.000	0.06		2.9	SURCHARGED
7.004	S75	155.496	0.101	0.000	0.05		2.9	SURCHARGED
9.000	S21	156.251	0.802	0.955	2.66		213.8	FLOOD
9.001	S63	155.954	0.536	0.000	2.74		212.7	FLOOD RISK
9.002	HW2	155.655	0.264	0.000	2.79		213.1	SURCHARGED
5.005	HW4	155.496	0.121	0.000	0.01		1.3	SURCHARGED
5.006	S26	155.495	0.165	0.000	0.00		1.5	SURCHARGED
5.007	S12	155.435	1.156	0.000	0.15		20.8	SURCHARGED
10.000	S59	155.486	0.599	0.000	0.35		22.9	SURCHARGED
10.001	S60	155.459	0.834	0.000	0.32		24.5	SURCHARGED
5.008	S61	155.439	1.213	0.000	0.46		52.7	SURCHARGED
5.009	S13	155.430	1.242	0.000	0.88		141.5	SURCHARGED
5.010	S14	155.165	1.253	0.000	1.05		141.4	FLOOD RISK
11.000	S35	156.105	1.550	5.568	1.60		313.5	FLOOD
11.001	S36	155.919	1.499	0.000	1.01		424.1	FLOOD RISK
12.000	S39	155.851	1.497	0.000	0.49		17.6	SURCHARGED
13.000	S65	155.836	1.543	0.000	0.64		19.2	SURCHARGED
12.001	S64	155.817	1.563	0.000	1.27		37.9	FLOOD RISK
11.002	S40	155.762	1.549	0.000	1.25		418.9	FLOOD RISK
14.000	S66	156.202	1.866	2.272	1.84		143.4	FLOOD
14.001	S41	155.768	1.616	0.000	1.76		204.4	SURCHARGED
11.003	S37	155.526	1.461	0.000	2.11		648.2	SURCHARGED
5.011	S38	155.084	1.099	0.000	2.94		787.2	FLOOD RISK
5.012	HW5	154.504	0.554	0.000	2.10		701.1	FLOOD RISK
15.000	S27	154.261	0.311	0.000	0.01		3.6	SURCHARGED
15.001	HW7	154.261	0.361	0.000	0.03		3.6	SURCHARGED
1.007	HW8	154.365	0.491	0.000	0.05		15.1	SURCHARGED
1.008	S23	154.390	0.925	0.000	0.20		7.4	SURCHARGED
1.009	S6	153.139	-0.150	0.000	0.25		7.4	OK

PN	US/MH Name	Level Exceeded
5.000	S17	
5.001	S18	
5.002	S19	
6.000	S76	