


Key




Proposed selected standard tree planting including stake and lvs.



Proposed selected 11/2 standard tree planting including stake and lvs.



Proposed hedge planting including 60mm depth no-fines bark mulch.




Proposed native whip planting with spiral rabbit guards including 60mm depth bark mulch.




Proposed areas to be turfed with cultivated grade turf.




Proposed areas to be seeded using Germinall seeds A19 mix to their specification.



Proposed Wildflower grass seed areas to be seeded using Emorsgate Meadow Mix EMZ to their specification.



Proposed Wildflower grass seed areas to be seeded using Emorsgate Pond Edge Mix EP1 to their specification.



Proposed areas of 60mm depth gravel laid over weed suppressing membrane.



Proposed erosion protection (granite setts) with dense shrub planting.

NOTE
To be read with Landscape Specification LDS17/C/L/S

REV C: Revised inline with Site Plan 01204-AL/023-H AKL 03/05/23

REV B: Attenuation basins revised to incorporate erosion protection measures. AKL 05/01/23

REV A: Attenuation basins revised and planting altered inline with Local Authority comments. 21/11/22



Landscape Design Solutions (NI) Ltd

100-102, The Old Mill, Mill Lane, Millbrook, Co. Wick, Ireland

01 977 7777

info@ldsdesignsolutions.com

Client

Mairden Homes

Project

Telford Lane, Upper Team

Drawing title

Planting Plan 2 of 2

Scale

1:250 @ A0

Drawn by

AKL

Date

Oct 2022

Drawing No.

LDS517-02C