

MANHOLE SCHEDULES – STORM SEWERS

MH REF	COVER LEVEL	INVERT LEVEL	DEPTH TO SOFFIT	PIPE NUMBER	PIPE DIA	PIPE LENGTH	PIPE MATERIAL	PIPE SLOPE (1:X)	MH TYPE	MH DIA	COVER GRADE	EASTING	NORTHING	COMMENT
S4	135.000	133.000	1.775	1.002	225	15.641	uPVC	195.5	TYPE B	1200	D400	401359.652	339190.318	
S5	136.300	132.920	3.155	1.003	225	21.400	uPVC	194.5	TYPE A	1200	D400	401359.663	339174.677	
S6	137.700	132.810	4.665	1.004	225	19.482	uPVC	194.8	TYPE A	1200	D400	401359.672	339153.277	
S7	137.700	132.710	4.765	1.005	225	45.751	uPVC	198.9	TYPE A	1200	D400	401359.675	339133.795	
S8	135.400	132.405	2.695	1.006	300	18.422	uPVC	204.7	TYPE B	1200	D400	401388.572	339098.324	
S9	135.100	132.315	2.485	1.007	300	6.356	uPVC	158.9	TYPE B	1200	D400	401384.251	339080.416	
S10	134.900	132.275	2.325	1.008	300	24.488	uPVC	204.1	TYPE B	1200	D400	401390.606	339080.330	
S11	134.100	132.155	1.645	1.009	300	19.050	uPVC	37.7	TYPE B	1200	D400	401390.615	339055.842	
S12	133.450	131.650	1.500	1.010	300	17.512	uPVC	38.9	TYPE B	1200	D400	401390.617	339036.792	
S13	133.000	131.200	1.500	1.011	300	11.521	uPVC	46.1	TYPE B	1200	D400	401399.874	339021.926	
S14	132.750	130.950	1.500	1.012	300	9.685	uPVC	48.4	TYPE B	1200	D400	401393.018	339012.469	
S15	132.550	130.750	1.500	1.013	300	31.567	uPVC	14.7	TYPE B	1200	D400	401386.723	339019.830	
S19	132.200	128.680	3.220	2.000	300	21.386	uPVC	213.9	TYPE A	1200	D400	401326.661	339043.326	
S20	132.200	128.580	3.320	2.001	300	36.811	uPVC	204.5	TYPE A	1200	D400	401338.472	339025.497	
S16	131.800	128.325	3.100	1.014	375	14.383	uPVC	239.7	TYPE B	1200	D400	401363.472	338998.478	
S17	131.600	128.265	2.960	1.015	375	16.087	uPVC	247.5	TYPE B	1200	D400	401363.475	338984.095	
S18-HB	131.500	128.200	2.925	1.016	375	5.553	uPVC	17.4	TYPE B	1200	D400	401350.523	338974.553	

- GENERAL NOTES
1. CONTRACTOR TO CHECK ALL DIMENSIONS AND REPORT ALL ERRORS AND OMISSIONS TO THE ENGINEER.
 2. ANY DISCREPANCY TO BE REPORTED IMMEDIATELY TO THE ENGINEER.
 3. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SUBCONTRACTORS AND SPECIALISTS DRAWINGS AND SPECIFICATIONS.

C	UPDATED INVERT LEVELS FOR S16–S20	AJ	05.01.23
B	UPDATED TO SUIT LATEST SITE LAYOUT	AJ	31.10.22
A	REMOVED 'DO NOT SCALE' NOTE	TE	07.07.22
Rev.	Detail	By	Date

Revisions

Reinforcement schedules nos.



Structural & Civil Engineering Consultants

First Floor
7 St James Crescent
Swansea
SA1 6DP

Telephone +44 1792 473 182
e-mail admin@cb3consult.co.uk
web www.cb3consult.co.uk

Client



Project

PROPOSED RESIDENTIAL DEVELOPMENT AT UTTOXETER ROAD, UPPER TEAN

Drawing Title

STORM WATER MANHOLE SCHEDULE

PRELIMINARY

Project No. C1941		Drawing No. C–SK08	
Scales –		Date 29.04.22	Revision
Drawn DH	Checked DF	Sheet Size A3	C