

MANHOLE SCHEDULES – STORM SEWERS

| MH REF | COVER LEVEL | INVERT LEVEL | DEPTH TO SOFFIT | PIPE NUMBER | PIPE DIA | PIPE LENGTH | PIPE MATERIAL | PIPE SLOPE (1:X) | MH TYPE | MH DIA | COVER GRADE | COMMENT |
|--------|-------------|--------------|-----------------|-------------|----------|-------------|---------------|------------------|---------|--------|-------------|---------|
| S4     | 135.000     | 133.000      | 1.700           | 1.002       | 300      | 15.621      | uPVC          | 195              | TYPE B  | 1200   | D400        |         |
| S5     | 136.300     | 132.920      | 3.080           | 1.003       | 300      | 21.400      | uPVC          | 192              | TYPE A  | 1200   | D400        |         |
| S6     | 137.700     | 132.810      | 4.665           | 1.004       | 300      | 19.482      | uPVC          | 194              | TYPE A  | 1200   | D400        |         |
| S7     | 137.700     | 132.710      | 4.690           | 1.005       | 300      | 45.751      | uPVC          | 152              | TYPE A  | 1200   | D400        |         |
| S8     | 135.400     | 132.405      | 2.695           | 1.006       | 300      | 15.654      | uPVC          | 173              | TYPE B  | 1200   | D400        |         |
| S9     | 135.100     | 132.315      | 2.485           | 1.007       | 300      | 8.917       | uPVC          | 222              | TYPE B  | 1200   | D400        |         |
| S10    | 134.900     | 132.275      | 2.325           | 1.008       | 300      | 22.619      | uPVC          | 188              | TYPE B  | 1200   | D400        |         |
| S11    | 134.100     | 132.155      | 1.645           | 1.009       | 300      | 19.012      | uPVC          | 37               | TYPE B  | 1200   | D400        |         |
| S12    | 133.450     | 131.650      | 1.500           | 1.010       | 300      | 13.523      | uPVC          | 30               | TYPE B  | 1200   | D400        |         |
| S13    | 133.000     | 131.200      | 1.500           | 1.011       | 750      | 50.426      | uPVC          | 46.1             | TYPE B  | 1200   | D400        |         |
| S19    | 132.200     | 128.680      | 3.220           | 2.000       | 300      | 19.956      | uPVC          | 213.9            | TYPE A  | 1200   | D400        |         |
| S20    | 132.200     | 128.580      | 3.320           | 2.001       | 300      | 36.411      | uPVC          | 204.5            | TYPE A  | 1200   | D400        |         |
| S16    | 131.800     | 128.325      | 3.100           | 1.014       | 375      | 15.058      | uPVC          | 239.7            | TYPE A  | 1200   | D400        |         |
| S17    | 131.600     | 128.265      | 2.960           | 1.015       | 375      | 19.438      | uPVC          | 247.5            | TYPE B  | 1200   | D400        |         |
| S18-HB | 131.500     | 128.200      | 2.925           | 1.016       | 375      | 7.315       | uPVC          | 17.4             | TYPE B  | 1200   | D400        |         |

GENERAL NOTES

1. CONTRACTOR TO CHECK ALL DIMENSIONS AND REPORT ALL ERRORS AND OMISSIONS TO THE ENGINEER.

2. ANY DISCREPANCY TO BE REPORTED IMMEDIATELY TO THE ENGINEER.

3. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SUBCONTRACTORS AND SPECIALISTS DRAWINGS AND SPECIFICATIONS.

|      |                                    |     |          |
|------|------------------------------------|-----|----------|
| E    | UPDATED TO SUIT LATEST SITE LAYOUT | MDK | 21.09.23 |
| D    | UPDATED TO SUIT LATEST SITE LAYOUT | CG  | 15.09.23 |
| C    | UPDATED INVERT LEVELS FOR S16–S20  | AJ  | 05.01.23 |
| B    | UPDATED TO SUIT LATEST SITE LAYOUT | AJ  | 31.10.22 |
| A    | REMOVED 'DO NOT SCALE' NOTE        | TE  | 07.07.22 |
| Rev. | Detail                             | By  | Date     |

Revisions

Reinforcement schedules nos.



Structural & Civil Engineering Consultants

First Floor  
7 St James Crescent  
Swansea  
SA16DP

Telephone +44 1792 473 182  
e-mail admin@cb3consult.co.uk  
web www.cb3consult.co.uk

Client



Project

PROPOSED RESIDENTIAL DEVELOPMENT AT UTTOXETER ROAD, UPPER TEAN

Drawing Title

STORM WATER MANHOLE SCHEDULE

PRELIMINARY

|                      |               |                       |          |
|----------------------|---------------|-----------------------|----------|
| Project No.<br>C1941 |               | Drawing No.<br>C–SK08 |          |
| Scales<br>–          |               | Date<br>29.04.22      | Revision |
| Drawn<br>DH          | Checked<br>DF | Sheet Size<br>A3      | E        |