

MANHOLE SCHEDULES – FOUL SEWERS

MH REF	COVER LEVEL	INVERT LEVEL	DEPTH TO SOFFIT	PIPE NUMBER	PIPE DIA	PIPE LENGTH	PIPE MATERIAL	PIPE SLOPE (1:X)	MH TYPE	MH DIA	COVER GRADE	EASTING	NORTHING	COMMENT
F1	134.800	133.800	0.900	1.000	100	19.357	uPVC	71.7	TYPE E	450	D400	401313.892	339156.895	
F2	136.400	133.530	2.770	1.001	100	19.119	uPVC	59.7	TYPE B	1200	D400	401333.203	339155.573	
F3	137.650	133.210	4.290	1.002	150	18.374	uPVC	131.2	TYPE A	1200	D400	401349.988	339146.419	
F4	137.800	133.070	4.580	1.003	150	51.024	uPVC	137.9	TYPE A	1200	D400	401362.625	339133.079	
F15	135.750	132.830	2.820	2.000	100	8.031	uPVC	61.8	TYPE B	1200	D400	401395.710	339093.412	
F5	135.600	132.700	2.750	1.004	150	16.897	uPVC	120.7	TYPE B	1200	D400	401388.808	339089.285	
F6	135.100	132.560	2.390	1.005	150	6.850	uPVC	137	TYPE B	1200	D400	401374.305	339080.615	
F7	134.850	132.510	2.190	1.006	150	20.558	uPVC	31.4	TYPE B	1200	D400	401372.711	339073.953	
F8	134.150	131.855	2.145	1.007	150	19.284	uPVC	38.2	TYPE B	1200	D400	401382.988	339056.147	
F9	133.500	131.350	2.000	1.008	150	16.717	uPVC	37.1	TYPE B	1200	D400	401393.013	339039.674	
F16	134.100	131.600	2.400	3.000	100	52.635	uPVC	75.2	TYPE B	1200	D400	401446.122	339052.427	
F10	133.000	130.900	1.950	1.009	150	51.279	uPVC	65.7	TYPE B	1200	D400	401401.153	339025.073	
F13	131.200	130.120	0.930	1.012	150	25.390	uPVC	131.3	TYPE D	600	D400	401357.163	338998.721	
F14	131.300	129.930	1.220	1.013	150	12.452	uPVC	135.1	TYPE C	1220x685	D400	401370.292	338976.964	

GENERAL NOTES

1. CONTRACTOR TO CHECK ALL DIMENSIONS AND REPORT ALL ERRORS AND OMISSIONS TO THE ENGINEER.

2. ANY DISCREPANCY TO BE REPORTED IMMEDIATELY TO THE ENGINEER.

3. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SUBCONTRACTORS AND SPECIALISTS DRAWINGS AND SPECIFICATIONS.

D	UPDATED TO SUIT LATEST SITE LAYOUT AND INCLUDED LOCATION	MDK	13.10.23
C	UPDATED TO SUIT LATEST SITE LAYOUT	CG	15.09.23
B	UPDATED TO SUIT LATEST SITE LAYOUT	AJ	31.10.22
A	REMOVED 'DO NOT SCALE' NOTE	TE	07.07.22
Rev.	Detail	By	Date

Revisions

Reinforcement schedules nos.



Structural & Civil Engineering Consultants

First Floor
7 St James Crescent
Swansea
SA1 6DP

Telephone +44 1792 473 182
e-mail admin@cb3consult.co.uk
web www.cb3consult.co.uk

Client



Project

PROPOSED RESIDENTIAL
DEVELOPMENT AT
UTTOXETER ROAD,
UPPER TEAN

Drawing Title

FOUL WATER
MANHOLE SCHEDULE

PRELIMINARY

Project No. C1941		Drawing No. C–SK07	
Scales –		Date 29.04.22	Revision
Drawn DH	Checked DF	Sheet Size A3	D