

LEVEL CHANGES UPPER TEAN			Lower or no change	29 Plots	
	Approved levels Rev C	Proposed levels Rev O	Higher	11 Plots	
PLOTS			DIFFERENCE in mm	Summary	Comments
1	165.42	167.60	-2.18	Higher	Levels increased at lower part of site to balance the site and reduce height and visible impact of masonry garden retaining walls
2	164.52	166.60	-2.08	Higher	
3	164.52	166.60	-2.08	Higher	
4	163.52	165.30	-1.78	Higher	
5	163.52	165.30	-1.78	Higher	
6	161.45	162.80	-1.35	Higher	
7	162.15	163.45	-1.30	Higher	
8	162.75	164.05	-1.30	Higher	
9	163.20	164.35	-1.15	Higher	
10	165.65	166.85	-1.20	Higher	
11	167.25	167.15	0.10	Lower	Levels reduced at highest existing ground level of site to balance and reduce impact of height of proposed masonry retaining walls
12	168.25	168.00	0.25	Lower	
13	169.50	168.39	1.11	Lower	
14	169.50	168.39	1.11	Lower	
15	171.15	169.59	1.56	Lower	
16	171.97	169.95	2.02	Lower	
17	170.60	170.60	0.00	No Change	
18	171.90	171.45	0.45	Lower	
19	171.90	170.75	1.15	Lower	
20	171.00	170.75	0.25	Lower	
21	171.00	169.75	1.25	Lower	
22	169.62	169.75	-0.13	Higher	
23	169.63	168.75	0.88	Lower	
24	169.60	168.75	0.85	Lower	
25	171.70	171.70	0.00	No Change	Levels no match approved Rev C - no change.
26	170.80	170.80	0.00	No Change	
27	169.90	169.90	0.00	No Change	
28	167.45	167.45	0.00	No Change	
29	167.45	167.45	0.00	No Change	
30	167.45	167.45	0.00	No Change	
31	166.65	166.65	0.00	No Change	House type changed to bungalows to reduce the impact of Tenford Lane residents from previously approved. No level change from approved C. There is a very minor increase on plot 38. The bungalows have removed 40 habitable room windows and reducing 1st floor height with roof
32	166.50	166.50	0.00	No Change	
33	166.50	166.50	0.00	No Change	
34	166.50	166.50	0.00	No Change	
35	166.50	166.50	0.00	No Change	
36	166.35	166.35	0.00	No Change	
37	164.42	164.42	0.00	No Change	
38	164.40	164.42	-0.02	Higher	
39	161.60	161.60	0.00	No Change	
40	160.50	160.50	0.00	No Change	

