

North

Footprint Total
Four Holiday Lodges
raised off ground
on screw piles 377 m2

Total Aggregate and Lodges
ie unsealed unvegetated is
 $377 + 564 = 941\text{m}^2$

Free draining aggregate:
Sitting areas and paths 156m2
8 car parking bays 100m2
Driveway and Turning 308m2
Total aggregate areas 564m2

Creation of new
woodland area
277 m2

Enhance existing
grassland by seeding
with wild flowers

existing
bus stop
and shelter

A523 Ashbourne Road

Hedging
Mixed hedge of
Crataegus monogyna
Rosa canina
Prunus padus
Ligustrum vulgare
Prunus spinosa

Distance apart for
bare root plants
5 - 7 per m
(60-80cm ht plants)

Create new hedge
in mixed species

Enhance existing
grassland by seeding
with wild flowers

Tree Planting and Maintenance

Planting and years 1 - 2
Trees to be planted from pots, provide 1.5 m stakes fastened minimum 0.5 m into ground, and tree ties at 0.5 and 1.0 m high. Keep a 1 metre diameter around the tree clear of weeds and grass for the first 2-3 years to reduce competition for moisture and nutrients. Provide tree guards to height of 0.6m.
Suppress weeds with mulch (bark chips). Apply it to a depth of around 10cm
Check tree guards and stakes are upright and pushed firmly into the soil.
Pull up any grass growing inside the guard and carefully replace the guard.

Year 3-10
Remove tree guards
Remove guards as soon as they split and before they start to disintegrate (usually after 5-10 years). Dispose of the plastics responsibly to protect local wildlife. Recycle where facilities exist.
Pruning
This is not essential but will encourage trees to grow upwards rather than outwards once established and help to create a diverse canopy structure. Most native trees are best pruned in winter when dormant. However, species such as cherry and walnut need pruning in summer to reduce risk of disease and sap bleeding.

Legend
Existing Tree 
Proposed Tree 

There are 73 existing trees and saplings on site, (within the red line) so it is proposed to give a 100% uplift by planting 75 No. standards, in the positions shown and create a mixed woodland area. These will be 14 No Field Maple (*Acer campestre*) 14 No English Oak (*Quercus robur*), 16 No Evergreen Scots Pine (*Pinus Sylvestris*) 17 No Rowan (*Sorbus aucuparia*) and 14 No Blackthorne (*prunus spinosa*). The first two are chosen because they offer great general biodiversity, and the rowan offers berries for birds, and the blackthorne sloe fruit for general feeding. The existing grassland will be enhanced as shown through the sowing of wild flowers. Also, night scented stock such as Jasmine and Honeysuckle will be planted in between which attracts moths, which in turn attract bats. Bat boxes can be hung on the rear of the lodges.

Creation of new
woodland area
1105 m2 including
existing trees of which
627m2 created by
new planting

Manager's
Lodge 1 bed

Outline of Site
for concurrent
application for
Manager's Lodge

Existing tarmac in
Holiday Lodge
Application
174 m2

existing
car park

The Green
Man

B5053 Bottom Lane

Scale 1:200 @A1

0 2 4 6 8 10 metres

Project Lodge Project
The Green Man
Bottomhouse, Leek

Title © Pinelog Ltd
Proposed Site Plan A1

Client Peak Venues
Scale 1:200 @A1 Date July 2024 Drawn RL
Job no. Peak 7/22 D01 Rev A

Preliminary	client	Signed and Dated Approved
Planning	internal	
Built/Control	internal	
Construction	contracts	
As Built	internal	

 pinelog
Pinelog Limited
Pinelog Works, Sheepbridge Lane
Chesterfield S41 9FE
Tel: (01629) 814481
Fax: (01629) 814634
www.pinelog.co.uk