



For the attention of: Mr H Wood at Staffordshire CC, Flood Risk

Dear Henry,

## **Moneystone Outfall Application DOC/2024/0028. Lead Local Flood Authority Planning Application Response**

Further Following my discussion with Mr Wood at Staffordshire CC (SCC) Flood Risk Management I am please to respond as follows. As set out in Condition 13 for Application DOC/2024/0028 there is a need to have approved the future maintenance and operation of the outfall.

The proposed outfall is a straight cut with no manmade structural elements to maintain. No flow restriction elements are included on the outfall arrangement as this would contravene EA Reservoir restrictions. However, it is accepted that floating debris from the lake or degradation of the cutting sides could partly block the channel and would from time to time need inspection and removal.

Our response to Condition 4, within Table 2, directly determines the type and frequency of monitoring, **and therefore maintenance**, of the outfall. Our current remit is to continue monitoring the stream and outfall during and post construction as per the Table 2 requirements and where necessary arrange for contractors to remove any obstructions etc that may occur.

We trust these proposals meet the Condition 13 requirements but please do not hesitate to contact myself if further clarification is required.

Yours Sincerely

Peter Lloyd