



Key

- Existing hedgerow retained
- Existing trees
- Proposed ornamental shrub planting, including 60mm depth no-fines bark mulch.
- Proposed hedge planting, including 60mm depth no-fines bark mulch.
- Proposed Standard tree planting including stake and tie.
- Proposed native shrub planting, including 60mm depth bark mulch.
- Proposed areas to be turfed with cultivated grade turf.
- Proposed areas to be seeded using Germinal seeds grass mix A19 (Amenity Areas) to their specification.
- Proposed areas to be seeded using Germinal seeds grass mix A4 (Attenuation Basins) to their specification.
- Proposed areas to be seeded using locally sourced hay/seed from similar site suitable for damp meadows and clay soils.
- Proposed areas of 50mm depth gravel laid over weed suppressing membrane.
- Log piles

Reproduced by permission of Ordnance Survey on behalf of Her Majesty's Stationery Office.
© Crown Copyright and database right 2010. All rights reserved.

01	Revised to clients comments	KS/AG	GA	16.09.24
Rev	Description	Drawn	Approved	Date

TEP

THE ENVIRONMENT PARTNERSHIP

401 Faraday Street, Birchwood Science Park, Warrington WA3 6GA
Tel 01925 844004 e-mail tep@tep.uk.com www.tep.uk.com

Project no.	Project name
10551	Ayr Road

Stage
RIBA Stage 3
Status
For planning
Title
Planting Plan (Sheet 3)

Drawing no.
D10551.203

Scale	Date	Rev
1:250 @ A0	06.06.2024	01
Drawn	Checked	Approved
EF/AG	KS	GA