

Rev.	Drawn	Comments	Date
A	KEW	Planting notes & lighting added	29.08.25
B	KEW	Boundary wall elevations added	11.12.25

Planting Notes

Topsail to Planting Areas

[illegible]

Cultivation

[illegible]

Planting

Canopy opening while soil and weather conditions are suitable. Do not plant during periods of frost, rain or strong winds. All plants and trees to be planted in accordance with the criteria as stated in BS 9396. All plants to be planted in upright, wellbalanced and with best side to front. All plants to be planted in holes excavated large enough to allow adequate root spread to a depth of minimum 25mm lower than the root system.

Trees to be 14-16cm girth (EHS) rootballed or container grown and square stocke using appropriate (bonded softwood and appropriate rubber biodegradable ties).

All plant and tree shrubs to be maintained for a minimum period of 5 years following planting. Any losses to be replaced like-for like during the next suitable planting. On completion of planting remove any back damaged twigs and shorter back trees or shrubs as necessary to compensate for any root reduction.

Works to Existing Trees:

Any pruning and tree removal works to be carried out to avoid nesting season (1st March to 31st August) must be carried out in accordance with the following conditions:

- All works to be carried out by a qualified arboriculturist. Existing trees to be pruned back to improve shape and stability. Trees to be thinned to allow retained trees and new native trees to flourish.
- All works to be approved by the local authority prior to commencement.
- Existing retained trees to be protected in accordance with BS 5837.

KEY

Shrubs -
T/SF -
1/7D -
Ficus Dornesicu
Sorbus Fastigiata
Mixture of suitable native planting such as Lavender Hidcole

Hedge Planning
plant material to comply with BS 3036 Pt 1:1997 and handled in accordance






with 'Handling'

Cultivate compacted ground and apply herbicide to kill weeds with herbicide to at least 0.5m width. Do not allow roots to dry out during prior to planting or heat up in enclosed boxes. Form a trench to the same depth as the roots, plant so that the finished topsoil level matches the level of the soil it was planted in. The nursery, firm plants in place and cover with well-rotted mulch and topsoil. Provide plastic free guards for protection young plants.

Species	Specification	% of mix	No.	Pail
<i>Cidalegus monogyra</i>	60 - 80 cms bore root	100 %	63	4

Native Hedge

New hedge (approximately 19 m in total) to be planted at 300mm centres



Boundary Treatments 1:100

Client
Mr T Boote

Project Conversion of Listed Barn A into Dwelling to Catswall Farm,

HUMPHREY LAITE, DALLIDA, 3113 / JN

External Works

Site Plan as Proposed Barn A - Dwelling

Planning

NOV 2023

Scale @A1 As Stated

Project No.	Drawing No.
-------------	-------------

00101 PL(0)12

Rev