

Planting Schedule							
NATIVE SHRUB PLANTING							
Qty	Latin Name	Common Name	Height	Form	Container Size	Rate/Plants m²	%
25	Acer campestre	Field maple	80-100cm	Whip		1	20
37	Corylus avellana	Hazel, Cobnut	80-100cm	Whip		1	30
37	Crataegus monogyna	Common hawthorn	80-100cm	Whip		1	30
12	Ilex aquifolium	Holly	80-100cm	Container	ZL	1	10
12	Viburnum opulus	Guelder Rose	80-100cm	Whip		1	10
123							
STANDARD TREES							
Qty	Latin Name	Common Name	Height	Form	Root Condition	Clear Stem	Girth
6	Betula pendula	Silver Birch	350-400cm	Heavy Standard	RB	Min 200cm	12-14cm
2	Crataegus persimilis 'Splendens'	Frosted Hawthorn	350-400cm	Heavy Standard	RB	Min 200cm	12-14cm
1	Prunus avium	Wild Cherry	350-400cm	Heavy Standard	RB	Min 200cm	12-14cm
9							
MIXED NATIVE HEDGEROWS (planted double staggered, 5 plants lin/m)							
Qty	Latin Name	Common Name	Height	Form	Root Condition	%	
20	Acer campestre	Field maple	80-100cm	Whip	BR	5	
20	Corylus avellana	Hazel, Cobnut	80-100cm	Whip	BR	5	
300	Crataegus monogyna	Common hawthorn	80-100cm	Whip	BR	75	
40	Prunus spinosa	Blackthorn	80-100cm	Whip	BR	10	
20	Viburnum opulus	Guelder Rose	80-100cm	Whip	BR	5	
400							
BULB PLANTING							
Qty	Latin Name	Common Name	Rate/Plants m²				
236	Mixed Narcissus	Mixed Daffodil	10				



This drawing is the property of FPCR Environment and Design Ltd and is issued on the condition it is not reproduced, retained or disclosed to any unauthorised person, either wholly or in part without written consent of FPCR Environment and Design Ltd. Ordnance Survey base mapping - supplied by client.

N

Site Boundary

Retained Vegetation
(See AT2 Tree Surveys 'Tree Survey Plan')

Standard Tree Planting

Native Shrub Planting

Native Hedgerows
(Planted in a double staggered row, 5 plants lin/m)

Wildflower Grassland
(To be Emorsgate EM2 'Standard General Purpose Meadow Mixture')

Bulb Planting
(Planted 10 bulbs sq/m)

Notes:

- Standard trees to be double staked.

- Native shrub planting to be set out at 1 plant sq/m. All whip planting to be staked using canes and protected using spiral guard. Ilex to be protected using mesh gurards.

- Native Hedgerows to be set out in a double staggered row, 5 plants lin/m. All whip planting to be staked using canes and protected using spiral guard.

P02	04/12/2025	Draft stamp removed		CC	DH
rev	date	description		dm	chk
client					
Carta Real Estate					
project					
Co-op Werrington					
title					
LANDSCAPE PROPOSALS					
number					
13678-FPCR-XX-XX-DR-L-0001					
status					
53					
rev					
P02					