

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Conditions			Tree Constraints Information								Observations				
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
1H	Hazel, Holly & Hawthorn	75	B1	0.9	2.5	1.5	N/A	N/A	N/A	N/A	Mature	Good	Boundary hedgerow.	N/A	N/A
2T	Birch spp	310, 300	C1	5.2	84.2	6	3	2.5	2.5	3	Early-mature	Fair	Ivy obscures both stems.	N/A	N/A
3T	Birch spp	375	C1	4.5	63.6	6	3	3	2.5	3	Early-mature	Fair	Ivy obscures lower stem, canopy sparse.	N/A	N/A
4T	Birch spp	300, 280	C1	4.9	76.2	5	2	1.5	1.5	2.5	Semi-mature	Fair	Torn branch 2.5m south, branch stub remains.	N/A	N/A
5T	Hawthorn	250	C1	3.0	28.3	4	1.5	1.5	1	1	Semi-mature	Fair	Set within hedge, suppressed by birch to west.	N/A	N/A
6T	Pedunculate Oak	630	A1	7.6	179.6	8	5	5	5	5	Mature	Good	Minor deadwood in extremities of canopy, typical of age and species. Squat form. Moderate deadwood 3m south.	N/A	N/A
7T	Pedunculate Oak	720	B1	8.6	234.5	8	4	4.5	5.5	4	Mature	Fair	Stem cavities at 1m north, 3m north west, torn large diameter limb at 2m north.	N/A	N/A
8T	Pedunculate Oak	440	C1	5.3	87.6	6	2	3	5	4	Mature	Fair	Moderate deadwood at 2.5m south, branch stub 2m north.	N/A	N/A
9T	Pedunculate Oak	1250	A1	15.0	707.0	11	8	8	8	7	Over Mature	Good	Minor dead wood typical of age and species. Lower limbs historically crown raised to 6m north over field . Large diameter deadwood at 2m west. Large diameter limb removed at 4m north.	N/A	N/A
10T	Pedunculate Oak	600	B1	7.2	162.9	12	5	5	7	3	Mature	Fair	Flush cut 2.5m north west and 3m north. Minor deadwood throughout canopy.	N/A	N/A
11G	Crab Apple	180	C3	2.2	14.7	4	N/A	N/A	N/A	N/A	Mature	Good	Contributes to hedgerow boundary, historically laid.	N/A	N/A
12T	Pedunculate Oak	460	C1	5.5	95.7	8	3.5	3.5	3	2	Mature	Fair	Decay noted within lower stem south east, stem has prominent kink west.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Largely Overcast			Tree Constraints Information								Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)								
							N	E	S	W					
13T*	Pedunculate Oak	250, 275	C1	4.5	62.5	7.5	1.5	6	3	0.5	Mature	Fair	Canopy development suppressed.	N/A	N/A
14T	Pedunculate Oak	400	B1	4.8	72.4	9	3.5	4	3.5	4	Early-mature	Fair	Limbs reduced/cut by flail up to 4m, branch stubs remain. Limbs cut by flail east up to 4m stubs with etiolated new growth remain.	N/A	N/A
15T	Apple	250, 260	B1	4.3	58.9	4.5	2	1	1.5	2.5	Mature	Good	No significant defects recorded.	N/A	N/A
16T	Goat Willow	200	C1	2.4	18.1	6	2.5	2	2.5	2	Semi-mature	Fair	Tall etiolated growth form.	N/A	N/A
17T	Goat Willow	320	C1	3.8	46.3	9	1.5	3	4	4	Early-mature	Good	Supressed, torn small diameter limb at 3.5m west.	N/A	N/A
18T	Pedunculate Oak	600	A1	7.2	162.9	11	5	6	5.5	6	Mature	Good	Minor deadwood throughout canopy typical of age and species. Moderate diameter deadwood at 2m west.	N/A	N/A
19T	Pedunculate Oak	350	B1	4.2	55.4	10	3.5	3.5	3.5	3.5	Early-mature	Fair	No significant defects recorded.	N/A	N/A
20G	Holly	150	C3	1.8	10.2	8.5	N/A	N/A	N/A	N/A	Semi-mature	Fair	Short stretch of holly.	N/A	N/A
21T	Pedunculate Oak	550	C1	6.6	136.9	10	5	2.5	3	5	Mature	Fair	Large diameter torn limbs at 3m and 6m south, tall etiolated new growth.	N/A	N/A
22T	Pedunculate Oak	150	C1	1.8	10.2	6	2	2	2	2	Semi-mature	Fair	Suppressed.	N/A	N/A
23T	Pedunculate Oak	430	B1	5.2	83.7	10	2.5	3.5	5.5	4.5	Mature	Fair	Stem wound 0.5m and 1m west from wire fencing torn limb 3m north, large diameter deadwood at 2.5m north.	N/A	N/A
24T	Apple	430, 310	B1	6.4	127.1	8	3	2.5	4	3	Over Mature	Good	Stem bifurcates at ground level, decay seam on northern stem btw ground level and 0.5m east. Dense canopy.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1, 2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information			Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m					N	E	S	W					
25T	Pedunculate Oak	600, 580	B1	10.0	315.0	10	4	3.5	5	3.5	Mature	Good	Stem bifurcates at base. Lower limbs west cutback with flail, up to 6m.	N/A	N/A
26T	Goat Willow	100	C1	1.2	4.5	6	1	1	2	1	Young	Fair	No significant defects recorded.	N/A	N/A
27T	Pedunculate Oak	540	B1	6.5	131.9	10	4	3	4	4	Mature	Fair	Cavity at ground level south, hollowing of main stem, a natural part of aging process.	Monitor for change in condition over the long term	3
28T	Goat Willow	430	C1	5.2	83.7	8	3	3	5	3	Mature	Poor	Saprophytic fungi on the main stem west, bark delamination .	N/A	N/A
29T	Pedunculate Oak	660	A1	7.9	197.1	10	3.5	5	7	5	Mature	Good	Small stem cavity ground level west, reaction growth evident.	N/A	N/A
30T*	Birch spp	170	U	2.0	13.1	4	1	1	1	1	Semi-mature	Poor	Stem cavity at 2m west. Canopy development suppressed.	N/A	N/A
31T	Pedunculate Oak	470	B1	5.6	99.9	10	5	2.2	3	3	Mature	Fair	Stem kinks at ground level south, stem cavity at 9.5m north, torn limbs remain partially attached 7m west.	N/A	N/A
32T	Goat Willow	280	C1	3.4	35.5	7	3.5	2	2	2	Semi-mature	Fair	Set within self set hawthorn and rowan along ditch/field boundary hedgerow.	N/A	N/A
33T	Pedunculate Oak	590	U	7.1	157.5	8	1	1.5	2.5	1	Mature	Poor	Central leader dead, little viable/live canopy restricted to lower southern canopy. Does provide ecological value .	N/A	N/A
34T	Pedunculate Oak	550	B1	6.6	136.9	11	6	5	6	6	Mature	Good	Tear out wounds on main stem from ground level to 2.5m west 3m to 4.5m, north and 5m to 6m east.	N/A	N/A
35G*	Rowan, Holly & Hawthorn	150	C1	1.8	10.2	8	N/A	N/A	N/A	N/A	Young	Fair	Defunct linear group.	N/A	N/A
36T	Pedunculate Oak	650	C1	7.8	191.2	8	4.5	4	4	4	Over Mature	Good	Stem cavity between ground level and 2m south east, further cavity opening on northern and western aspects. A Valuable ecological receptor	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Conditions			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
37T	Sycamore	100	U	1.2	4.5	4	1.5	1.5	1.5	1.5	Semi-mature	Poor	Upper canopy dead.	N/A	N/A
38T	Sycamore	150, 150	C1	2.5	20.4	5	2	2	2	2	Young	Fair	Stem bifurcates at 0.25m. Intertwined.	N/A	N/A
39T	Elder	75	C1	0.9	2.5	3	2	2	1.5	1.5	Young	Fair	Self set.	N/A	N/A
40T	Hawthorn	75	C1	0.9	2.5	2.5	1	1	1	1	Young	Fair	Self set.	N/A	N/A
41G	Birch spp	300	C3	3.6	40.7	8	1.5	2.5	1.5	2	Semi-mature	Fair	Northern members sparse.	N/A	N/A
42T	Pedunculate Oak	640	C1	7.7	185.3	10	1	1	5	4	Mature	Fair	Stem wound at ground level to 1.5m south west associated with loss of large diameter limb. North eastern aspects of canopy harshly pruned to provide clearance from power lines. Epicormic growth on stem as a response .	N/A	N/A
43T*	Alder	400	U	4.8	72.4	4.5	1.5	1.5	1.5	1.5	Early-mature	Poor	Pollard at 2m set below power lines.	N/A	N/A
44H	Holly, Hazel, Hawthorn & Alder	75	B1	0.9	2.5	2	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species hedgerow.	N/A	N/A
45T	Alder	290	C1	3.5	38.1	8	1.5	2	2.5	2	Semi-mature	Fair	Tall etiolated growth form, set within hedgerow.	N/A	N/A
46T	Alder	290, 300, 270	U	6.0	111.7	8.5	2	1.5	1	2	Early-mature	Poor	Lower stem not visible set in hedgerow, upper canopy sparse/low bud density .	N/A	N/A
47T	Pedunculate Oak	1050	U	12.6	498.8	12	5	5	6	5	Over Mature	Poor	Large section of bark lost/delaminated from ground level to upper canopy north and west. Multiple cracks and splits with bat roost potential. Some live growth remain in southern	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
													aspect of canopy . <i>Ceriporus squamosus</i> fungal bracket 1m north east.		
48T	Pedunculate Oak	660, 650	B1	11.1	388.2	10	5	5	5	5	Mature	Good	Epicormic growth on main stem, large diameter deadwood at 4m east, minor deadwood throughout. Squat form.	N/A	N/A
49T	Alder	200, 200	C1	3.4	36.2	8	0.5	0.5	1.5	1.5	Semi-mature	Good	Stem bifurcates at 1m.	N/A	N/A
50T	Pedunculate Oak	700	B1	8.4	221.7	10	5	5	5	5	Mature	Good	Set to north of 1.5m ditch, minor deadwood through canopy.	N/A	N/A
51T	Birch spp	400	U	4.8	72.4	9	2	2	1.5	1.5	Early-mature	Poor	Retrenchment of canopy noted.	N/A	N/A
52T	Birch spp	410	B1	4.9	76.1	9	3	3	2.5	3.5	Early-mature	Fair	No significant defects recorded.	N/A	N/A
53T	Birch spp	380	C1	4.6	65.3	8	2.5	3	2	2	Early-mature	Fair	Minor deadwood within exterminates of canopy.	N/A	N/A
54T	Pedunculate Oak	500, 500	B1	8.5	226.2	14	7	3	5	6	Mature	Fair	Stem bifurcates at ground level set behind dense holly.	N/A	N/A
55T	Birch spp	590	B1	7.1	157.5	13	4	4	4	4	Mature	Good	No significant defects recorded.	N/A	N/A
56T	Birch spp	300	C1	3.6	40.7	8	2	1	2	5	Semi-mature	Fair	Ivy on lower stem which kinks west.	N/A	N/A
57T	Pedunculate Oak	730	B1	8.8	241.1	13	6	5	4	4	Mature	Good	No significant defects recorded.	N/A	N/A
58T	Pedunculate Oak	640	B1	7.7	185.3	9	5	5	5	5	Mature	Good	Squat form ivy on stem.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Largely Overcast			Tree Constraints Information								Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)								
							N	E	S	W					
59T	Goat Willow	325, 350, 300, 300, 340	C1	8.7	236.9	12	5	9	8	6	Mature	Fair	Multi-stemmed, ivy on all stems.	N/A	N/A
60T	Pedunculate Oak	690	U	8.3	215.4	7	3	1.5	0.5	1	Mature	Dead	Of ecological value.	N/A	N/A
61T	Pedunculate Oak	680, 490	B1	7.4	173.9	10	4.5	4	5	5	Mature	Good	Stem bifurcates at 1.5m, has been crown raised to 4m, pruning wounds/elongated shoots on main stem at all cardinal points.	N/A	N/A
62T	Holly	260	C1	3.1	30.6	9	2	1	2	2	Mature	Fair	Eastern aspect of canopy maintained by flail.	N/A	N/A
63G	Birch & Goat willow	200	C3	2.4	18.1	9	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species group.	N/A	N/A
64T	Pedunculate Oak	600	B1	7.2	162.9	9	5.5	4	5	4	Mature	Good	Squat form.	N/A	N/A
65T	Pedunculate Oak	750	B1	9.0	254.5	14	4	8	10	8	Mature	Good	Ivy obscures stem.	N/A	N/A
66T	Birch spp	250	C1	3.0	28.3	13	5	4	1.5	1	Semi-mature	Fair	Suppressed, tall, etiolated growth form.	N/A	N/A
67T	Pedunculate Oak	600	B1	7.2	162.9	15	4	6	4	6	Mature	Good	Steep ditch to west, moderate deadwood at 4m south 6m east, large diameter deadwood 7m south east.	N/A	N/A
68T	Birch spp	360	C1	4.3	58.6	11	2	6	1.5	4	Early-mature	Fair	Supressed canopy development.	N/A	N/A
69T	Birch spp	300	U	3.6	40.7	8	1	1	1	1.5	Mature	Fair	Little live growth.	N/A	N/A
70T	Birch spp	360	C1	4.3	58.6	10	3.5	4	4	2	Early-mature	Fair	Large stem cavity at 1m south.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1, 2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information															
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
71T	Birch spp	300	C1	3.6	40.7	8.5	2	1.5	2.5	1.5	Mature	Fair	Ivy obscures mains stem.	N/A	N/A
72T	Pedunculate Oak	710	C1	8.5	228.1	10	5	5	5	9	Mature	Fair	Significant decay (cubical brown rot) of main union leading into dominant western stem.	N/A	N/A
73H	Hawthorn	75	C3	0.9	2.5	3	N/A	N/A	N/A	N/A	Semi-mature	Fair	Defunct hedgerow spans the length of the southern boundary.	N/A	N/A
74T	Alder	290	C1	3.5	38.1	9	1.5	1	1.5	2	Semi-mature	Fair	Suppressed canopy development.	N/A	N/A
75T	Pedunculate Oak	610	B1	7.3	168.4	10	6	3	3.5	5.5	Over Mature	Good	Historically crown raised south to 5m.	N/A	N/A
76T	Pedunculate Oak	580	B1	7.0	152.2	10	6	6	5	3.5	Mature	Good	Historically crown raised south to 5m.	N/A	N/A
77T	Ash	350, 370	B1	6.1	117.3	12	6	5	3	7	Early-mature	Good	Reasonable bud density/vitality at present.	Monitor annually for ash die back	3
78T	Alder	210, 200, 300, 150	C1	5.3	88.9	10	3	5	3	4	Semi-mature	Fair	Multi-stemmed.	N/A	N/A
79T*	Holly	150	C1	1.8	10.2	9	1	4	1	1	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
80T	Pedunculate Oak	300	C1	3.6	40.7	8	2	6	1.5	1.5	Semi-mature	Fair	Poor shape and form.	N/A	N/A
81T	Goat willow	820	C1	9.8	304.2	7	6	2	2	5	Mature	Fair	Ivy on stem, loss of eastern section of canopy.	N/A	N/A
82T	Goat Willow	400	C1	4.8	72.4	10	2	1.5	2	4	Early-mature	Fair	Stem kink west, a phototropic response during early development.	N/A	N/A
83T	Pedunculate Oak	450	B1	5.4	91.6	12	5	5	4	4	Mature	Good	No significant defects recorded.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic Largely overcast

			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
84T	Pedunculate Oak	370, 500, 340	B1	8.5	227.3	11	5	3	6	3	Mature	Good	Stem trifurcates at 0.5m, two of which are fused at 2.5m .	N/A	N/A
85G	Goat willow, hazel & Alder	320	C1	3.8	46.3	12	N/A	N/A	N/A	N/A	Early-mature	Fair	Mixed species tree group.	N/A	N/A
86T	Pedunculate Oak	900	A1	10.8	366.5	13	6	5	7	8	Mature	Good	Ivy obscures stem. Torn limbs at 8m east and south west typical of individuals of this age .	N/A	N/A
87H	Blackthorn & Goat Willow	75	C3	0.9	2.5	3	N/A	N/A	N/A	N/A	Semi-mature	Good	Short section of hedgerow.	N/A	N/A
88T	Pedunculate Oak	1050	B1	12.6	498.8	10	4	2	6	6	Over Mature	Good	Large tear out wound at 3.5m south east on main stem, further torn limbs between 5m to 6m north. Desiccated fruiting body 2m east, little of the fruiting body remains.	N/A	N/A
89T	Pedunculate Oak	910	B1	10.9	374.7	11	8	7	7	6	Mature	Good	Historic pruning wound at 2.5m east and 3m south almost fully occluded. Tear out wound on eastern primary limb at 4m south east. Further tears out wounds noted within mid canopy.	N/A	N/A
90G	Blackthorn	100	C3	1.2	4.5	3.5	N/A	N/A	N/A	N/A	Semi-mature	Fair	Dense groups.	N/A	N/A
91T	Alder	500, 250, 260	U	7.4	172.0	8	2	2	2	4	Mature	Fair	Main stem failed at 2m leaving large stem cavity with aerial roots, a good ecological receptor.	N/A	N/A
92T	Alder	320	C1	3.8	46.3	10	1.5	1	3	2	Semi-mature	Good	Tall, etiolated growth form.	N/A	N/A
93T	Pedunculate Oak	620	C1	7.4	173.9	10	5.5	5	6	5	Mature	Fair	Massive stem cavity at 1.5m north.	N/A	N/A
94T	Alder	240	C1	2.9	26.1	8	1	5	1	1	Semi-mature	Fair	Supressed canopy development.	N/A	N/A
95H	Blackthorn	75	B3	0.9	2.5	1.5	N/A	N/A	N/A	N/A	Semi-mature	Fair	Maintained by flail at 1.5m in height.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information															
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
96T	Pedunculate Oak	675	A1	8.1	206.1	10	6	6	6	6	Mature	Good	Good potential for future growth/lateral development.	N/A	N/A
97T	Pedunculate Oak	400	B1	4.8	72.4	8	3	3	3	3	Early-mature	Good	No significant defects recorded.	N/A	N/A
98T	Pedunculate Oak	500	B1	6.0	113.1	9	3	5	3	3.5	Mature	Fair	Lower stem obscured by holly hedgerow.	N/A	N/A
99T	Pedunculate Oak	650	C1	7.8	191.2	8.5	2	3	4	4	Mature	Fair	Set in hedgerow obscure parts of lower stem. Large stem wound between 0.5m to 1.5m north west, large limb cut at 1.5m.	N/A	N/A
100T	Pedunculate Oak	440	B1	5.3	87.6	9	3	3.5	3	2.5	Mature	Good	No significant defects recorded.	N/A	N/A
101T	Alder	225, 100, 100, 120, 100	C1	3.7	43.0	7	3	2	4.5	2	Early-mature	Fair	Historic coppice.	N/A	N/A
102H	Hazel, holly & hawthorn	75	B3	0.9	2.5	1.25	N/A	N/A	N/A	N/A	Semi-mature	Good	Mixed species hedgerow	N/A	N/A
103T	Pedunculate Oak	590	B1	7.1	157.5	7	3	3	4	3	Mature	Fair	Ivy obscures main stem.	N/A	N/A
104T	Pedunculate Oak	1000	B1	12.0	452.4	9	4	5	5	4.5	Mature	Good	No significant defects recorded.	N/A	N/A
105T	Pedunculate Oak	820	B1	9.8	304.2	11	4	5	4	7	Mature	Good	No significant defects recorded.	N/A	N/A
106T	Pedunculate Oak	720	B1	8.6	234.5	11	4	4	5	5	Mature	Fair	Several torn limbs/branch stubs in mid canopy west	N/A	N/A
107T	Pedunculate Oak	400	C1	4.8	72.4	7	3	3	3	3	Early-mature	Fair	Stem obscured by ivy, squat form upper western branch have been pruned in past, etiolated regrowth.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
108T	Pedunculate Oak	680	B1	8.2	209.2	11	5	4	6	4.5	Mature	Fair	Torn limb at 4m east.	N/A	N/A
109T	Pedunculate Oak	490	B1	5.9	108.6	11	5	5	5	5	Mature	Good	No significant defects recorded.	N/A	N/A
110T	Pedunculate Oak	500	B1	6.0	113.1	9	5	3	3	3.5	Mature	Poor	No significant defects recorded.	N/A	N/A
111T	Pedunculate Oak	310	B1	3.7	43.5	11	2.5	3	4	3	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
112T	Pedunculate Oak	690	A1	8.3	215.4	10	7	6	6	7	Mature	Good	Large diameter deadwood at 3m south.	N/A	N/A
123T	Pedunculate Oak	390	C1	4.7	68.8	9	2	3	1.5	2.5	Early-mature	Fair	Decay seam/open stem cavity from ground level to 1.5m north west.	N/A	N/A
114T	Pedunculate Oak	500	B1	6.0	113.1	9	2.5	2.5	3	2.5	Mature	Good	Squat form.	N/A	N/A
115T	Pedunculate Oak	960	B1	11.5	417.0	10	5	5	5	5	Mature	Good	Large diameter limbs torn at 2m south east and 3.5m south east	N/A	N/A
116G	Pedunculate Oak	675	B3	8.1	206.1	13	N/A	N/A	N/A	N/A	Mature	Good	Canopies form cohesive boundary feature.	N/A	N/A
117T	Pedunculate Oak	970	B1	11.6	425.7	9	4	4.5	4	4	Mature	Good	No significant defects recorded.	N/A	N/A
118T	Ash	420	C1	5.0	79.8	12	5	5	2	5	Early-mature	Fair	Partially occluded pruning wound on main stem at 0.3m south and 0.75m south west. Bottle but. Reasonable bud density at present.	Monitor annually for ash die back	3
119T	Pedunculate Oak	440	C1	5.3	87.6	10	1.5	7.5	1.5	1.2	Mature	Fair	Poor shape and form, canopy development bias east suppressed by larger ash to the west.	N/A	N/A
120T	Ash	720	U	8.6	234.5	16	6	6	5.5	5.5	Mature	Poor	Massive stem cavity 0.3m to 2m north.	Monolith to 3m to retain as eco receptor	1

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Observations: Largely Overcast			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
121T	Pedunculate Oak	710	B1	8.5	228.1	11	2.5	3	5	3	Mature	Fair	Torn primary limb at 3.5m east and 4m north.	N/A	N/A
122T	Pedunculate Oak	500	B1	6.0	113.1	12	2	3.5	6	7	Mature	Fair	Torn limb 5m south, tear out wound 8m central canopy.	N/A	N/A
123T	Ash	570	B1	6.8	147.0	14	7	4	7	7	Mature	Fair	Reasonable bud density/vitality at present.	Monitor annually for ash die back	3
124G	Ash & Cherry	250	C3	3.0	28.3	8	N/A	N/A	N/A	N/A	Semi-mature	Fair	Tall, etiolated growth form.	N/A	N/A
125T	Pedunculate Oak	540	B1	6.5	131.9	12	5	5	5	5	Mature	Fair	No significant defects recorded.	N/A	N/A
126G	Hawthorn & Blackthorn	100	C3	1.2	4.5	5	N/A	N/A	N/A	N/A	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
127G	Hawthorn & Blackthorn	100	C1	1.2	4.5	5	N/A	N/A	N/A	N/A	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
128T	Ash	550	U	6.6	136.9	11	4.5	6	6	4.5	Mature	Poor	Two stem cavities between 3.5m and 4m west, torn primary limb 3.5 north. Branch cavity at 4m south, elongated limb over road.	Remove	2
129T	Pedunculate Oak	350	B1	4.2	55.4	8	2.5	2.5	3	1.5	Early-mature	Fair	No significant defects recorded.	N/A	N/A
130T	Pedunculate Oak	310	B1	3.7	43.5	8	3	2.5	3	2	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
131T	Pedunculate Oak	580	B1	7.0	152.2	8	4.5	2	5	5.5	Mature	Good	No significant defects recorded.	N/A	N/A
132G	Goat willow & Hazel	180	C3	2.2	14.7	5	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species tree group	N/A	N/A
133T	Ash	400	B1	4.8	72.4	10	3	3	3	3	Early-mature	Good	No significant defects recorded.	Monitor annually for ash die back	3

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Largely Overcast			Tree Constraints Information								Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)								
							N	E	S	W					
134T	Ash	370, 400	B1	6.5	134.3	10	5	3	5	5	Semi-mature	Fair	Reasonable bud density/vitality at present.	Monitor annually for ash die back	3
135T	Pedunculate Oak	420	C1	5.0	79.8	7	4	1.5	3	5	Early-mature	Good	Supressed by neighbouring, ash squat asymmetric canopy.	N/A	N/A
136T	Pedunculate Oak	570	B1	6.8	147.0	12	5	4	5	4.5	Mature	Good	No significant defects recorded.	N/A	N/A
137T	Ash	340	C1	4.1	52.3	8	2.5	1.5	2.5	2.5	Semi-mature	Fair	Stem ivy clad, minor deadwood largely noted within mid canopy east.	Monitor annually for ash die back	3
138H	Blackthorn	75	C3	0.9	2.5	1.5	N/A	N/A	N/A	N/A	Early-mature	Fair	Defunct in parts.	N/A	N/A
139T	Ash	260, 220	C1	4.1	52.5	9	3	3	1.5	1	Semi-mature	Fair	Stem bifurcates at base.	Monitor annually for ash die back	3
140T	Pedunculate Oak	570	C1	6.8	147.0	8	3.5	4.5	3	4.5	Mature	Fair	Large tear out wound 2.5m to 4m north east.	Reduce to a 4m Monolith to retain as ecological asset	2
141T	Ash	870	C1	10.4	342.5	10	3.5	4.5	6	5	Mature	Poor	Extensive stem cavity from ground level to 6m north east.	Reduce to a 6m Monolith to retain as ecological asset	1
142H	Hawthorn, Blackthorn, Hazel & Holly	75	B3	0.9	2.5	1.5	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species hedgerow.	N/A	N/A
143G	Pedunculate Oak	830	A1	10.0	311.7	14	N/A	N/A	N/A	N/A	Mature	Good	Linear group roadside oak with occasional smaller specimens between.	Clear hung up branches/moderate to large diameter deadwood over roadside	2
144T	Damson	120, 120, 100, 100	C1	2.9	26.6	7	2	2	2	2	Semi-mature	Fair	Multi-stemmed.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Largely Overcast			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
145T	Pedunculate Oak	790	A1	9.5	282.4	14	6	5	8	7	Mature	Good	Large diameter deadwood at 4m south. Further moderate diameter deadwood within wood mid canopy.	Remove moderate – large deadwood over highway	2
146T	Pedunculate Oak	620	U	7.4	173.9	6.5	4	3	2	1.5	Mature	Fair	Massive stem cavity north ground level to 2m .	Monolith at 3m retain as ecological asset	2
147T	Ash	940	B1	11.3	399.8	16	10	9	8	6	Mature	Fair	Stem cavity 3.5m south. Branch cavity noted on eastern primary limb at 4m south east. Further branch cavities at 6m west and 12m west. Reasonable bud density at present.	Monitor annually for ash die back	3
148T	Ash	810	U	9.7	296.9	15	6	1	7	9	Over Mature	Poor	Failure of western stem at 6m west, <i>Inonotus hispidus</i> bracket below failure point. Stem cavity on western stem 6m south east. Retrenchment of canopy indicates vascular dysfunction /decline	Reduce to a 6m Monolith to retain as ecological asset	1
149T	Apple	200	C1	2.4	18.1	4	1	1.5	1	1.5	Semi-mature	Good	No significant defects recorded.	N/A	N/A
150G	Birch spp	375	C3	4.5	63.6	11	N/A	N/A	N/A	N/A	Early-mature	Fair	Linear group.	N/A	N/A
151H	Holly, Blackthorn & Hazel	75	B1	0.9	2.5	1.5	0.5	0.5	0.5	0.5	Young	Fair	Mixed species hedgerow.	N/A	N/A
152T	Pedunculate Oak	670	B1	8.0	203.1	14	3	2	6	6	Mature	Fair	Storm damage/ torn limbs at 5m and 8m east, has left canopy unbalanced. The tree had the potential to occluded wound and re-place section of the canopy with time.	N/A	N/A
153G	Hawthorn	100	C3	1.2	4.5	6	N/A	N/A	N/A	N/A	Semi-mature	Good	No significant defects recorded.	N/A	N/A
154T	Birch spp	390, 400	C1	6.7	141.2	10	3	3	3	3	Mature	Fair	Stem bifurcates at ground level, ivy on stems .	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information															
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
155T	Pedunculate Oak	610	B1	7.3	168.4	10	5	6	3.5	5	Mature	Good	Squat form.	N/A	N/A
156T	Pedunculate Oak	630	B1	7.6	179.6	11	6	6	5	6	Over Mature	Fair	Small stem wound 4m south east.	N/A	N/A
157H	Hazel	75	C3	0.9	2.5	1.5	N/A	N/A	N/A	N/A	Early-mature	Good	Defunct throughout.	N/A	N/A
158T	Pedunculate Oak	650	A1	7.8	191.2	11	6	6	6	6	Mature	Good	No significant defects recorded.	N/A	N/A
159T	Pedunculate Oak	240	C1	2.9	26.1	11	0.5	1	2	0.5	Semi-mature	Poor	Canopy development suppressed	N/A	N/A
160T	Hazel	100	C1	1.2	4.5	5	1.5	2	1	2	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
161T	Ash	350	C1	4.2	55.4	10	4	0.5	1	6	Early-mature	Fair	Poor shape and form.	Monitor annually for ash die back	3
162T	Pedunculate Oak	740	A1	8.9	247.8	16	6	4	5	4	Mature	Good	Torn limb 6m east and 7 south.	N/A	N/A
163T	Pedunculate Oak	430	B1	5.2	83.7	10	5	4	3	5	Mature	Good	No significant defects recorded.	N/A	N/A
164H	Hazel & hawthorn	75	B3	0.9	2.5	2	N/A	N/A	N/A	N/A	Early-mature	Good	No significant defects recorded.	N/A	N/A
165G	Pedunculate Oak	650	B3	7.8	191.2	10	N/A	N/A	N/A	N/A	Mature	Good	Minor deadwood/small diameter torn limb typical of age and species.	N/A	N/A
166T	Pedunculate Oak	380	C1	4.6	65.3	4.5	1.5	1	1.5	1.5	Early-mature	Fair	No significant defects recorded.	N/A	N/A
167T	Pedunculate Oak	1020	B1	12.2	470.7	14	4	5	4.5	7	Mature	Good	Old pruning wound 2m north west, torn limb 4m north, large tear out wound between 6m to 7m south. Further tear out 4m to 7m south.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information															
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
168T	Pedunculate Oak	840	B1	10.1	319.2	14	7	7	7	7	Mature	Fair	Moderate diameter deadwood at 5m north east. Minor deadwood throughout extremities of canopy, notably south western quadrant.	N/A	N/A
169G	Ash , Oak, Cherry & Holly	280	C3	3.4	35.5	8	N/A	N/A	N/A	N/A	Early-mature	Fair	Contains dead sections of cherry.	N/A	N/A
170T	Pedunculate Oak	500	B1	6.0	113.1	9	5	2	4	5	Mature	Fair	Large diameter limb removed at 3m south east, tall etiolated new growth.	N/A	N/A
171T	Pedunculate Oak	460	B1	5.5	95.7	9	4	3.5	4	4	Mature	Fair	Set in dense holly.	N/A	N/A
172T	Pedunculate Oak	725	B1	8.7	237.8	9	5	4.5	5	4	Over Mature	Good	Set on banks of steep ditch.	N/A	N/A
173G	Holly & Hawthorn	150	C3	1.8	10.2	6	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species tree group.	N/A	N/A
174T*	Pedunculate Oak	310	C1	3.7	43.5	7	3	5	5	2	Mature	Fair	Set in ditch.	N/A	N/A
175T	Pedunculate Oak	580	B1	7.0	152.2	11	6	6	3	5	Mature	Fair	Torn limb 5m west, tall etiolated re-growth.	N/A	N/A
176T	Ash	430	C1	5.2	83.7	10	0.5	1	2	2.5	Early-mature	Fair	Poor shape and form.	Monitor annually for ash die back	3
177T	Pedunculate Oak	850	B1	10.2	326.9	12	4.5	9.5	7	6	Over Mature	Fair	Stem cavity 3m south, torn limb 3m south west.	N/A	N/A
178T	Pedunculate Oak	900	B1	10.8	366.5	13	8	7	8	8	Over Mature	Fair	Torn limbs between 7m and 9m south west.	N/A	N/A
179T	Pedunculate Oak	760	B1	9.1	261.3	8	4	4	3	4	Mature	Good	Squat form.	N/A	N/A
180G	Ash & Alder	390	C3	4.7	68.8	12	N/A	N/A	N/A	N/A	Early-mature	Fair	Tall, etiolated growth form, provides good eco resource/boundary marker.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information			Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code								
Category Grade	Radius of RPA (m)	Area of RPA (m2)						Height (m)	Canopy Spread (m)						
									N	E	S	W			
181T	Ash	500, 520	U	8.7	235.4	13	2	7	8	6	Mature	Fair	Basal decay of northern buttress, noted prolific ivy on stems.	Remove with an increase in occupancy/land use	2
182T	Ash	740	B1	8.9	247.8	15	6	5	7	7	Over Mature	Fair	Reasonable bud density/vitality at present.	Monitor annually for ash die back	3
183T	Pedunculate Oak	780, 720	B1	12.7	509.8	8	3	6	6	6	Over Mature	Fair	Stem bifurcates at 0.5m, several tear out wounds throughout scaffold limbs .	N/A	N/A
184G	Alder	500	B3	6.0	113.1	13	N/A	N/A	N/A	N/A	Mature	Good	No significant defects recorded.	N/A	N/A
185T	Hawthorn	75	C1	0.9	2.5	4	1	1	1	1	Semi-mature	Good	Self set.	N/A	N/A
186T	Elder	100	C1	1.2	4.5	4	0.5	0.5	1	0.5	Young	Fair	Self set.	N/A	N/A
187T	Alder	300	C1	3.6	40.7	8	2	3	2	1.5	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
188T	Hawthorn	100, 100, 100, 100, 100	C1	2.7	22.6	8	1.5	1	1.5	2	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
189T	Pedunculate Oak	760	B1	9.1	261.3	9	6.5	6	6	6	Over Mature	Fair	Developing internal canopy, typical of over mature age class prior to retrenchment. A natural part of aging process.	N/A	N/A
190H	Hawthorn, Blackthorn & Holly	75	B3	0.9	2.5	2	N/A	N/A	N/A	N/A	Young	Fair	Mixed species hedgerow.	N/A	N/A
191T	Pedunculate Oak	480	U	5.8	104.2	6	3	2	1.5	1	Mature	Poor	Lost large diameter limb at 2m east and west, little photosynthetic mass, restricted to northern canopy.	N/A	N/A
192T	Holly	120	U	1.4	6.5	3.5	1	0.5	1	0.5	Semi-mature	Poor	Sparse canopy.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Conditions			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
193T	Pedunculate Oak	340	B1	4.1	52.3	7	4	4	2	4	Semi-mature	Fair	Southern limbs pruned back from power line.	N/A	N/A
194H	Hawthorn Blackthorn, Elder & Oak	75	B3	0.9	2.5		N/A	N/A	N/A	N/A	Semi-mature	Fair	Several gaps in eastern half.	N/A	N/A
195T	Pedunculate Oak	710	B1	8.5	228.1	13	2	7	7	4.5	Over Mature	Fair	Northern limbs have been cut back to stem to provide clearance from power lines .	N/A	N/A
196T	Pedunculate Oak	940	B1	11.3	399.8	13	2	6	6	6	Over Mature	Good	Stem bifurcates at 1.6m. Fused limbs 6m south east. Northern limbs pruned back power lines.	N/A	N/A
197G	Pedunculate Oak	650	B3	7.8	191.2	12	N/A	N/A	N/A	N/A	Mature	Good	Linear group denotes ditch , younger holly and oak beneath. Several members have had lower eastern limbs recently removed.	N/A	N/A
198W	Oak, Holly, Hazel, Birch & Blackthorn	600	A1	7.2	162.9	14	N/A	N/A	N/A	N/A	Mature	Good	Predominantly comprising of oak.	N/A	N/A
199T	Pedunculate Oak	860	A1	10.3	334.6	15	7	6	6	5	Over Mature	Good	Larger than it's counterparts	N/A	N/A
200T	Pedunculate Oak	630	A1	7.6	179.6	12	6	6	5	5	Mature	Good	No significant defects recorded.	N/A	N/A
201T	Pedunculate Oak	150	C1	1.8	10.2	7	1	1	1	1	Young	Good	No significant defects recorded.	N/A	N/A
202T	Pedunculate Oak	160	C1	1.9	11.6	5	1	1.5	1.5	1	Young	Fair	No significant defects recorded.	N/A	N/A
203T	Pedunculate Oak	750	A1	9.0	254.5	14	3.5	6	8	7	Over Mature	Good	No significant defects recorded.	N/A	N/A
204T	Pedunculate Oak	720	B1	8.6	234.5	9	5	6	2	2.5	Mature	Good	Canopy development suppressed.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information															
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
205T	Hawthorn	100	C1	1.2	4.5	6	2	0.5	1	0.5	Semi-mature	Good	Canopy development suppressed.	N/A	N/A
206T*	Goat Willow	100	C1	1.2	4.5	5	2	1	1	0.5	Semi-mature	Good	Self set.	N/A	N/A
207T	Ash	525	B1	6.3	124.7	13	4.5	5	3.5	3.5	Early-mature	Fair	Reasonable bud density/vitality at present.	Monitor annually for ash die back	3
208T	Alder	340	C1	4.1	52.3	12	3.5	1.5	1.5	3.5	Semi-mature	Fair	Set on bank of ditch.	N/A	N/A
209G	Hawthorn & Holly	100	C3	1.2	4.5	5	N/A	N/A	N/A	N/A	Semi-mature	Good	Short stretch of hawthorn and holly.	N/A	N/A
210W	Alder, oak, goat willow	300	B3	3.6	40.7	14	N/A	N/A	N/A	N/A	Early-mature	Fair	Mixed species woodland.	N/A	N/A
211T	Pedunculate Oak	980	B1	11.8	434.5	13	5	6	5	6	Over Mature	Good	Large wound on northern side of southern stem, has storm damage in upper canopy, no clear leader.	N/A	N/A
212G	Birch & Alder	100	C3	1.2	4.5	5	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species tree group.	N/A	N/A
213T	Alder	490, 470	B1	7.6	179.7	12	3	3.5	4	3.2	Mature	Fair	Stem bifurcates at 0.5m.	N/A	N/A
214T	Goat Willow	100	U	1.2	4.5	3.5	1.5	3	1.5	1	Young	Fair	Located in a depression, likely to be water logged for large duration of the winter/period of heavy rainfall.	N/A	N/A
215G	Birch & Alder	100	C3	1.2	4.5	5	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species tree group.	N/A	N/A
216T	Pedunculate Oak	880	B1	10.6	350.4	13	5	9	6	10	Over Mature	Fair	Compaction from livestock, basal decay/open cavity at ground level west. Moderate deadwood in mid canopy.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
217T	Pedunculate Oak	630	B1	7.6	179.6	12	5	3.5	4	3.5	Mature	Fair	Compaction from livestock, stem wound ground level to 1.5m west	N/A	N/A
218T	Pedunculate Oak	320	B1	3.8	46.3	9	2.5	3	4	4	Semi-mature	Good	No significant defects recorded.	N/A	N/A
219G	Alder & Goat willow	300	C3	3.6	40.7	9	N/A	N/A	N/A	N/A	Early-mature	Fair	No significant defects recorded.	N/A	N/A
220T*	Pedunculate Oak	590	B1	7.1	157.5	12	5	6	7	1.5	Mature	Fair	Asymmetric canopy.	N/A	N/A
221G	Hawthorn & Hazel	100	C3	1.2	4.5	3	N/A	N/A	N/A	N/A	Semi-mature	Fair	Hawthorn hazel extends north.	N/A	N/A
222T	Ash	840	B1	10.1	319.2	16	5	8	7	5	Over Mature	Fair	Stem cavity at 2m north east, form suggests loss of main leaders at 10m in early development with tall etiolated poles extending from this point.	Monitor annually for ash die back	3
223T	Pedunculate Oak	820	B1	9.8	304.2	16	7	6.5	5	7	Over Mature	Good	Large wound at 5m south west on eastern stem, split at 4.5m on northern primary limb.	N/A	N/A
224G	Hawthorn, Birch Hazel & Oak	290	C3	3.5	38.1	7	N/A	N/A	N/A	N/A	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
225T	Ash	640	B1	7.7	185.3	13	6.5	7	8	7	Mature	Fair	Reasonable bud density/vitality at present.	Monitor annually for ash die back	3
226G	Hawthorn & holly	100	C3	1.2	4.5	4	N/A	N/A	N/A	N/A	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
227T	Ash	420	C1	5.0	79.8	9	1.5	1	1.5	2.5	Early-mature	Fair	Bottle butt, indicates a response to decay providing some compensation to a perceived weakness.	Monitor annually for ash die back	3
228G	Hawthorn	120	C3	1.4	6.5	4	N/A	N/A	N/A	N/A	Semi-mature	Good	Cohesive tree group.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information															
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
229T	Pedunculate Oak	630	A1	7.6	179.6	12	6	6	6	6	Mature	Good	No significant defects recorded.	N/A	N/A
230T	Pedunculate Oak	680	B1	8.2	209.2	12	5.5	5	6	6	Over Mature	Good	Pruning wound at 1.8m, north east, directly below main union, partially occluded.	N/A	N/A
231T	Birch spp	470	C1	5.6	99.9	12	7	1.5	5	6	Mature	Fair	Basal decay south west, stem cavity 1.8m north east below tight union.	N/A	N/A
232T	Pedunculate Oak	750	U	9.0	254.5	3	7	1	0.5	1	Over Mature	Fair	Stem cavity ground level to 1.5m north, stem collapsed at 2m	N/A	N/A
233T	Birch spp	420, 490	B1	7.7	188.4	14	6	4.5	5	5	Mature	Good	No significant defects recorded.	N/A	N/A
234T	Holly	150	C1	1.8	10.2	9	2	2	2	2	Mature	Fair	No significant defects recorded.	N/A	N/A
235T	Alder	500	U	6.0	113.1	8	7	4	4	2	Mature	Poor	Stem cavity 1.5m south and 2.5m north east.	N/A	N/A
236T	Alder	480	B1	5.8	104.2	9	5	2	4	2.5	Mature	Good	No significant defects recorded.	N/A	N/A
237T	Alder	500	B1	6.0	113.1	9.5	3	5	3	3.5	Mature	Good	No significant defects recorded.	N/A	N/A
238G	Alder	490	B3	5.9	108.6	13	N/A	N/A	N/A	N/A	Mature	Fair	Linear group .	N/A	N/A
239T	Birch spp	380	B1	4.6	65.3	9	3.5	3.5	2.5	3.5	Early-mature	Fair	No significant defects recorded.	N/A	N/A
240H	Hawthorn	100	C1	1.2	4.5	4	2	2	2	2	Semi-mature	Good	No significant defects recorded.	N/A	N/A
241T	Ash	390	B1	4.7	68.8	9	6	4.5	5	4	Early-mature	Fair	Reasonable bud density/vitality at present.	Monitor annually for ash die back	3

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information			Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m					N	E	S	W					
242T	Beech	670	B1	8.0	203.1	10	6	5	5	5	Over Mature	Fair	Stem divides from included union at 2.5m, no internal bracing .	N/A	N/A
243T	Pedunculate Oak	680	B1	8.2	209.2	9.5	5	4	6	6	Mature	Good	Squat form.	N/A	N/A
244T	Pedunculate Oak	680	B1	8.2	209.2	11	9	8	9	2	Mature	Fair	Burrs on lower stem, asymmetric canopy suppressed by neighbouring ash .	N/A	N/A
245T	Ash	960	B1	11.5	417.0	18	10	8	10	7	Over Mature	Good	Elongated limbs north and north east, heavy loading, reasonable bud at present.	Monitor annually for ash die back	3
246T	Pedunculate Oak	520	B1	6.2	122.3	12	4	3.5	6	3	Mature	Good	No significant defects recorded.	N/A	N/A
247T	Ash	560	C1	6.7	141.9	13	2	2.5	7	5	Mature	Fair	Inonotus hispidus bracket and stem cavity 6m north.	N/A	N/A
248T	Pedunculate Oak	1210	B1	14.5	662.4	19	6	7	10	10	Over Mature	Fair	Has lost large diameter limbs at 6m north and 9m south.	N/A	N/A
249G	Hazel & hawthorn	100	C3	1.2	4.5	6	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species tree group.	N/A	N/A
250T	Pedunculate Oak	680	C1	8.2	209.2	11	2	3	4	3	Mature	Fair	Retrenchment noted.	N/A	N/A
251G	Ash	450	B3	5.4	91.6	13	N/A	N/A	N/A	N/A	Early-mature	Good	Members Ivy clad.	N/A	N/A
252T	Pedunculate Oak	680	B1	8.2	209.2	13	3	1	6	7	Mature	Good	Ivy on stem asymmetric.	N/A	N/A
253T	Ash	900	B1	10.8	366.5	14	3	7	7	5	Over Mature	Fair	Ivy on stem asymmetric canopy development.	Monitor annually for ash die back	3
254T	Pedunculate Oak	400	B1	4.8	72.4	9	4	4	4	4	Early-mature	Fair	No significant defects recorded.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Observations: Largely Overcast			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
255T*	Birch spp	220	C1	2.6	21.9	8	1	1	1	1	Semi-mature	Fair	Sparse canopy.	N/A	N/A
256T*	Birch spp	210	C1	2.5	20.0	8	1	1.5	1.5	0.5	Semi-mature	Poor	Sparse canopy.	N/A	N/A
257T	Pedunculate Oak	880	B1	10.6	350.4	12	5.5	8	8	8	Over Mature	Fair	Crown raised to 6m north.	N/A	N/A
258T	Pedunculate Oak	470	U	5.6	99.9	9	1	1.5	3	1	Mature	Fair	Crown raised to 6m, limited viable canopy.	N/A	N/A
259T	Birch spp	310	C1	3.7	43.5	10	2	4	3	3	Early-mature	Fair	No significant defects recorded.	N/A	N/A
260T	Ash	940	B1	11.3	399.8	15	8	6	9	9	Over Mature	Fair	Torn limb at 4m west.	Monitor annually for ash die back	3
261T	Pedunculate Oak	580	B1	7.0	152.2	9	4	4	3	4	Mature	Good	No significant defects recorded.	N/A	N/A
262T	Ash	840	B1	10.1	319.2	15	8	7	7	4	Over Mature	Fair	No significant defects recorded.	Monitor annually for ash die back	3
263G	Hawthorn	130	C3	1.6	7.6	5	N/A	N/A	N/A	N/A	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
264T	Pedunculate Oak	600	B1	7.2	162.9	8	3	4	2.5	4	Mature	Good	Squat from.	N/A	N/A
265T	Pedunculate Oak	830	A1	10.0	311.7	12	9	9	8	12	Over Mature	Good	Wide spreading canopy.	N/A	N/A
266T	Alder	850	A3	10.2	326.9	11	1.5	4	5	3	Over Mature	Fair	Stem cavity between ground level west and between 1.5m further opening between 2m to 3m north east. Decay between wound likely to coalesce. Meets Veteran classification	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information															
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
267T	Elder	100	C1	1.2	4.5	4	1	2	1.5	1.5	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
268T	Alder	640	B1	7.7	185.3	8	2	3	1.5	4	Mature	Fair	Stem cavity at 1.5 m south east.	N/A	N/A
269T	Goat Willow	450	U	5.4	91.6	5	1	4	10	2.5	Mature	Poor	Fallen goat willow.	N/A	N/A
270T	Pedunculate Oak	710	A1	8.5	228.1	13	6	6	7	7	Mature	Good	No significant defects recorded.	N/A	N/A
271T	Ash	1030	U	12.4	480.0	12	5	6	7	6	Mature	Poor	Massive cavity at base north, shell buckling 2m south, wood pecker holes between 6m and 9m south.	Reduce to a 4m Monolith to retain as an ecological receptor	2
272T	Ash	980	U	11.8	434.5	16	6	10	7	6	Over Mature	Fair	Basal decay at ground level west. Moderate deadwood throughout canopy.	Monitor annually for ash die back	3
273T	Pedunculate Oak	520	B1	6.2	122.3	10	2	2	7	4	Mature	Fair	Asymmetric canopy, suppressed.	N/A	N/A
274T	Pedunculate Oak	830	A1	10.0	311.7	12	8	7	8	6	Over Mature	Good	Crown raised to 8m north.	N/A	N/A
275T	Pedunculate Oak	640	B1	7.7	185.3	11	5	0.5	3	6	Over Mature	Good	Burrs on main stem , canopy heavily distorted, epicormic growth where crown raised to 8m.	N/A	N/A
276T	Pedunculate Oak	730	A1	8.8	241.1	12	6	7	9	6	Over Mature	Good	No significant defects recorded.	N/A	N/A
277G	Pedunculate Oak	550	A1	6.6	136.9	14	N/A	N/A	N/A	N/A	Mature	Good	Of wildlife value.	N/A	N/A
278T	Pedunculate Oak	670	C1	8.0	203.1	8	4	4	2	1	Mature	Poor	Basal decay, significant stage retrenchment, in decline.	N/A	N/A
279T	Pedunculate Oak	700	B1	8.4	221.7	12	4	4	4	3.5	Over Mature	Fair	Large diameter pruning wound on main stem up to 4m. Torn limb 4m south east	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information			Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code								
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m						Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)			
												N	E	S	W
280T	Pedunculate Oak	300	C1	3.6	40.7	5	1	2.5	1.5	1.5	Mature	Poor	Canopy development suppressed.	N/A	N/A
281T	Scots Pine	570	A1	6.8	147.0	16	5	2.5	4	5	Mature	Good	No significant defects recorded.	N/A	N/A
282T	Scots Pine	470	A1	5.6	99.9	15	1	2	4.5	2	Mature	Good	Torn limb at 3.5m and 4m south.	N/A	N/A
283T	Scots Pine	420	C1	5.0	79.8	8	1.5	3	3.5	1	Early-mature	Fair	Top torn and twisted.	N/A	N/A
284T	Pedunculate Oak	930	C1	11.2	391.3	14	2	6	8	7	Over Mature	Fair	Large stem cavity 0.5m north west. Moderate deadwood throughout canopy.	N/A	N/A
285T*	Pedunculate Oak	460	C1	5.5	95.7	9	2	8	6	7	Mature	Fair	Cavity at ground level west and 2.5m west. Supressed.	N/A	N/A
286T	Pedunculate Oak	530	B1	6.4	127.1	12	4	4	5	6	Mature	Good	No significant defects recorded.	N/A	N/A
287T	Pedunculate Oak	690	B1	8.3	215.4	13	6	7	5	5	Over Mature	Fair	Stem cavity at ground level west, buttress fluted, reaction growth, no obvious signs of retrenchment/physiological stress.	N/A	N/A
288G	Birch, Hazel, Holly & Hawthorn	100	C3	1.2	4.5	4	N/A	N/A	N/A	N/A	Semi-mature	Fair	Spans length of boundary.	N/A	N/A
289T	Pedunculate Oak	620	U	7.4	173.9	11	4	6	3.5	3	Mature	Poor	Large stem cavity.	N/A	N/A
290T	Pedunculate Oak	720	A1	8.6	234.5	12	4	5	4	5	Mature	Good	No significant defects recorded.	N/A	N/A
291T	Birch spp	450	C1	5.4	91.6	8	5	4	1	2	Mature	Fair	No significant defects recorded.	N/A	N/A
292T	Pedunculate Oak	480	B1	5.8	104.2	9	2	2.5	3	4	Mature	Fair	No significant defects recorded.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information			Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m					N	E	S	W					
293T	Wild Cherry	240	C1	2.9	26.1	5	1.5	3	2.5	1.5	Mature	Good	No significant defects recorded.	N/A	N/A
294T	Ash	480	C1	5.8	104.2	11	4	3	2.5	3.5	Mature	Fair	Torn limb 4m south west, historically has lost its top at 4m, remaining stems competing for apical dominance.	Monitor annually for ash die back	3
295T	Pedunculate Oak	540	A1	6.5	131.9	12	5	5	3.5	7	Over Mature	Fair	Minor deadwood throughout canopy typical of age and species.	N/A	N/A
296T	Birch spp	580	B1	7.0	152.2	12	4	7	6	5	Mature	Good	No significant defects recorded.	N/A	N/A
297T	Birch spp	180, 190	C1	3.1	31.0	11	2	4	2	2.5	Semi-mature	Good	Stem bifurcates at 0.3m.	N/A	N/A
298T	Pedunculate Oak	710	A1	8.5	228.1	15	7	7.5	7	7	Mature	Good	No significant defects recorded.	N/A	N/A
299T	Pedunculate Oak	460	C1	5.5	95.7	4	1.5	1.5	7.5	1.5	Mature	Poor	Supressed canopy, heavily distorted, bias south, poor shape and form.	N/A	N/A
300T	Pedunculate Oak	710	A1	8.5	228.1	14	7	5	9	7	Mature	Good	No significant defects recorded.	N/A	N/A
301T*	Birch spp	230, 200, 150, 150	C1	4.5	62.4	10	3	3	3	3	Mature	Fair	Multi-stemmed form.	N/A	N/A
302T	Pedunculate Oak	780	B1	9.4	275.3	14	7	4	9	7.5	Over Mature	Fair	Wound of upper surface of exposed roots from passing live-stock stock. Large tear out at 5m north.	N/A	N/A
303T	Pedunculate Oak	1210	A1	14.5	662.4	13	9	4.5	9	7.5	Over Mature	Good	Burrs on lower stem, significant girth and stature,	N/A	N/A
304T	Pedunculate Oak	790	U	9.5	282.4	12	5	6	7	4	Mature	Poor	Large stem cavity at 2m west, small opening 1m east.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Conditions			Tree Constraints Information								Largely Overcast				
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
305T*	Pedunculate Oak	750	A1	9.0	254.5	14	7	4.5	8	7	Mature	Good	No significant defects recorded.	N/A	N/A
306T	Hawthorn	200	C1	2.4	18.1	6	1.5	1.5	1.5	1.5	Mature	Fair	Dense holly obscures lower stem.	N/A	N/A
307G	Hawthorn, holly	200	C3	2.4	18.1	6	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species tree group.	N/A	N/A
308T	Pedunculate Oak	710	B1	8.5	228.1	10	6	9	8	9	Mature	Good	Squat form.	N/A	N/A
309T	Ash	700	U	8.4	221.7	13	8	6	8	8	Mature	Poor	Basal decay and canopy retrenchment noted	Reduced as 5m monolith to retain as a ecological receptor in the long terms	2
310T	Pedunculate Oak	540	B1	6.5	131.9	10	5	4.5	3.5	6.5	Mature	Good	No significant defects recorded.	N/A	N/A
311G	Alder	330	C3	4.0	49.3	13	N/A	N/A	N/A	N/A	Mature	Fair	Tall etiolated alder set to north of brook, many historically coppiced.	N/A	N/A
312G	Alder & Holly	300	C3	3.6	40.7	12	N/A	N/A	N/A	N/A	Semi-mature	Poor	Eastern section of group becomes shorter/smaller, sparse and lower vitality	N/A	N/A
313T	Pedunculate Oak	720	B1	8.6	234.5	8	4	4	4	4	Mature	Fair	Cubical brown rot at base, south, hollowing of stem is a natural part of aging process. Damage to upper side of primary roots south from livestock, stem bifurcates at 3.5m. Two stem cavities east below main union, large tear out wound at 5m south and north on southern stem. Good bud density/vitality.	N/A	N/A
314G	Hawthorn, Oak, Goat willow & Holly	150	C3	1.8	10.2	4	N/A	N/A	N/A	N/A	Semi-mature	Fair	Engulfed by bramble, defunct in parts.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
315T	Alder	310, 360	C1	5.7	102.1	8	2	1.5	2	2	Semi-mature	Fair	Stem bifurcates at ground level	N/A	N/A
316T	Pedunculate Oak	590	B1	7.1	157.5	13	6	6	6	6	Mature	Fair	Crown raised to 4m south, large pruning wound remain, some occlusion growth.	N/A	N/A
317T	Pedunculate Oak	810	A1	9.7	296.9	12	5.5	7	5	7	Mature	Good	Gateway to north, significant compaction noted. Large deadwood in central mid to upper canopy.	N/A	N/A
318H	Hawthorn & Holly	150	C1	1.8	10.2	4	N/A	N/A	N/A	N/A	Mature	Fair	Defunct in parts.	N/A	N/A
319T	Aspen	410	C1	4.9	76.1	9	7	6	5	6	Early-mature	Poor	Squat form.	N/A	N/A
320T	Pedunculate Oak	870	B1	10.4	342.5	12	5	6	6	7	Mature	Good	Large diameter deadwood within upper canopy south typical of age and species.	N/A	N/A
321T	Pedunculate Oak	830	A1	10.0	311.7	14	5.5	7	7	7	Over Mature	Good	Moderate diameter deadwood within lower diameter typical of age and species.	N/A	N/A
322T	Pedunculate Oak	570	B1	6.8	147.0	9	4	5.5	5.5	5	Mature	Good	No significant defects recorded.	N/A	N/A
323T	Pedunculate Oak	730	B1	8.8	241.1	13	5	6	6	9	Mature	Fair	Elongated limb extending from 3m west.	N/A	N/A
324T	Pedunculate Oak	440	C1	5.3	87.6	7	3	3.5	2	2.5	Mature	Fair	Early signs of retrenchment.	N/A	N/A
325T	Pedunculate Oak	810	A1	9.7	296.9	12	6	6	6	6	Mature	Good	No significant defects recorded.	N/A	N/A
326T	Birch spp	290	C1	3.5	38.1	6	2	1	1.5	2	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
327T	Pedunculate Oak	725	B1	8.7	237.8	7	4	4.5	4	4	Mature	Good	Squat form.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information															
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
328T	Pedunculate Oak	710	A1	8.5	228.1	14	4.5	7	8	8	Mature	Good	Occluded spiral wound between 1m east and 3.5m south.	N/A	N/A
329T	Pedunculate Oak	710	C1	8.5	228.1	5	3	3	3	3	Mature	Fair	Squat form, flush cuts on main stem west, used to fixed hinges of a gate	N/A	N/A
330G	Birch, Hawthorn, Oak & holly	280	C3	3.4	35.5	10	N/A	N/A	N/A	N/A	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
331T	Pedunculate Oak	570, 580	B1	9.8	299.2	11	7	7	8	8	Mature	Fair	No significant defects recorded.	N/A	N/A
332T	Pedunculate Oak	630	A1	7.6	179.6	12	5	5	5	5	Mature	Good	No significant defects recorded.	N/A	N/A
333G	Pedunculate Oak	400	B3	4.8	72.4	10	N/A	N/A	N/A	N/A	Early-mature	Fair	No significant defects recorded.	N/A	N/A
334T	Pedunculate Oak	780	A1	9.4	275.3	14	5	5	6	5	Mature	Good	Large deadwood at 3m east, torn blanch between 2m and 5m west.	N/A	N/A
335T	Pedunculate Oak	380	C1	4.6	65.3	10	2.5	4	3	3.5	Early-mature	Fair	Canopy development suppressed.	N/A	N/A
336T	Pedunculate Oak	310	C1	3.7	43.5	10	3	4.5	2	3	Semi-mature	Fair	Canopy development suppressed.	N/A	N/A
337T	Pedunculate Oak	800	A1	9.6	289.6	14	7	6.5	6	7	Mature	Good	No significant defects recorded.	N/A	N/A
338H	Holly & Blackthorn	75	C1	0.9	2.5	1.5	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species hedgerow.	N/A	N/A
339T	Goat Willow	75	U	0.9	2.5	4	0.5	1	1	1	Semi-mature	Poor	Self set, low vitality	N/A	N/A
340T	Birch spp	90	U	1.1	3.7	4	1	1	0.5	1	Young	Poor	Self set.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
341T	Pedunculate Oak	650	B1	7.8	191.2	10	2.5	4	6	7	Mature	Fair	Torn limb 5m north west.	N/A	N/A
342T	Pedunculate Oak	460	B1	5.5	95.7	8	3.5	4	4	4	Semi-mature	Fair	Stem wound 1m west where fencing wire has been hammered in.	N/A	N/A
343T	Hawthorn	110	C1	1.3	5.5	3.5	1	1	1	1	Young	Fair	Self set.	N/A	N/A
344T	Hawthorn	75	C1	0.9	2.5	1.5	0.5	0.5	0.5	0.5	Semi-mature	Fair	Self set.	N/A	N/A
345T	Hawthorn	90	C1	1.1	3.7	3	1	1	1	1	Young	Fair	Self set.	N/A	N/A
346T	Pedunculate Oak	1100	B1	13.2	547.5	10	4	4	4.5	6	Mature	Fair	Large diameter branch stub at 3m north	N/A	N/A
347H	Blackthorn	75	B3	0.9	2.5	1	N/A	N/A	N/A	N/A	Semi-mature	Fair	Of wildlife value	N/A	N/A
348T	Pedunculate Oak	820	B1	9.8	304.2	8	5	4	5	6	Mature	Fair	Ivy on stem, extends into canopy.	N/A	N/A
349T	Pedunculate Oak	910	A1	10.9	374.7	10	5	5	6	6	Over Mature	Good	No significant defects recorded.	N/A	N/A
350T	Pedunculate Oak	930	A1	11.2	391.3	13	7	7	6	7	Mature	Good	Stem divides above 1.5m from tight union,	N/A	N/A
351T	Aspen	450	B1	5.4	91.6	12	5	4	4	4	Semi-mature	Poor	No significant defects recorded.	N/A	N/A
352T	Pedunculate Oak	730	C1	8.8	241.1	8.5	5	6.5	5	5	Mature	Poor	Large stem cavity at 4m.	N/A	N/A
353T	Hawthorn	100	C1	1.2	4.5	4	1	1	1	1	Mature	Good	Self set, bark damage from browsing livestock.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Largely Overcast			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
354T	Pedunculate Oak	540	B1	6.5	131.9	7	4	4	4	4	Mature	Good	Squat form.	N/A	N/A
355G	Alder	200	C3	2.4	18.1	6	N/A	N/A	N/A	N/A	Semi-mature	Good	No significant defects recorded.	N/A	N/A
356T	Pedunculate Oak	670	C1	8.0	203.1	12	2	4	4	3.5	Mature	Fair	Large stem cavity at 5m north east.	N/A	N/A
357G	Pedunculate Oak	640	A1	7.7	185.3	12	N/A	N/A	N/A	N/A	Mature	Good	No significant defects recorded. Forms linear group.	N/A	N/A
358T	Ash	350	C1	4.2	55.4	12	3	3	3	3	Early-mature	Fair	Tall, etiolated growth form, prolific ivy obscures main stem, poor lateral development of canopy.	Monitor annually for ash die back	3
359H	Hawthorn, Blackthorn, & Hazel	75	B3	0.9	2.5	1	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species hedgerow	N/A	N/A
360T	Pedunculate Oak	530	B1	6.4	127.1	12	4	4	4	4	Mature	Good	Grown raised to6m north.	N/A	N/A
361T	Pedunculate Oak	680	B1	8.2	209.2	12	5	6	5	5	Over Mature	Fair	Crown raised to 5m north, branch stub remain	N/A	N/A
362T	Pedunculate Oak	480	B1	5.8	104.2	7	2	4	3.5	3.5	Mature	Fair	Crown raised to 4m north branch stubs remain	N/A	N/A
363T	Pedunculate Oak	610	B1	7.3	168.4	7	2.5	3	4	4	Mature	Fair	Crown raised to 5m north branch stub remain	N/A	N/A
364G	Pedunculate Oak	675	B3	8.1	206.1	12	N/A	N/A	N/A	N/A	Mature	Good	Linear tree group, crown raised to 7m north	N/A	N/A
365T	Pedunculate Oak	670	C1	8.0	203.1	10	2	4	4.5	4.5	Mature	Fair	Stem divides above 1.5m large cavity entrances on both stems at 2m north. Good ecological asset. Crown raised to 6m . Asymmetrical canopy .	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1, 2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
366G	Hawthorn & Elder	150	C1	1.8	10.2	4.5	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species tree group.	N/A	N/A
367T	Pedunculate Oak	460	C1	5.5	95.7	7	4	4	4	4	Mature	Fair	Stem cavity opening from ground level to 1m east, squat shape and form	N/A	N/A
368T	Pedunculate Oak	530	B1	6.4	127.1	13	6	4	6	6	Mature	Good	Compaction by livestock.	N/A	N/A
369T	Pedunculate Oak	610	B1	7.3	168.4	13	6	6	6	6	Mature	Good	Torn branch at 6m east.	N/A	N/A
370G	Hazel	75	C3	0.9	2.5	4.5	N/A	N/A	N/A	N/A	Semi-mature	Good	Self set.	N/A	N/A
371T	Pedunculate Oak	540	B1	6.5	131.9	12	7	5	5	5	Mature	Fair	No significant defects recorded.	N/A	N/A
372T	Pedunculate Oak	750	B1	9.0	254.5	13	7	7	5	5.5	Over Mature	Fair	Partially occluded crack between 5m and 6.5m north. Tear out wound 7m south west. Large diameter deadwood at 5m south.	N/A	N/A
373T	Pedunculate Oak	470	C1	5.6	99.9	8	2	3	3.5	2.5	Mature	Fair	Canopy development suppressed by larger oak to the north.	N/A	N/A
374G*	Hawthorn	100	C3	1.2	4.5	5	N/A	N/A	N/A	N/A	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
375T	Pedunculate Oak	670	A1	8.0	203.1	14	5	5	4.5	5	Mature	Good	No significant defects recorded.	N/A	N/A
376T	Pedunculate Oak	640	A1	7.7	185.3	14	5	6	5.5	6	Mature	Good	No significant defects recorded.	N/A	N/A
377T	Pedunculate Oak	670	B1	8.0	203.1	11	1	4.5	6	6	Mature	Poor	Has lost companion shelter to north	N/A	N/A
378G	Rowan, Hawthorn & Birch	230	C3	2.8	23.9	9	N/A	N/A	N/A	N/A	Semi-mature	Fair	Tall etiolated growth forms.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information			Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m					N	E	S	W					
379T	Pedunculate Oak	400	B1	4.8	72.4	7	5	6	4.5	5	Early-mature	Fair	No significant defects recorded.	N/A	N/A
380H	Blackthorn, Holly & Hawthorn	75	C1	0.9	2.5	1	N/A	N/A	N/A	N/A	Semi-mature	Fair	Gappy in parts.	N/A	N/A
381G	Alder	420	C3	5.0	79.8	11	N/A	N/A	N/A	N/A	Early-mature	Fair	Several members have stem wounds torn limbs from historic storm damage.	N/A	N/A
382T	Pedunculate Oak	810	A1	9.7	296.9	15	4	4.5	7.5	4	Mature	Good	No significant defects recorded.	N/A	N/A
383T	Ash	400	B1	4.8	72.4	14	3.5	3	3	3	Early-mature	Good	Good bud density/vitality at present.	Monitor annually for ash die back	3
384T	Pedunculate Oak	840	A1	10.1	319.2	15	3.5	4	5	6	Mature	Good	No significant defects recorded.	N/A	N/A
385T	Ash	460	C1	5.5	95.7	12	3	3.5	4	5	Mature	Fair	Stem cavity at 0.5m south, extend beyond 30cm over cross section of stem bottle butt indicates reaction growth to perceived weakness.	Monitor annually for ash die back	3
386H	Blackthorn	75	C1	0.9	2.5	1	N/A	N/A	N/A	N/A	Semi-mature	Fair	Gappy in parts.	N/A	N/A
387G	Birch & Oak	300 #	B3	3.6	40.7	12	N/A	N/A	N/A	N/A	Semi-mature	Good	Off-site tree group, dimensions estimated.	N/A	N/A
388T	Pedunculate Oak	820	A1	9.8	304.2	14	7	5	5	6	Mature	Good	No significant defects recorded.	N/A	N/A
389T	Pedunculate Oak	550	C1	6.6	136.9	10	2.5	6	5.5	4	Mature	Fair	Stem cavity opening at 1m south west. Cavity extends beyond 25cm of the cross section of the stem. Bulging of stem at this point indicates reaction growth a response to perceived weakness.	N/A	N/A
390G	Alder	700	B3	8.4	221.7	12	N/A	N/A	N/A	N/A	Mature	Fair	Large for species, set in margins of brook, liable to flood on occasion, some members display	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
													signs of stem decay symptomatic with age class and species.		
391T	Alder	570, 710	B3	10.9	375.0	12	4.5	5	7	1.5	Over Mature	Fair	Large stem cavity, aerial roots historic stem failure, meets veteran classification as a "survivor" .	N/A	N/A
392T	Alder	720	B3	8.6	234.5	12	4	1	3.5	4.5	Mature	Fair	Large stem cavity, historic stem failure, aerial roots, meets veteran classification as a "survivor" .	Consider managing as a pollard to retain in long term, see ATF guidance to prolong longevity.	3
393T	Hawthorn	150	C1	1.8	10.2	4.5	2	2	2	2	Mature	Fair	No significant defects recorded.	N/A	N/A
394T*	Hawthorn	150	C1	1.8	10.2	4	1.5	1.5	1.5	1.5	Semi-mature	Good	No significant defects recorded.	N/A	N/A
395T	Ash	750	B1	9.0	254.5	15	7	5.5	8	7	Mature	Fair	Minor deadwood in extremities reasonable bud density.	Monitor annually for ash die back	3
396T	Pedunculate Oak	680	B1	8.2	209.2	8	7.5	6.5	8	4	Over Mature	Good	Squat form.	N/A	N/A
397T	Ash	220, 250, 325	C1	5.6	98.0	11	2	1.5	4	4	Mature	Fair	Multi-stemmed, etiolated shoots through scaffold limbs typical response to physiological stress.	N/A	N/A
398T	Ash	770	B1	9.2	268.3	15	6	6	8	7	Mature	Fair	Reasonable physiological condition/bud density at present.	Monitor annually for ash die back	3
399T	Pedunculate Oak	1050	A1	12.6	498.8	12	4.5	4	7	7	Over Mature	Good	Fluted stem, broad canopy.	N/A	N/A
400T	Pedunculate Oak	780	C1	9.4	275.3	13	5	4.5	7	7.5	Mature	Fair	Large stem cavity at 1.8m south east with cubical brown rot. Elongated limb 2m west with tear out wound 2.5m south.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Conditions			Largely Overcast			Tree Constraints Information									
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
401T	Pedunculate Oak	950	A1	11.4	408.3	14	8	11	9.5	7	Over Mature	Fair	Large pruning wound 2m south west, many years of incremental growth attempting to occlude.	N/A	N/A
402G	Pedunculate Oak	790	A1	9.5	282.4	13	N/A	N/A	N/A	N/A	Mature	Fair	Minor dead wood and torn limbs to be expected of items within this age class. All members have good vitality.	N/A	N/A
403G	Birch, holly hawthorn	150	C3	1.8	10.2	5	N/A	N/A	N/A	N/A	Semi-mature	Fair	Self set contains dead sections.	N/A	N/A
404T	Pedunculate Oak	390	B1	4.7	68.8	8	1.2	1.5	2.5	2.5	Early-mature	Fair	No significant defects recorded.	N/A	N/A
405T	Pedunculate Oak	670	U	8.0	203.1	9	4	3	2	6	Mature	Fair	Large stem cavity between ground level and 4m south east.	N/A	N/A
406T	Pedunculate Oak	870	A1	10.4	342.5	14	8	7	6	8	Over Mature	Good	No significant defects recorded.	N/A	N/A
407T	Pedunculate Oak	920	B1	11.0	383.0	13	3.5	6	3.5	5.5	Mature	Fair	Bifurcates above 1.5m minor dead typical of age and species.	N/A	N/A
408T	Pedunculate Oak	600	B1	7.2	162.9	12	0.5	3	6	3	Over Mature	Fair	Canopy has a strong bias south, extends over pond.	N/A	N/A
409G	Hawthorn	150	C3	1.8	10.2	4	N/A	N/A	N/A	N/A	Semi-mature	Fair	Denotes perimeter of the pond.	N/A	N/A
410T	Pedunculate Oak	550	B1	6.6	136.9	12	5	3.5	3.5	5	Mature	Good	No significant defects recorded.	N/A	N/A
411T	Pedunculate Oak	840	B1	10.1	319.2	11	8	8	10	6	Over Mature	Good	Minor to moderate deadwood throughout canopy.	N/A	N/A
412T	Pedunculate Oak	970	B1	11.6	425.7	10	3	6	5	6	Over Mature	Good	Multi-stemmed at 2m. A historic coppice.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information			Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m					N	E	S	W					
413T	Pedunculate Oak	1020	A1	12.2	470.7	13	8	8	8	8	Mature	Good	Large limbs removed at 2m north west and west. Wide spreading form, good branching structure.	N/A	N/A
414G	Holly & Blackthorn	150	C3	1.8	10.2	4	N/A	N/A	N/A	N/A	Semi-mature	Fair	Self set extends south into next field boundary.	N/A	N/A
415T	Pedunculate Oak	370	B1	4.4	61.9	7	3	3.5	3.5	3	Early-mature	Good	Good potential to develop further.	N/A	N/A
416T	Pedunculate Oak	500	C1	6.0	113.1	7	4	3	1	3	Mature	Fair	Canopy development suppressed.	N/A	N/A
417T	Pedunculate Oak	820	B1	9.8	304.2	9	6	5	4	6	Mature	Fair	Undergrowth obscures lower stem .	N/A	N/A
418T	Sycamore	200	C1	2.4	18.1	6.5	1	4	5	4.5	Semi-mature	Fair	Canopy development suppressed.	N/A	N/A
419T	Pedunculate Oak	800	B1	9.6	289.6	8	5	5	5	5	Over Mature	Fair	Early signs of retrenchment as it reaches late mature age class. A natural part of aging.	N/A	N/A
420G	Birch, Hawthorn Ash & Oak	300	C3	3.6	40.7	10	N/A	N/A	N/A	N/A	Early-mature	Fair	Forms a sections of eastern field boundary.	N/A	N/A
421T	Ash	520	U	6.2	122.3	16	4	4	2	9	Mature	Poor	Elongated limb at 3m west, highly likely to tear out in future years. Several torn limbs between 3m and 7m north, canopy sparse, bud have gone into to flush early for the species	Monitor annually for ash die back	3
422T	Sycamore	590, 500	B1	9.3	270.6	12	6	7	7	7	Mature	Fair	Stem bifurcates at 0.3m.	N/A	N/A
423T	Pedunculate Oak	900	B1	10.8	366.5	11	4	4.5	4.5	4.5	Over Mature	Fair	No significant defects recorded.	N/A	N/A
424T	Sycamore	590	B1	7.1	157.5	12	4	2.5	7	6	Mature	Fair	Asymmetric canopy.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information															
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
425T	Pedunculate Oak	630	C1	7.6	179.6	9	4	4	4	4	Mature	Fair	Set on side of brook.	N/A	N/A
426T	Pedunculate Oak	450	B1	5.4	91.6	10	5	4	5	4	Semi-mature	Fair	Set on side of brook .	N/A	N/A
427T	Pedunculate Oak	410	U	4.9	76.1	8	5	2	3	7	Early-mature	Poor	North eastern stem has failed leaving large wound and loss of this aspect of the canopy.	N/A	N/A
428T	Sycamore	390	B1	4.7	68.8	10	4	4	1.5	4	Early-mature	Fair	No significant defects recorded.	N/A	N/A
429G	Birch, Sycamore, Oak & Hawthorn	300	C3	3.6	40.7	10	N/A	N/A	N/A	N/A	Early-mature	Fair	Birch form the dominant component of this group.	N/A	N/A
430T	Pedunculate Oak	500	B1	6.0	113.1	12	5	5	5	4	Mature	Fair	No significant defects recorded.	N/A	N/A
431T	Pedunculate Oak	600	B1	7.2	162.9	12	5	5	5	5	Mature	Fair	Pruning wound 1m north east, minor deadwood throughout upper canopy.	N/A	N/A
432T	Crack Willow	500	U	6.0	113.1	7	3	6	2	6	Mature	Poor	Main stem split at 1.5m.	pollard at point of failure to retain in lesser form	3
433T	Pedunculate Oak	760	B1	9.1	261.3	8	5	4	4	4	Mature	Fair	Squat form.	N/A	N/A
434H	Hawthorn	75	C1	0.9	2.5	1	N/A	N/A	N/A	N/A	Young	Fair	Defunct hedgerow contains frequent sections of gorse.	N/A	N/A
435G	Pedunculate Oak	425	B3	5.1	81.7	8	N/A	N/A	N/A	N/A	Mature	Fair	Linear group of oak, squat form.	N/A	N/A
436T	Pedunculate Oak	610	B1	7.3	168.4	10	4	4	5	4	Mature	Fair	Marginally larger than other members in 435G.	N/A	N/A
437T	Pedunculate Oak	590	B1	7.1	157.5	8	4	4	4	4	Mature	Fair	Marginally larger than other members in 435G, stem cavity at 3m north east.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information			Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m					N	E	S	W					
438T	Pedunculate Oak	680	A3	8.2	209.2	13	4.5	5	4.5	5	Over Mature	Good	Provides shelter to owl box on neighbouring oak to south.	N/A	N/A
439T	Pedunculate Oak	500	B1	6.0	113.1	8	3	3	4	3	Mature	Good	No significant defects recorded.	N/A	N/A
440T	Pedunculate Oak	520	B1	6.2	122.3	8	4	5	4	2.5	Mature	Fair	No significant defects recorded.	N/A	N/A
441T	Pedunculate Oak	640	A1	7.7	185.3	13	6	6	7	4	Mature	Good	Minor deadwood and torn branch's typical of age	N/A	N/A
442G	Hawthorn & Holly	150	C3	1.8	10.2	4	N/A	N/A	N/A	N/A	Semi-mature	Fair	Self set.	N/A	N/A
443T	Pedunculate Oak	860	B1	10.3	334.6	14	7	7	7	7	Over Mature	Fair	Stem leans west, pruning wound 1.5m east, remnants of desiccated fruiting bracket within wound, limbs crown raised to 6m east, branch stubs remain.	Identify fruiting body within autumn	3
444T	Birch spp	310	U	3.7	43.5	7	1	1	2	1	Early-mature	Poor	Central leader dead.	N/A	N/A
445T	Pedunculate Oak	790	A1	9.5	282.4	16	7	8	8	7	Mature	Good	No significant defects recorded.	N/A	N/A
446T	Pedunculate Oak	590	B1	7.1	157.5	9	6	6	6	6	Mature	Good	Squat form.	N/A	N/A
447T	Pedunculate Oak	530	B1	6.4	127.1	8	6	6	4	4	Mature	Fair	No significant defects recorded.	N/A	N/A
448T	Pedunculate Oak	690	B1	8.3	215.4	12	5.5	6	6	6	Mature	Good	No significant defects recorded.	N/A	N/A
449T	Pedunculate Oak	200	C1	2.4	18.1	6	2.5	1.5	2.5	1.5	Young	Fair	No significant defects recorded.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm Ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

Tree Constraints Information															
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
450T	Pedunculate Oak	580	B1	7.0	152.2	9	7	5	7	6	Mature	Fair	No significant defects recorded.	N/A	N/A
451T	Pedunculate Oak	560	B1	6.7	141.9	8	6	6	5	3	Mature	Fair	No significant defects recorded.	N/A	N/A
452T	Birch spp	180	C1	2.2	14.7	5	0.5	1	1	1	Semi-mature	Fair	No significant defects recorded.	N/A	N/A
453H	Hawthorn & Holly	100	C3	1.2	4.5	1.5 to 3	N/A	N/A	N/A	N/A	Semi-mature	Poor	Height varies from 1.5m to 3m, defunct in parts.	N/A	N/A
454H	Blackthorn, Hazel, Elder & Holly	75	B1	0.9	2.5	1	N/A	N/A	N/A	N/A	Semi-mature	Fair	Mixed species hedgerow.	N/A	N/A
455T	Pedunculate Oak	390	C1	4.7	68.8	5	4	3.5	3.5	4	Early-mature	Fair	Squat form, large diameter deadwood at 2m .	N/A	N/A
456T	Pedunculate Oak	480	B1	5.8	104.2	8.5	4	4	4	4	Mature	Fair	Good potential for future growth.	N/A	N/A
457T	Pedunculate Oak	520	B1	6.2	122.3	7	5	5	6	5	Mature	Good	Good potential for future growth.	N/A	N/A
458T	Pedunculate Oak	630	B1	7.6	179.6	8	6.5	5	5	5	Mature	Good	No significant defects recorded.	N/A	N/A
459T	Pedunculate Oak	350	B1	4.2	55.4	7	2	2.5	2	2	Early-mature	Good	No significant defects recorded.	N/A	N/A
460H	Holly, Oak, Goat willow & Hawthorn	100	C3	1.2	4.5	3	N/A	N/A	N/A	N/A	Semi-mature	Fair	Unmanaged hedgerow, defunct in parts.	N/A	N/A
461T	Pedunculate Oak	425	B1	5.1	81.7	7	5	5	4	4.5	Semi-mature	Good	No significant defects recorded.	N/A	N/A
462T	Pedunculate Oak	360	C1	4.3	58.6	5	3	6	3	5.5	Early-mature	Fair	No significant defects recorded.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6 and Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic conditions Largely overcast

			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
463T	Pedunculate Oak	800	A1	9.6	289.6	11	7	7	7	7	Mature	Good	Good shape and form.	N/A	N/A
464T	Pedunculate Oak	610	B1	7.3	168.4	6	4.5	5	5	5	Mature	Good	Squat form, ivy extends into canopy.	N/A	N/A
465T	Ash	730	B1	8.8	241.1	17	4	5	7	4.5	Mature	Fair	Stem devices at 5m. Dead limb/branch stub 5.5m north and south.	Monitor annually for ash die back	3
466T*	Alder	640	C1	7.7	185.3	7	4	1.5	4	1.5	Mature	Fair	Stem cavity 1.5m next to stem bifurcation, northern stem historical failed at 2m. Canopy development suppressed.	N/A	N/A
467T	Alder	570	C1	6.8	147.0	14	3	2.5	3	6	Mature	Fair	Large stem cavity between 0.75m to 1.75m north.	N/A	N/A
468T	Ash	840	C1	10.1	319.2	14	3	6	5	5	Mature	Fair	Stem bifurcates above 1.5m dividing from tight included union, reduced by 1.5m to alleviate loading . Minor deadwood throughout canopy.	Reduced canopy by 1.5m to alleviate loading on included union Monitor annually for ash die back	2 3
469T	Alder	530, 550	C1	9.2	263.9	9	3	4	6	4.5	Mature	Fair	Large stem cavity on southern stem from 0.25m to 1.8m decay extends upwards	N/A	N/A
470T	Alder	550	B1	6.6	136.9	11	4.5	5	4.5	3	Mature	Good	No significant defects recorded.	N/A	N/A
471T	Alder	590	B1	7.1	157.5	11	3.5	2	5	3	Mature	Good	No significant defects recorded.	N/A	N/A
472G	Alder, Birch, Oak Holly & Hazel	490	B3	5.9	108.6	12	N/A	N/A	N/A	N/A	Mature	Fair	Mixed species tree group.	N/A	N/A
473T	Pedunculate Oak	650	B1	7.8	191.2	8	5	4	5	4.5	Mature	Good	Branch weld/fused at 3m within central canopy	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm

Site New Buildings Solar Farm
 Client New Buildings Solar farm ltd
 Surveyor D.Williams
 Survey date 28/02/2023 – 24/03/2023
 Climatic
 conditions Largely overcast

			Tree Constraints Information												
Tree Reference No.	Species	Stem Diameter (mm) at 1.5m	Category Grade	Radius of RPA (m)	Area of RPA (m2)	Height (m)	Canopy Spread (m)				Life Stage	Physiological Condition	Structural Condition	Recommendations	Priority Code
							N	E	S	W					
474G	Birch, Holly & Hawthorn	200	C3	2.4	18.1	10	N/A	N/A	N/A	N/A	Semi-mature	Fair	Self set tree group, partly consequential of succession from adjacent woodland.	N/A	N/A

- The tree survey process has been undertaken in accordance with [Section 4.4 of BS5837:2012 Trees in Relation to Design, Demolition and Construction Recommendations](#), summarised in [Appendix 1](#) of the Arboricultural Appraisal.
- Each item surveyed has been given a sequential number with the respective suffix 'T' for trees 'G' for groups of trees, 'H' for hedgerows and 'W' for woodland which corresponds to the Tree Constraints Plan ([Plan 1](#)) and Tree Protection Plan ([Plan 2](#)).
- The Root Protection Area (RPA) values have been calculated using the methodology set out in [Section 4.6](#) and [Annexes C & D of BS5837:2012](#). Where pre-existing site conditions may indicate that the rooting system is not asymmetric, the RPAs may be modified in [Plan 1](#) and [Plan 2](#) but the area not reduced based on arboricultural reasoning. Such instances include the physical obstruction to root development or inhospitable rooting environments.
- Where trees are located outside of the client land ownership, or access is not achievable stem diameter have been estimated, highlighted using the suffix #. Those trees plotted by hand are identified with the suffix * after their identification number.
- Category Grading afforded to each item surveyed provides a hierarchy system for retention based on condition, amenity value and longevity in accordance with [Table 1 Cascade Chart for Tree Quality Assessment described in BS5837:2012](#). **A** = High value, **B** = Moderate value **C** = low value & **U** compromised condition. Suffix 1,2 & 3 related to Arboricultural, Landscape and Conservation value respectively.
- Priority codes provide a classification of the urgency of works; Code 1 = Undertake within one month of the survey date, Code 2 = Perform within 6 months of the survey date, Code 3 = Complete works within one year.
- Where specified small diameter limbs/deadwood refer to a diameter <75mm, moderate deadwood/medium diameter limb equates to that of 75mm – 150mm and large diameter limbs/deadwood are those that exceed a diameter of 150mm