

Tree Planting Operations:
Trees shall be planted into tree pits and well staked with 2no stakes and a single cross bar set 600 above gl. Base of tree pits shall be broken up to 300 before planting. Prior to backfilling, the soil shall be finely broken down and 200g of slow release fertilizer such as 'Vitax' incorporated into the backfill with tree planting compost (50% by vol)
Puddle the backfilled tree pit with a 1:99 solution 'Algimure' to ensure the tree pit is well watered

extg hedges to north, east and west
boundaries to be retained



LANDSCAPING KEY

- new drystone boundary wall to match extg
- av 700h stone retaining wall incorporating planting bed
- 1500h timber post and rail fence
- new screen planting to include mix of hazel, holly, photinia and forsythia
- grass
- paving
- gravel/hoggin
- Silver birch tree (*Betula pendula*); standard (see planting specification above)



Revisions			
A	Birch trees added	18.05.26	
B	Drawing size and scale rev	28.05.26	

Job

Meadow Place Farm, Ipstones

Proposed New Dwelling

Title

Landscape Plan

Date

08.04.26

Scale

1/100 @ A2

Dwg. No.

M/PF-12

Rev.

B

Ian Ankers architects
Building and Design Consultants
Ryecroft Farm, Rushon Spencer, Macclesfield, SK11 0RP
t 01250 546944
e ian@ianankers.co.uk
w www.ianankers.co.uk