

Mr. Ronald Dale
277 Congleton Road
Biddulph
Staffordshire
ST8 7SE

Direct Line :(01785) 276700
Facsimile :(01785) 276712
E-mail: john.dixon@staffordshire.gov.uk
Please ask for John Dixon

My Ref
HoSS//mrh/jd/CDB0236/B1743

Your Ref

Date
20th October 2010

Dear Mr. Dale,

BAILEYS WOOD BRIDGE REPLACEMENT SCHEME – A527 CONGLETON ROAD

Further to our recent conversation I am writing to confirm that the current works adjoining your property will increase the flow capacity of the culvert under the A527 Congleton Road by approximately 96%.

I can confirm that the Environment Agency has given consent for these works and the calculations regarding the percentage increase flow capacity of the culvert are based on CIRIA C689, (2010), Culvert design and operation guide.

Staffordshire County Council has been made aware that there is a history of the Baileys Wood Bridge / culvert overflowing onto the road and draining through your property. It is hoped that the current works will either eliminate or greatly alleviate any future flooding of your land.

On behalf of the council I would like to thank you for your continued support and forbearance with regard to the ongoing construction works adjacent to your home.

Should you require any further clarification on this matter please do not hesitate to contact me on the e-mail address or telephone number above.

Yours Sincerely



John Dixon
Project Engineer (Bridges)

