The copyright of this drawing and design is vested in the Architect and must not be copied or reproduced without written consent. All dimensions given are to be verified on site by the contractor. This drawing must not be scaled.

SCHEDULE OF PLANTS

Nr	
50	Bergenia cordifolia purpurea 2litre c.g
14	Brachyglotis Sunshine 2 litre 45-60 c.g
10	Ceonothus thyrsiflorus repens 2 litre 450 spread c.g
16	Choisya Aztec Pearl 3 litre 45-60 c.g
9	Cistus Silver Pink 3 litre 45-60 c.g
21	Cornus Kelsyi 2 litre 30-45 c.g
42	Cotoneaster Gnom 2 litre 300 spread
19	Eleagnus Limelight 3 litre 45-60 c.g
13	Escallonia Red Dream 2 ltre 25-30 c.g.
14	Euonymus Silver Queen 2 litre 15-20 c.g
28	Geranium Johnsons Blue 2 litre
12	Geranium endressii 2 litre
24	Hebe albicans 2 litre 20-30 c.g
5	Hebe Autumn Glory 2 litre 25-30 c.g
13	Hebe White Gem 2 litre 20-30 c.g
3	Hedera colchica Sulphur Heart 2 litre caned
117	Hedera Glacier 2 litre 30 spread c.g
60	Hedera Green Ripple 2 litre 30 spread
13	Hypericum x moserianum 2 litre 30-45 c.g
21	Lavendula Munstead 2 litre 15-20 c.g
19	Lonicera Loughall Evergreen 2 litre 30-45 c.g.
10	Mahonia Apollo 3 litre 30-45 c.g
15	Osmanthus x burkwoodii 3 litre 30-45 c.g.
33	Pachysandra terminalis 2 litre 10-15 c.g
5	Potentilla Abbotswood 2 litre 30-45
13	Potentilla Tangerine 2 lire 20-30 c.g
79	Prunus lusitanica 2 litre 30-40 c.g
9	Salvia purpurea 2 litre 20-30 c.g
17	Spiraea Firelight 2 litre 20-30 c.g
17	Stachys lanata 2 litre 10-15 c.g
128	Symphoricarpos chenaultii Hancock 2 litre 450 spread.
22	Viburnum davidii 3 litre 30-45 c.g

NOTES
TOPSOIL To BS 3882:2007
LAWNS Rotovate aras to 150mm deep lay 150mm topsoil and roll to a firm condition before laying cultivated meadow turf in staggered pattern.
TREES to be to BS 3936 Part 1. Tree pits to be 700 diam. and 600 deep with base and sides broken up 150mm Plant trees with 75mm diam. tree stake twice tied with adjustable ties nailed to stake. Backfill with topsoil enriched with 40 litres Tree Planting Compost each pit.
SHRUBS to BS 3936 Part 1 Shrub beds to be 450mmm deep with sides and base broken up to 150mm. Lay 400mm topsoil enriched with Tree Planting Compost at the rate of 50mm a square metre. All shrubs to be with minimum three branches. Remove containers and free roots before planting in a randon pattern.
BARK MULCH Spread 50mm composted bark mulch 5mm-20mm size to all tree pits and shrub beds except under area planted with Ivies.
GRAVEL 6mm diam natural gravel 50mm deep laid on permeable geotextile membrane.
Shrub beds adjacent to house frontage to have 600mm wide gravel strip for window access.

FOR TREE SCHEDULE
SEE DRAWING 105-14-01

existing trees on adjacent site

existing tree on adjacent site.

Rev	Details	Alt.	Date/Chk
A	Plots 13 and 14 Handed	-	02.10.14

CLIENT
The Wrekin Housing Trust

PROJECT
Proposed Residential Development
Land Off Bank Street
Cheadle ST 10 1NR

DRAWING
Planting Plan

SCALE 1:100 @A0 | DATE June 2014

DRAWING NUMBER 105-14-02 | REVISION A | DRAWN BY BE

brian evans landscape design studio ltd
smithy cottage bickford penkridge
stafford st19 5qj tel 01785 715917